



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N°: HSO-SBT-PL-013  
 Iss/Rev : 2.3  
 DATE : 26/01/2004  
 PAGE : I

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

***SPIRE & PACS Sorption Coolers***  
***AIV PLAN***

SBT internal ref : SBT/CT/2001-25

	Name & Function	Date	Signature
<b>Prepared</b>	L. Duband - Cooler project manager		
<b>SBT PA Check</b>	M. Dubois – Cooler PA manager	<b>29/06/04</b>	<b>APPROVED</b> by default
<b>SPIRE Approval</b>			
<b>PACS Approval</b>			
<b>PA Approval</b>			
<b>Project Approval</b>	J.L Augueres - SAp HSO project manager	<b>29/06/04</b>	<b>APPROVED</b> by default
<b>Project Approval</b>	L. Duband - Cooler project manager		

Service des Basses Températures (SBT)  
 Département de Recherche Fondamentale sur la Matière Condensée (DRFMC)  
 COMMISSARIAT A L'ENERGIE ATOMIQUE - GRENOBLE (CEA-Grenoble)  
 17, rue des Martyrs 38054 GRENOBLE Cédex 9, France.



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N°: HSO-SBT-PL-013  
 Iss/Rev : 2.3  
 DATE : 26/01/2004  
 PAGE : II

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

**Document Status**

Issue	Revision	Date	Nb of pages	Modifications
0	0	26/04/2001	-	First draft
0	1	13/09/2001		Baking and V test tasks switched. Verification matrix improved
0	2	17/09/2001		HS070 and HS080 switched. CO220 modified
0	3	18/10/2001		Laser marking task added (MA020) Assembling tasks reviewed
1	0	29/10/2001		Gold plating task performed on parts before assembly : new task MA030 added. Gold plating tasks for cooler heart and switch suppressed. Tasks re-numbered
1	1	20/11/2001	64	§ 1, 4.2. Tasks MA010, CO010, CO080, CO090, CO110, CO250, CO280, CO290, CO310, CO330, CO350, CO360, ST010, HS050. Task MA030 suppressed : transfered into two new tasks CO095 and HS 065. Verification matrix updated.
2	0	17/09/2003		AIV updated after CQM qualification and delivery. Tasks rearranged in accordance with as run plan
2	1	25/11/2003		Updated after FM Fab phase review Board comment (see H-P-ASP-RP-3846 v 1.1)
2	2	20/01/2004		Task ST030 added, C0060, 070 and 080 rearranged. Flow chart updated.
2	3	26/01/2004		“After” manufacturing tasks rearranged (cleaning task added after laser marking). Minor corrections



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N°: HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : III

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

**Table of Contents**

1	Scope of the document .....	1
2	Documents .....	2
2.1	Applicable documents .....	2
3	Verification matrix .....	3
4	Tests sequence .....	5
4.1	Organization and Methods .....	5
4.2	Test program .....	6
4.2.1	MAIV Flow chart .....	8
4.2.1.1	Symbols explanation .....	8
4.2.1.2	Flow chart .....	9
4.2.2	Manufacturing .....	14
4.2.3	Cooler "heart" / Cooler fully assembled .....	17
4.2.4	Structure .....	50
4.2.5	Heat Switches .....	53
5	Appendix .....	64
5.1	Health Check Report data sheet .....	64



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N°: HSO-SBT-PL-013  
 Iss/Rev : 2.3  
 DATE : 26/01/2004  
 PAGE : IV

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

*List of Acronyms*

AD	Applicable Document		
CEA	Commissariat à l' Energie Atomique		
CDR	Critical Design Review	Revue de conception détaillée	RCD
CQM	Cryogenic Qualification Model		
EV	Evaporator		
FI	Inspection Sheet	Fiche d'Inspection	
FIRST	Far Infrared and Submillimetre Telescope		
FS	Flight spare		
HSE	Heat Switch (on evaporator)		
HSP	Heat Switch (on sorption pump)		
LLB	Laboratory Log Book		
N/A	Not Applicable		
PACS	Photoconductor. Array Camera and Spectrometer		
PFM	ProtoFlight Model		
RD	Reference Document		
SAP	Service d'Astrophysique		
SBT	Service des Basses Températures		
SCO	Sorption Cooler (full unit)		
SP	Sorption pump		
SPIRE	Spectral & Photometric Imaging Receiver		
SST	Support Structure		
TS	Thermal Shunt		
TSES	Thermal Strap to Evaporator Switch		
TSPS	Thermal Strap to Pump Switch		



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 1

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

## **1 Scope of the document**

This document defines the sequence of tasks and tests which shall lead to the qualification of the sorption cooler. It comprises the Assembly, Integration and Verification phases. this document should be read in accordance with the MAIV Flow Chart (ref. HSO-SBT-FC-003). Unless otherwise specified it applies to the CQM, STM, PFM and FS cooler.



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 2

***SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]***

## **2 Documents**

### **2.1 Applicable documents**

All Applicable Documents are listed in the AD chapter of the CIDL (HSO-SBT-LI-010).



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 3

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

### **3 Verification matrix**

The STM, CQM, PFM and FS coolers are designed based on our mechanical and low temperature know how and manufactured and assembled by qualified and skilled subcontractors and CEA-SBT.

All precautions are taken to guarantee successful devices and the coolers are controlled at various step during their fabrication. The manufacturing, assembling, integration and verification flow chart is described in the document “MAIV Flow Chart” ref. HSO-SBT-FC-003.

The table hereafter is a verification matrix in which for each relevant specification or requirement is indicated whether it is verified by analysis, design, test and/or inspection. The column “§ Spec.” refers to the related paragraph in the document “SPIRE & PACS Sorption Cooler Specifications”, ref. HSO-SBT-SP-001.

These verifications apply to all models (to the exception of the STM).



# SPIRE & PACS Sorption Coolers AIV Plan

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 4

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

§ Spec	Heading	Verification method			
		Analysis	Design	Test	Inspection
4.1	<b>Functional requirements</b>				
4.1 a)	Thermal architecture (4K / 1.8 K)		X		
4.1 b)	Performance versus orientation		X	X	
4.1 c)	Design "plug in" type		X		
4.1.1 a)	10 $\mu$ W net heat lift @ 290 mK		X	X	
4.1.1 b)	12 $\mu$ W maximum parasitic load		X	X	
4.1.1 c)	Hold time $\geq$ 22 h – 46 h favoured		X	X	
4.1.1 d)	Recycling time $\leq$ 2 h		X	X	
4.1.1 e)	Energy per cycle $\leq$ 860 J		X	X	
4.2	<b>Operational requirements</b>				
4.2.1	Safety : Leak Before Burst	X	X		
4.2.2	Lifetime	X	X		
4.2.3	Operating modes		X	X	
4.2.4	Commands : thermometers & heaters		X		
4.2.5	Monitoring : thermometers accuracy		X		
4.3	<b>Environmental requirements</b>				
4.3.1 a)	Ground & launch thermal environment		X	X	
4.3.1 b)	Storage & handling		X		
4.3.1 c)	Humidity		X		
4.3.1 d)	Test or orbit (idem 4.1 a)		X		
4.3.2.1	Limit loads and launch levels	X	X	X	X
4.3.2.2	Orbit		X	X	
4.3.2.3	Ground		X	X	
4.3.3	Electrical environment		X		
4.3.4	Radiation environment		X		
4.4	<b>Design &amp; construction requirements</b>				
4.4.1	Interchangeability		X		
4.4.2	Control electronics	Under responsibility of SAP			
4.4.3.1	Maximum operating pressure		X		
4.4.3.2	Proof pressure and Burst pressure	X	X	X	
4.4.4	Mass		X		
4.4.5	Size		X		
4.4.6	Mechanical stiffness requirement	X	X	X	
4.4.7.1	Design margin – Structural	X	X	X	
4.4.8.1	Parts, Material and processes	X	X		X
4.4.8.2	Magnetic materials		X		
4.4.8.3	Fungus Nutrient Materials		X		
4.4.8.4	Flammable, toxic & unstable materials		X		
4.4.8.5	Cleanliness			X	X
4.4.8.6	Finish		X		
4.4.8.7	Outgassing		X		
4.4.8.8	Susceptibility to stress corrosion		X		
4.8.8.9	Limited lifetime materials		X		
4.5	<b>Interface requirements</b>				
4.5.1	Thermal interface to detector		X		
4.5.2	Mechanical interface to the heat sink		X		
4.5.3	Thermal interface to the heat sink		X		
4.5.4	Electrical interface		X	X	
4.6	Logistic requirements		X		X





## **SPIRE & PACS Sorption Coolers AIV Plan**

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 5

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

### **4 Tests sequence**

This section describes the tests sequence to be performed on the sorption cooler which contributes, together with analysis and other verification methods, to qualification. This test program covers the functional, performance and environmental tests required to provide confidence in the ability of the cooler to meet the specified requirements. Tasks related to the manufacturing and cooler assembly are also included in this program. Performance measurements will be made before and after the environmental tests, designed to detect changes in performance parameters which may indicate a potential failure.

#### **4.1 Organization and Methods**

The test team will schedule and prepare all test procedures, will identify all necessary tests equipment and tools, and finally will performed the tests program. The test team includes engineers and technicians with the necessary experience. They will be supported by specialists when appropriate. The test team also includes members of the quality department who will carry out the PA tasks as described in the PA plan. The project manager is responsible for the implementation of the complete qualification program.

Most tests are conducted in accordance with procedures approved by the project manager, under the Product Assurance control. The tests will be performed following the tasks description identified hereafter. Prior to the start of any major test activities and after the completion of a test a formal technical review will be held. This review will determine if the tests requirements have been met.

The outcome of each test performed will be documented in a test report for all major test, and in an inspection sheet (FI : fiche d'inspection) for other test. In addition a test referenced as the "Health Check Report" has been set up. This test allows to verify nominal operation of the cooler from a mechanical, leaktightness and thermal point of view. A specific data sheet referenced as "Health Check Report" has been established, in which the experimental results will be reported (see appendix & 5.1). This health check will be performed whenever necessary to check for the integrity of the cooler.

In the event a decision is made to reject the test, the re-test and trouble-shooting requirements will be defined.

During transportation phases, dedicated container (one per model) are used following :

- before assembly : each set of cooler parts are carried in a transportation suitcase
- after assembly : each cooler (excluding STM) are handled in a transport container which includes a clean inner container maintained under a dry nitrogen environment

During all test activities a daily laboratory log book (LLB) will be kept in the working area. This will be a "live" document containing an outline of the day's activities carried out, with cross reference to any problems arising during those activities.

Finally the history of the cooler after assembly will be recorded in a Log Book which will be part of the Acceptance Data Package (ADP).



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 6

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

#### 4.2 Test program

This plan defines the methods and sequence by which all verification by test activities are intended to be performed. The test activities required to complete the test program are compiled into major test phases in a logical sequence. The following list of test includes for each test the following :

- Task name and number
- Objectives
- Required documentation
- Cooler and test configuration
- Facility and Ground support equipment
- Task description
- Acceptance criteria and comments
- Output document

Tasks are numbered 010, 020, 030 ... to enable future revisions to incorporate additional supporting tasks in sequence. The tasks have been arranged and named in the following way :

<b>Task reference</b>	<b>Related to</b>
MA nnn	Manufacturing phase
CO nnn	Cooler heart and later cooler fully assembled
ST nnn	Structure
HS nnn	Heat Switch

Only the tasks marked with an “\*” applies to the STM.

The task numbered CO 260 corresponds to a test referenced as the “Health Check”. This test allows to verify nominal operation of the cooler from a mechanical, leaktightness and thermal point of view. A specific data sheet referenced as “Health Check Report” has been established, in which the experimental results will be reported (see appendix § 5.1). This health check will be performed whenever necessary to check for the integrity of the cooler.

A set of procedures has been produced and can be reviewed at CEA-SBT premises. Most of these procedures are intended to be used by the test team and by French companies, and thus are written in French.

Unless otherwise stated the tests are carried out at CEA-SBT.

The table hereafter summarizes the sequence of tasks.



# SPIRE & PACS Sorption Coolers AIV Plan

DOC N° : HSO-SBT-PL-013  
 Iss/Rev : 2.3  
 DATE : 26/01/2004  
 PAGE : 7

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

task	Manufacturing	Cooler heart	Structure	Heat Switch
010	Critical Parts Verification + fit check*	Pump and Evaporator Pre Assembly	Assembly of Main Structure *	Pre Assembly – Switch base
020	Laser marking of specific parts*	Welding inspection and Leaktightness tests	Final Machining of Main Structure *	Assembly – Switch
030	Cleaning of parts	Soldering of Thermal Shunt and Fill Tube	Cleaning of structure	Leak Tightness Test
040	Assembly of Pump and Evaporator Half Sphere		Charcoal Mounting	
050	Baking and Mounting of Procelit		Closing of Minipump	
060	Charcoal Gluing onto Copper Casing (pump)		Leak Tightness Test	
070	Gluing of Grid and Cover		Gold plating	
080	Assembly of Evaporator Copper Half Sphere		Baking and cleaning of switch	
090	Closing of Cooler Heart		Filling / Crimping of Heat Switch	
100	Assembling and heat treatment of straps		Gluing of Thermometers and Heaters / Pre wiring	
110	Gold plating		Thermal characterization of Heat Switch	
120	Leaktightness and Proof Pressure Test at 20 MPa			
130	Cleaning and baking of Cooler Heart / Structure			
140	Gluing of Thermal Parts / Pre wiring			
150	Performance Test (Cooler Empty)			
160	<sup>3</sup> He Filling of Cooler Heart / Pre-test (Cold Phase)			
170	Crimping of Cooler			
180	Mounting of Mechanical Items*			
190	Mounting of Cooler into Main Structure*			
200	Processing of Kevlar strings*			
210	Integration of Heat Switches			
220	Cabling, Soldering of Connectors & Thermal Parts			
230	Mounting and Adjustment of Snubbers			
240	Integration of Thermal Straps			
250	Final assembly			



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
 Iss/Rev : 2.3  
 DATE : 26/01/2004  
 PAGE : 8


**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

task	Cooler fully assembled
260	Thermal Test #1 (reference – Health Check (HCR))
270	Thermal vacuum
280	Thermal Test #2 (HCR)
290	Vibration Test*
300	Thermal Test #3 (HCR)
310	Performance Test
320	Packing
330	Delivery


**4.2.1 MAIV Flow chart**

The MAIV flow chart summarizes the AIV plan in a graphical form. Each task is then detailed in the following paragraph (§ 4.2.2 and further).

**4.2.1.1 Symbols explanation**



**4.2.1.2 Flow chart**








# SPIRE & PACS Sorption Coolers AIV Plan

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 10


SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]













**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
 Iss/Rev : 2.3  
 DATE : 26/01/2004  
 PAGE : 14

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

**4.2.2 Manufacturing**

<b>TASK NUMBER : MA 010</b>
<b><i>TASK NAME</i></b>
Critical Parts Verification and fit check
<b><i>OBJECTIVES</i></b>
Verify the critical parts (in particular the thin wall titanium tubes) – Establish the mass budget for each part. Perform a fit check. Take photographic record of one full set
<b><i>REQUIRED DOCUMENTATION</i></b>
All detailed drawings related to reference 2000-14 B 000, 100, 200, 300, 400, 530, 540 Certificate of conformity from subcontractor
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room, ambient conditions Metrology devices – weighing machine
<b><i>TASK DESCRIPTION</i></b>
<ul style="list-style-type: none"> <li>- Particularly check all parts subjected to pressure. In particular check for any geometrical and visual defects parts reference 2000-14 B203, B205 and B211</li> <li>- Check the surface quality on all pulleys and capstan (ref. B109, B114, B129)</li> <li>- Weight each piece and perform a fit check</li> <li>- Take photographic record of one full set</li> </ul>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
All dimensions shall be within tolerances – No defects can be accepted on critical parts, i.e. submitted to internal pressure. No defects on surface quality can be accepted for pulleys and capstans
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB – For all thin wall tubes, report in Inspection Sheet (FI) Photographic records Fill in the “as run procedure”



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 15

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : MA 020</b>
<b><i>TASK NAME</i></b>
Laser marking of specific parts
<b><i>OBJECTIVES</i></b>
Laser mark all major components for identification purpose
<b><i>REQUIRED DOCUMENTATION</i></b>
HSO-SBT-SP-039 (Identification des pièces et sous ensembles)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Operation subcontracted - Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>
All demountable cooler components and toolings are marked using a Nd-Yag laser – Cooler components include : cooler heart, heat switches, structure, lateral covers, evaporator cover, pump cover, pump strap, evaporator strap. Applies to STM cooler too.
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Work performed in accordance with subcontractor quality program
<b><i>OUTPUT DOCUMENTS</i></b>
N/A



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 16

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : MA 030</b>
<b><i>TASK NAME</i></b>
Cleaning of Parts
<b><i>OBJECTIVES</i></b>
Clean all parts
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-0026 (Nettoyage)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room, ambient conditions Cleaning facility
<b><i>TASK DESCRIPTION</i></b>
- Clean all parts following cleaning procedure
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB Fill in the "as run procedure"



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 17

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

**4.2.3 Cooler “heart” / Cooler fully assembled**

<b>TASK NUMBER : CO 010</b>
<b><i>TASK NAME</i></b> Pump and Evaporator Pre-assembly
<b><i>OBJECTIVES</i></b> Electron beam welding of thin wall titanium tubes with evaporator and pump half titanium sphere
<b><i>REQUIRED DOCUMENTATION</i></b> Related drawings HSO-SBT-SP-014 (Spécifications qualité appliquées à la fabrication) HSO-SBT-FC-023 (Organigramme des soudures)
<b><i>COOLER AND TEST CONFIGURATION</i></b>  N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>  Dedicated tool provided by SBT Operation subcontracted - Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>  See HSO-SBT-FC-023 – Use tool ref 2000-14 T470, 2000-14 T480, 2000-14 T460 1. Perform a first EB weld on test samples to define parameters and verify the weld quality 2. EB weld part ref B209 with part ref B211, and the resulting piece with part ref B207 3. EB weld part ref B205 with part ref B202
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>  Work performed in accordance with subcontractor quality program Outcome of task CO 020
<b><i>OUTPUT DOCUMENTS</i></b>  Certificate of conformity



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 18

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 020</b>
<b><i>TASK NAME</i></b>
Welding Inspection and Leaktightness Tests
<b><i>OBJECTIVES</i></b>
Verify the quality and leaktightness of the welds
<b><i>REQUIRED DOCUMENTATION</i></b>
N/A
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room - Ambient conditions Helium leak detector (mass spectrometer)
<b><i>TASK DESCRIPTION</i></b>
Use appropriate rubber plugs and connection to leak detector to check for the leaktightness of the welded joint under vacuum.
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Leakrates level must not exceed $10^{-9}$ mB.Ls <sup>-1</sup>
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB – report outcome in Inspection Sheet (FI)



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 19

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : CO 030</b>
<b><i>TASK NAME</i></b>
Soldering of Thermal Shunt and Fill Tube
<b><i>OBJECTIVES</i></b>
Assemble (brazing) the thermal shunt and fill tube with the pumping line
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings HSO-SBT-SP-014 (Spécifications qualité appliquées à la fabrication) HSO-SBT-FC-023 (Organigramme des soudures)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Dedicated tool provided by SBT Operation subcontracted – Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>
See HSO-SBT-FC-023– Use tool ref 2000-14 T350, 2000-14 T300 Brazing of thermal shunt (part ref. B210), copper fill tube and copper tubes with partly assembled pumping line (tube - evaporator half sphere and tube - pump half sphere). Note : the copper fill tube must be at least 150 mm long
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Work performed in accordance with subcontractor quality program
<b><i>OUTPUT DOCUMENTS</i></b>
Certificate of conformity



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 20

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : CO 040</b>
<b><i>TASK NAME</i></b>
Assembly of Pump and Evaporator Half Sphere
<b><i>OBJECTIVES</i></b>
Brazing of copper end parts to pump and evaporator half titanium sphere + internal copper structures to copper end parts (pump and evap).
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings HSO-SBT-SP-014 (Spécifications qualité appliquées à la fabrication) HSO-SBT-FC-023 (Organigramme des soudures)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Operation subcontracted – Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>
See HSO-SBT-FC-023 1. Brazing of evaporator 1/2 sphere (ref. B201) with evaporator cold tip (ref. B219) 2. Brazing of evaporator cup (ref. B203) with evaporator cold tip (ref. B219) 3. Brazing of pump 1/2 sphere (ref. B208) with pump cold tip (ref. B220) 4. Brazing of charcoal casing (ref. B212) with pump cold tip (ref. B220)
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Work performed in accordance with subcontractor quality program Once parts are back at SBT : perform a leaktightness test : Leakrates level must not exceed $10^{-9}$ mB.Ls <sup>-1</sup>
<b><i>OUTPUT DOCUMENTS</i></b>
Certificate of conformity





**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 21

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 050</b>
<b><i>TASK NAME</i></b>
Baking and Mounting of Procelit
<b><i>OBJECTIVES</i></b>
Insert the porous material (Procelit) use for liquid confinement into evaporator
<b><i>REQUIRED DOCUMENTATION</i></b>
N/A
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler partly assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Baking chamber equipped with primary vacuum pump
<b><i>TASK DESCRIPTION</i></b>
<ol style="list-style-type: none"><li>1. Weights Part ref. B206 (Procelit) prior to baking</li><li>2. Baked out Part B206 at 100°C under vacuum (primary) for 12 hours minimum (overnight)</li><li>3. Weights Part B206 after baking</li><li>4. Insert Part B206 into evaporator cup (Part ref. B203)</li></ol>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
No damages acceptable to Part B206
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 22

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 060</b>
<b><i>TASK NAME</i></b>
Charcoal Gluing onto Copper Casing (pump)
<b><i>OBJECTIVES</i></b>
Assembling of sorption pump
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-024 (Mise en place du charbon actif)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler partly assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room. Ambient conditions. Weighing machine. Baking chamber equipped with primary pump
<b><i>TASK DESCRIPTION</i></b>
Follow procedure HSO-SBT-PR-024. Summary : <ol style="list-style-type: none"><li>1. Perform a visual selection of charcoal pellets</li><li>2. Bake out at 140°C under vacuum (primary) the charcoal pellets for 24 hours</li><li>3. Weights and prepare the appropriate amount</li><li>4. Glue the pellets onto the charcoal casing (B212) using Stycast 2850 FT</li></ol>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Total amount of charcoal must be glued (few pellets left is acceptable). Charcoal pellets must not fall when slightly shaking the sorption pump.
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB Fill in the “as run procedure”



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 23

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 070</b>
<b><i>TASK NAME</i></b>
Gluing of Grid and Cover
<b><i>OBJECTIVES</i></b>
Install the filter mesh at the input of the pumping line on the sorption pump side
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler partly assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
N/A
<b><i>TASK DESCRIPTION</i></b>
<ul style="list-style-type: none"><li>- Install mesh ref. B218 against part ref B209</li><li>- Insert the cover (ref. B217) and glue the cover on part B209/B211 using Stycast 2850 FT.</li></ul>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
No Stycast acceptable on the mesh.
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 24

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 080</b>
<b><i>TASK NAME</i></b>
Assembly of Evaporator Copper Half Sphere
<b><i>OBJECTIVES</i></b>
Close the internal evaporator copper sphere containing the Procelit piece
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings HSO-SBT-SP-014 (Spécifications qualité appliquées à la fabrication) HSO-SBT-FC-023 (Organigramme des soudures)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler partly assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Operation subcontracted – Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>
See HSO-SBT-FC-023 EB weld Part ref B203 with Part ref B204 (closing of Procelit copper casing)
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Work performed in accordance with subcontractor quality program
<b><i>OUTPUT DOCUMENTS</i></b>
Certificate of conformity



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 25

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : CO 090</b>
<b><i>TASK NAME</i></b> Closing of Cooler
<b><i>OBJECTIVES</i></b> EB weld the titanium half spheres together (evaporator and pump). Cooler heart is fully assembled.
<b><i>REQUIRED DOCUMENTATION</i></b> Related drawings HSO-SBT-SP-014 (Spécifications qualité appliquées à la fabrication) HSO-SBT-FC-023 (Organigramme des soudures)
<b><i>COOLER AND TEST CONFIGURATION</i></b>  Cooler partly assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>  Dedicated tool provided by SBT Operation subcontracted – Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>  See HSO-SBT-FC-023 - Use tool ref 2000-14 T450 Perform a first EB weld on test samples to define parameters and verify the weld quality - EB weld part ref B201 with part ref B202, and part ref B207 with part ref B208
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>  Work performed in accordance with subcontractor quality program Once parts are back at SBT : perform a leaktightness test : Leakrates level must not exceed $10^{-9}$ mB.Ls <sup>-1</sup> Final acceptance established at output of task CO120 (leaktightness and proof pressure test)
<b><i>OUTPUT DOCUMENTS</i></b>  Certificate of conformity Report outcome in Inspection Sheet (FI)



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 26

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : CO 100</b>
<b><i>TASK NAME</i></b>
Assembling and heat treatment of straps
<b><i>OBJECTIVES</i></b>
Production of thermal straps (evaporator and sorption pump side + shunt)
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings HSO-SBT-SP-014 (Spécifications qualité appliquées à la fabrication) HSO-SBT-FC-023 (Organigramme des soudures) 2000-14 B530, 2000-14 B540, 2000-14 B550
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Operation either partly subcontracted and performed at SBT– Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>
<ol style="list-style-type: none"><li>1. TIG welding of copper braid with part ref. B531 and part ref. B532</li><li>2. TIG welding of copper braid with part ref. B541 and part ref. B542</li><li>3. TIG welding of copper braid with part ref. B551 and part ref. B552</li><li>4. If necessary heat treatment of straps following procedure HSO-SBT-PR-080</li></ol>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Work performed in accordance with subcontractor and SBT quality program
<b><i>OUTPUT DOCUMENTS</i></b>



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 27

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : CO 110</b>
<b><i>TASK NAME</i></b>
Gold Plating
<b><i>OBJECTIVES</i></b>
Gold plating of all external copper surfaces
<b><i>REQUIRED DOCUMENTATION</i></b>
HSO-SBT-SP-044 (Définition des pièces à dorer)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Operation subcontracted – Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>
Gold plate all external copper surfaces (nota : to the exception of: the surfaces indicated in HSO-SBT-SP-044) <ul style="list-style-type: none"><li>- pump and evaporator cold tip</li><li>- thermal shunt</li><li>- thermal straps – end piece only (evaporator, pump and shunt)</li><li>- switches head and base</li></ul>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Work performed in accordance with subcontractor quality program
<b><i>OUTPUT DOCUMENTS</i></b>
Certificate of conformity



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 28

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

**TASK NUMBER : CO 120**

***TASK NAME***

Leaktightness and Proof Pressure Test at 20 MPa.

***OBJECTIVES***

Internal pressure test of the cooler to 20 MPa to address the proof and burst pressure requirements. Test is carried out with <sup>4</sup>He gas.

***REQUIRED DOCUMENTATION***

Procedure HSO-SBT-PR-025 (Test en pression)

***COOLER AND TEST CONFIGURATION***

Cooler heart almost fully assembled - Cooler inserted into test box (vacuum jacket) and connected via its fill tube to a high pressure helium bottle

***FACILITY AND GROUND SUPPORT EQUIPMENT***

Clean room, ambient conditions

High pressure helium bottle with pressure regulator, pressure transducer, test box (vacuum jacket), leak detector and possibly primary vacuum pump.

***TASK DESCRIPTION***

Follow procedure HSO-SBT-PR-025 - Summary

1. Insert cooler heart inside test box, with pressure line connected to the fill tube (soft solder)
2. Connect the test box to the leak detector
3. increase the internal pressure inside the cooler to 20 MPa over the course of typically one minute, and once the pressure reaches 20 MPa, remains at this value for 2 minutes. Then release the pressure.

***ACCEPTANCE CRITERIA AND COMMENTS***

Leakrates level must not exceed  $10^{-9}$  l.mB.s<sup>-1</sup>.

After the test, the cooler must be pumped down in secondary vacuum for 2 hours minimum, and then left in appropriate environment (see task CO 110 : plastic bag under helium gas, fill tube plugged with rubber plug).

***OUTPUT DOCUMENTS***

Report in LLB – Report outcome in Inspection Sheet (FI)  
Fill in the “as run procedure”





**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 29

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 130</b>
<b><i>TASK NAME</i></b>
Cleaning and baking of Cooler Heart / Structure
<b><i>OBJECTIVES</i></b>
Cleaning of cooler external to be under cleanliness and contamination control - Remove any trace of pollution from activated charcoal (baking).
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-0026 (Nettoyage) Procedure HSO-SBT-PR-0035 (Etuvage)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler heart almost fully assembled (closed, to the exception of the fill tube) Structure fully assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room. Ambient conditions. Baking chamber equipped with primary pump
<b><i>TASK DESCRIPTION</i></b>
Clean out the cooler heart and structure following cleaning procedure Bake out at 80°C under vacuum (primary) for 12 hours minimum Once baked and cleaned, parts must be kept in appropriate environment (plastic bag under helium gas is acceptable) and the fill tube must be plugged with a rubber plug
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
N/A
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB Fill in the “as run procedure”



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 30

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 140</b>
<b><i>TASK NAME</i></b>
Gluing of Thermal Parts / Pre wiring
<b><i>OBJECTIVES</i></b>
Instrument the cooler heart with heaters and thermometers
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-033 (Collage, thermalisation et soudure des composants)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler heart almost fully assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions
<b><i>TASK DESCRIPTION</i></b>
Glue all required heaters and thermometers on the evaporator, sorption pump and thermal shunt, using Stycast 2850 FT (see procedure HSO-SBT-PR-033) Pre wire all components, including thermal anchoring at shunt of wires routed to the evaporator (see procedure). All wires are twisted manganin wires 200 µm diameter.
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Visual check Electrical resistance check (component resistance and electrical isolation with regards to cooler).
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB Fill in the “as run procedure”



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 31

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 150</b>
<b>TASK NAME</b>
Performance Test (Cooler Empty)
<b>OBJECTIVES</b>
Thermally characterize the thermal conductance between the cooler and cold heat sink (cryostat).
<b>REQUIRED DOCUMENTATION</b>
Partly apply : Procedure HSO-SBT-PR-029 (Remplissage du cooler)
<b>COOLER AND TEST CONFIGURATION</b>
Cooler heart mounted in test cryostat following procedure HSO-SBT-PR-029. Cooler fill tube connected to cryostat internal high pressure circuitry (once cooler is connected, circuitry must be leak tested under 6 MPa – IMPORTANT : following this pressure test cooler must be pumped down in secondary vacuum for 2 hours minimum).
<b>FACILITY AND GROUND SUPPORT EQUIPMENT</b>
Clean Room – Ambient conditions. Test cryostat with all relevant associated equipment : secondary vacuum pump, liquid helium level indicator, temperature bridges, power supplies, voltmeters, large capacity vacuum pump (bath pumping), manometers, etc...
<b>TASK DESCRIPTION</b>
For a heat sink temperature of 1.8 K (pumped bath) and cooler structure of 4.2 K, characterize the following conductance : <ol style="list-style-type: none"><li>1. sorption pump to cold heat sink</li><li>2. thermal shunt to cold heat sink</li><li>3. evaporator to cold heat sink</li></ol> The thermal conductance will be characterized with the switches in the ON and OFF position.
<b>ACCEPTANCE CRITERIA AND COMMENTS</b>
Results shall be consistent with predictions. This task will allow once the cooler will be filled with helium gas to check for any unexpected problems (thermoacoustic oscillations, etc...) which signatures are in most cases unexpected thermal conductance.  Following this test, if no problems arises, the cooler is filled with $^3\text{He}$ gas (or $^4\text{He}$ )
<b>OUTPUT DOCUMENTS</b>
Report in LLB – Test report



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 32

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 160</b>
<b><i>TASK NAME</i></b>
<sup>3</sup> He Filling of Cooler / Pre test (Cold Phase)
<b><i>OBJECTIVES</i></b>
Fill the cooler with <sup>3</sup> He gas. Cooler heart becomes thermally operational.
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-029 (Remplissage du cooler)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Idem CO 150
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Idem as CO 150, plus high pressure <sup>3</sup> He bottle and appropriate manometers and valves. In addition a leak detector with the mass 3 option is connected to cryostat internal vacuum.
<b><i>TASK DESCRIPTION</i></b>
The cryostat bath can be either at 4.2 K or 1.8 K. Follow procedure HSO-SBT-PR-029. Summary : <ol style="list-style-type: none"><li>1. Connect high pressure <sup>3</sup>He bottle to cryostat internal high pressure circuitry</li><li>2. Turn ON both heat switches</li><li>3. Inject the appropriate amount of <sup>3</sup>He gas – check for any internal leak (cryostat vacuum)</li><li>4. Close high pressure <sup>3</sup>He bottle and valves to cryostat</li></ol>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Internal pressure at room temperature consistent with prediction (check at warm up) – see CO170.
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB Fill in the “as run procedure”



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 33

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 170</b>
<b><i>TASK NAME</i></b>
Crimping of Cooler
<b><i>OBJECTIVES</i></b>
Crimp the cooler fill tube. Cooler heart becomes then self contained.
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-030 (Quesottage)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler mounted in test cryostat. Test cryostat at room temperature, open.
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions. Crimping tool. Soldering tool. Leak detector with the <sup>3</sup> He mass option. Test box (vacuum jacket)
<b><i>TASK DESCRIPTION</i></b>
Follow procedure HSO-SBT-PR-030. Summary : 1. Once cooler and cryostat are at room temperature, check the cooler internal pressure 2. Crimp the fill tube / cut it / Soft solder plug it / Release crimp tool 3. Leak test / glue Part ref. B221 on crimped tube 4. Perform final leak test
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Before crimping internal cooler pressure must be 8 MPa at 20°C to within 5% Leakrates level must not exceed 10 <sup>-9</sup> l.mB.s <sup>-1</sup> or vacuum box <sup>3</sup> He background measured prior to insertion of cooler
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB – Report outcome in Inspection sheet (FI) Fill in the “as run procedure”



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 34

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 180</b>
<b><i>TASK NAME</i></b>
Mounting of Mechanical Items
<b><i>OBJECTIVES</i></b>
Install all pulleys and axis on the evaporator and sorption pump
<b><i>REQUIRED DOCUMENTATION</i></b>
Detailed drawings 2000-14 B 000 and associated drawings
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler heart almost fully assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions
<b><i>TASK DESCRIPTION</i></b>
Task name and objectives are self descriptive. All torques must be verified.
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
No damage on pulleys and capstans surfaces acceptable
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 35

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 190</b>
<b><i>TASK NAME</i></b>
Mounting of Cooler into Main Structure
<b><i>OBJECTIVES</i></b>
To insert cooler heart into the structural box and to install all Kevlar cords
<b><i>REQUIRED DOCUMENTATION</i></b>
Partly apply : Procedure HSO-SBT-PR-028 (Installation et réglages des suspentes Kevlar)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler heart fully assembled and structural box
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions
<b><i>TASK DESCRIPTION</i></b>
Follow procedure HSO-SBT-PR-028 - Summary 1. Insert cooler heart inside structural box 2. Screw in the centering screws (B134, B135) to secure the cooler heart 3. Install all Kevlar cords 4. Release cooler heart (unscrew B134 and B135)
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
See procedure – Visual check, cooler heart centered, etc..
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB Fill in the “as run procedure”



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 36

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 200</b>
<b><i>TASK NAME</i></b>
Processing of Kevlar strings
<b><i>OBJECTIVES</i></b>
Thermally trained and tune the suspension system (Kevlar strings) to stabilize the tension (Kevlar).
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-028 (Installation et réglages des suspentes Kevlar)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler heart mounted inside structural box
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions – Baking chamber equipped with primary pump Tensiometer
<b><i>TASK DESCRIPTION</i></b>
Follow procedure HSO-SBT-PR-028 After initial tensioning of strings, suspension system is baked three times at 80°C for 4 hours and is retensioned during the process.
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB. Report measured tension in Inspection Sheet (FI) Fill in the “as run procedure”





**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 37

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 210</b>
<b><i>TASK NAME</i></b>
Integration of Heat Switches
<b><i>OBJECTIVES</i></b>
Integrate the two heat switches inside the cooler
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler heart mounted inside structural box
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions
<b><i>TASK DESCRIPTION</i></b>
Mechanically mount the two heat switches inside the cooler structural box. The recommended torque for the three holding screws is 2.1 Nm.
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Must be done with great care : thin titanium tube on heat switch is fragile and critical to the performance of the heat switch / cooler Verify the electrical isolation with respect to the structure
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 38

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 220</b>
<b><i>TASK NAME</i></b>
Cabling and Soldering of Connectors and Thermal Parts
<b><i>OBJECTIVES</i></b>
Connect all thermometers and heaters to the two electrical connectors via manganin wires
<b><i>REQUIRED DOCUMENTATION</i></b>
Interface Control Document (HSO-SBT-ICD-012) Procedure HSO-SBT-PR-033 (Collage, thermalisation et soudure des composants)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler heart + heat switches mounted inside structural box
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions. Soldering tool
<b><i>TASK DESCRIPTION</i></b>
Follow procedure HSO-SBT-PR-033 Refer to wiring table in ICD. All the wires connected to the evaporator are thermally anchored to the thermal shunt (done previously at task CO 140)
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Visual check Electrical resistance check (component resistance and electrical isolation with regards to cooler) Electrical isolation of cooler heart and heat switch with the structure (Nota : make sure the centering screws (transit screws) are removed)
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB – Report outcome in Inspection Sheet (FI) Fill in the “as run procedure”



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 39

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : CO 230</b>
<b><i>TASK NAME</i></b>
Mounting and Adjustment of Snubbers
<b><i>OBJECTIVES</i></b>
Mechanically mount and adjust the snubbers on the heat switches to prevent any excessive lateral motion
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler heart + heat switches mounted inside structural box
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions
<b><i>TASK DESCRIPTION</i></b>
Mount and adjust the snubbers (Part ref. B119, B120, B311). The snubbers must be centered with regards to the “inside” part.
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
No contact is acceptable between snubber and “inside” part
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 40

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : CO 240</b>
<b><i>TASK NAME</i></b>
Integration of Thermal Straps
<b><i>OBJECTIVES</i></b>
Connect the thermal straps : switch end to evaporator, switch end to pump and shunt to evaporator switch base
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler heart + heat switches mounted inside structural box
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions
<b><i>TASK DESCRIPTION</i></b>
<ol style="list-style-type: none"><li>1. Secure the cooler heart with the centering screws (B134, B135)</li><li>2. Connect thermal strap B530 between the pump heat switch and sorption pump cold tip</li><li>3. Connect thermal strap B540 between the evaporator heat switch and evaporator cold tip</li><li>4. Connect thermal strap B550 between the shunt and the evaporator switch base</li><li>5. Remove the centering screws</li></ol>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Do not apply any torque on the heat switches to avoid any damage to the thin wall titanium tube. Always use two wrenches (one on each side) when tightening screws
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 41

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 250</b>
<b><i>TASK NAME</i></b>
Final assembly
<b><i>OBJECTIVES</i></b>
Complete the final assembly of the cooler
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler fully operational.
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions
<b><i>TASK DESCRIPTION</i></b>
<ol style="list-style-type: none"><li>1. Set in place Part ref. B136 (guiding tube)</li><li>2. Mount the two lateral plates ref. B404 and B405</li><li>3. Mount Part ref. B137 (evaporator cover)</li><li>4. Mount Part ref. B124 (pump cover)</li></ol>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Visual check
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 42

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : CO 260</b>
<b><i>TASK NAME</i></b>
Thermal Test #1 (reference – Health Check (HCR))
<b><i>OBJECTIVES</i></b>
Perform a thermal check of the cooler performance. This test sequence defines the test referenced as ‘Health Check’
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-031 (Health Check)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Operational cooler mounted in test cryostat
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean Room – Ambient conditions. Test cryostat with all relevant associated equipment : secondary vacuum pump, liquid helium level indicator, temperature bridges, power supplies, voltmeters, large capacity vacuum pump (bath pumping), manometers, etc...
<b><i>TASK DESCRIPTION</i></b>
Follow procedure HSO-SBT-PR-031. Summary of data recorded : <ol style="list-style-type: none"><li>1. Leak rate (before and after thermal tests)</li><li>2. Kevlar cords tension</li><li>3. ultimate temperature (right side up and upside down)</li><li>4. cooling power curve (right side up and upside down)</li><li>5. hold time under 30 and 200 <math>\mu</math>W load</li></ol>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Results shall be consistent with predictions See procedure HSO-SBT-PR-031 and health check data sheet. This test will then serve as a reference for all subsequent thermal tests.
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB – Health Check Report (HCR) data sheet



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 43

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 270</b>
<b><i>TASK NAME</i></b>
Thermal Vacuum
<b><i>OBJECTIVES</i></b>
Bake out the cooler at 80°C under vacuum for 5 days to check for any effect on the performance
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-035 (Etuvage)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler fully assembled – Self standing unit
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room. Ambient conditions. Baking chamber equipped with primary pump
<b><i>TASK DESCRIPTION</i></b>
Follow procedure HSO-SBT-PR-035 Bake out the cooler at 80°C under vacuum (primary) for 5 days Note : no thermal cycling foreseen
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
No visual damage – this test is followed by a heath check to check for the cooler integrity
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB + Log Book Fill in the “as run procedure”



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 44

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 280</b>
<b><i>TASK NAME</i></b>
Thermal Test #2 (HCR)
<b><i>OBJECTIVES</i></b>
Verify the cooler performance are not affected after the thermal vacuum (bake out)
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-031 (Health Check)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler mounted in test cryostat
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean Room – Ambient conditions. Test cryostat with all relevant associated equipment : secondary vacuum pump, liquid helium level indicator, temperature bridges, power supplies, voltmeters, large capacity vacuum pump (bath pumping), manometers, etc...
<b><i>TASK DESCRIPTION</i></b>
Follow procedure HSO-SBT-PR-031. Summary of data recorded : 1 Leak rate (before and after thermal tests) 2 Kevlar cords tension 3 ultimate temperature (right side up and upside down) 4 cooling power curve (right side up and upside down) 5 hold time under 30 and 200 $\mu$ W load
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Results shall be consistent with the first set of data established during Task CO 260 (first health check) See procedure HSO-SBT-PR-031 and health check data sheet.
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB + Log Book – Health Check Report (HCR) data sheet





**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 45

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : CO 290</b>
<b><i>TASK NAME</i></b>
Vibration Test
<b><i>OBJECTIVES</i></b>
Determine the resonant frequencies and demonstrate the ability of the cooler to withstand the V test
<b><i>REQUIRED DOCUMENTATION</i></b>
Vibration levels (HSO-SBT-SP-001) Procedure HSO-SBT-PR-045 (Tests Vibratoires)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler fully assembled – Self standing unit. Clean room – Ambient conditions
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Operation subcontracted – Under CEA-SBT and subcontractor responsibility.
<b><i>TASK DESCRIPTION</i></b>
Perform required vibration sequence for each axis - before each run and at the end of each axis, perform a low level sine sweep to control the dynamic behavior.
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Cooler shall survive the specified vibration levels Performance in accordance with predictions (see HSO-SBT-SP-037) During and at completion of the tests inspect visually for any external damages Work performed in accordance with subcontractor quality program and SBT PA Plan
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB + Log Book – Test report (from subcontractor)



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 46

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 300</b>
<b><i>TASK NAME</i></b>
Thermal Test #3 (HCR)
<b><i>OBJECTIVES</i></b>
Verify the cooler performance are not affected after the vibration tests
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-031 (Health Check)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler mounted in test cryostat
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean Room – Ambient conditions. Test cryostat with all relevant associated equipment : secondary vacuum pump, liquid helium level indicator, temperature bridges, power supplies, voltmeters, large capacity vacuum pump (bath pumping), manometers, etc...
<b><i>TASK DESCRIPTION</i></b>
Follow procedure HSO-SBT-PR-031. Summary of data recorded : <ol style="list-style-type: none"><li>1. Leak rate (before and after thermal tests)</li><li>2. Kevlar cords tension</li><li>3. ultimate temperature (right side up and upside down)</li><li>4. cooling power curve (right side up and upside down)</li><li>5. hold time under 30 and 200 <math>\mu</math>W load</li></ol>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Results shall be consistent with the first set of data established during Task CO 260 (first health check) See procedure HSO-SBT-PR-031 and health check data sheet.
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB + Log Book – Health Check Report (HCR) data sheet



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 47

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 310</b>
<b><i>TASK NAME</i></b>
Performance Test
<b><i>OBJECTIVES</i></b>
Verify the cooler performance against specifications (hold time and operating temperature)
<b><i>REQUIRED DOCUMENTATION</i></b>
“Specifications” ref. HSO-SBT-SP-001
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler mounted in test cryostat
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean Room – Ambient conditions. Test cryostat with all relevant associated equipment : secondary vacuum pump, liquid helium level indicator, temperature bridges, power supplies, voltmeters, large capacity vacuum pump (bath pumping), manometers, etc...
<b><i>TASK DESCRIPTION</i></b>
Follow standard recycling procedure (see procedure HSO-SBT-PR-031). After recycling set the cooler orientation to horizontal. Then record the following data : <ol style="list-style-type: none"><li>1. all timings</li><li>2. hold time and ultimate temperature of cooler under 10 <math>\mu</math>W heat load</li><li>3. all input power, so as to determine the energy dissipated during the cycle</li></ol>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Results shall at a minimum meet the predictions
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB + Log Book – Test Report



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 48

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : CO 320</b>
<b><i>TASK NAME</i></b>
Packing
<b><i>OBJECTIVES</i></b>
Pack the cooler before delivery
<b><i>REQUIRED DOCUMENTATION</i></b>
CQM : Procedure HSO-SBT-PR-077 (Handling, packing, transportation and storage manual) (applies also to FM for now).
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler fully assembled – Self standing unit, cleaned.
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Dedicated transportation container
<b><i>TASK DESCRIPTION</i></b>
Before packing : perform a last leaktightness test Follow procedure HSO-SBT-PR-077. Summary : <ul style="list-style-type: none"><li>- mounting of cooler inside inner container</li><li>- purging with dry nitrogen</li><li>- mounting of inner container inside transportation container</li></ul>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Leakrates level must not exceed $10^{-9}$ mB.Ls <sup>-1</sup> Internal pressure of inner container must remains at least 100 mB above atmospheric pressure
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB + Log Book



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 49

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : CO 330</b>
<b><i>TASK NAME</i></b>
Delivery
<b><i>OBJECTIVES</i></b>
Deliver the cooler to RAL (SPIRE) or SAp (PACS)
<b><i>REQUIRED DOCUMENTATION</i></b>
Acceptance Data Package
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Cooler fully assembled – Self standing unit, cleaned and packed in transportation container
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Transportation box. The cooler is carried by car or train and is accompanied
<b><i>TASK DESCRIPTION</i></b>
Review of documentation Delivery of cooler
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
- No damage during transportation - Shock level indicator not triggered
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB + Log Book. Acceptance Data Package (including Log Book)



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 50

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

**4.2.4 Structure**

<b>TASK NUMBER : ST 010</b>
<b><i>TASK NAME</i></b> Assembly of Main Structure
<b><i>OBJECTIVES</i></b> EB Welding of parts composing the main structural box
<b><i>REQUIRED DOCUMENTATION</i></b> Related drawings HSO-SBT-SP-014 (Spécifications qualité appliquées à la fabrication) HSO-SBT-FC-023 (Organigramme des soudures)
<b><i>COOLER AND TEST CONFIGURATION</i></b>  N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>  Dedicated tool provided by SBT Operation subcontracted - Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>  See HSO-SBT-FC-023 – Use tool ref. 2000-14 T500 Perform a first EB weld on test samples to define parameters and verify the weld quality 1. EB weld part ref B401, B402, B403, B406 and EB407 (according to drawing ref. 2000-14 B 400)
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>  Work performed in accordance with subcontractor quality program Assembled structure in accordance with drawings specifications
<b><i>OUTPUT DOCUMENTS</i></b>  Certificate of conformity



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 51

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : ST 020</b>
<b><i>TASK NAME</i></b>
Final Machining of Main Structure
<b><i>OBJECTIVES</i></b>
Remove by machining the extra material (TA6V) initially left for EB welding purpose
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings HSO-SBT-SP-014 (Spécifications qualité appliquées à la fabrication) HSO-SBT-FC-023 (Organigramme des soudures)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Operation subcontracted – Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>
Remove by machining the extra material (TA6V) initially left for EB welding purpose on the support structure
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Work performed in accordance with subcontractor quality program
<b><i>OUTPUT DOCUMENTS</i></b>
Certificate of conformity



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 52

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : ST 030</b>
<b><i>TASK NAME</i></b>
Cleaning of Structure
<b><i>OBJECTIVES</i></b>
Clean the structure (after final assembly and laser marking)
<b><i>REQUIRED DOCUMENTATION</i></b>
N/A
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Operation subcontracted – Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>
Clean the structure to remove all trace of contamination (grease, machining, etc...)
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Work performed in accordance with subcontractor quality program
<b><i>OUTPUT DOCUMENTS</i></b>
Certificate of conformity





**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 53

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

**4.2.5 Heat Switches**

<b>TASK NUMBER : HS 010</b>
<b><i>TASK NAME</i></b> Pre Assembly – Switch base
<b><i>OBJECTIVES</i></b> Assemble heat switch base
<b><i>REQUIRED DOCUMENTATION</i></b> Related drawings : 2000-14 B300 HSO-SBT-SP-014 (Spécifications qualité appliquées à la fabrication) HSO-SBT-FC-023 (Organigramme des soudures)
<b><i>COOLER AND TEST CONFIGURATION</i></b>  N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>  Operation subcontracted – Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>  See HSO-SBT-FC-023 EB weld part ref. B310 with part ref. B309
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>  Work performed in accordance with subcontractor quality program
<b><i>OUTPUT DOCUMENTS</i></b>  Certificate of conformity



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 54

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : HS 020</b>
<b><i>TASK NAME</i></b>
Assembly - Switch
<b><i>OBJECTIVES</i></b>
Assemble the heat switch
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings : 2000-14 B300 HSO-SBT-SP-014 (Spécifications qualité appliquées à la fabrication) HSO-SBT-FC-023 (Organigramme des soudures)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Operation subcontracted – Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>
See HSO-SBT-FC-023 Brazing of part ref. B301, B302, 103, B309/B310, B305, B306
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Work performed in accordance with subcontractor quality program Acceptance established at output of task HS 030 (leaktightness test)
<b><i>OUTPUT DOCUMENTS</i></b>
Certificate of conformity



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 55

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : HS 030</b>
<b><i>TASK NAME</i></b>
Leak Tightness Test
<b><i>OBJECTIVES</i></b>
Verify the quality and leaktightness of all joints
<b><i>REQUIRED DOCUMENTATION</i></b>
N/A
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Heat switch partly assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room - Ambient conditions Helium leak detector (mass spectrometer)
<b><i>TASK DESCRIPTION</i></b>
Use appropriate rubber plugs and connection to leak detector to check for the leaktightness of all joints under vacuum.
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Leakrates level must not exceed $10^{-9}$ mB.Ls <sup>-1</sup>
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB – Report outcome in Inspection Sheet (FI)



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 56

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : HS 040</b>
<b><i>TASK NAME</i></b>
Charcoal mounting
<b><i>OBJECTIVES</i></b>
Pre assembly of miniature sorption pump
<b><i>REQUIRED DOCUMENTATION</i></b>
N/A
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Heat switch partly assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room. Ambient conditions. Weighing machine. Baking chamber equipped with primary pump
<b><i>TASK DESCRIPTION</i></b>
<ol style="list-style-type: none"><li>1. Perform a visual selection of charcoal pellets</li><li>2. Bake out at 140°C under vacuum (primary) the charcoal pellets for 12 hours minimum</li><li>3. Weights and prepare the appropriate amount, ie 20 milligrams</li><li>4. Insert the fine mesh inside the minipump (B306) and then the pellet into the minipump</li></ol>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
N/A
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 57

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : HS 050</b>
<b><i>TASK NAME</i></b>
Closing of Minipump
<b><i>OBJECTIVES</i></b>
EB weld the minipump cap
<b><i>REQUIRED DOCUMENTATION</i></b>
Related drawings HSO-SBT-SP-014 (Spécifications qualité appliquées à la fabrication) HSO-SBT-FC-023 (Organigramme des soudures)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Heat switch partly assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Operation subcontracted – Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>
See HSO-SBT-FC-023 EB weld Part ref. B306 with Part ref. B307
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Work performed in accordance with subcontractor quality program Acceptance established at output of task HS 060 (leaktightness test) After this operation the heat switch must be kept in a clean environment – Put a rubber plug on fill tube
<b><i>OUTPUT DOCUMENTS</i></b>
Certificate of conformity



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 58

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : HS 060</b>
<b><i>TASK NAME</i></b>
Leak Tightness Test
<b><i>OBJECTIVES</i></b>
Verify the leaktightness of the heat switch
<b><i>REQUIRED DOCUMENTATION</i></b>
N/A
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Heat switch partly assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room - Ambient conditions Helium leak detector (mass spectrometer)
<b><i>TASK DESCRIPTION</i></b>
Use appropriate connection to leak detector to check for the leaktightness of the heat switches under vacuum
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Leakrates level must not exceed $10^{-9}$ mB.Ls <sup>-1</sup>
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB – Report outcome in Inspection Sheet (FI)



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 59

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : HS 070</b>
<b><i>TASK NAME</i></b>
Gold Plating
<b><i>OBJECTIVES</i></b>
Gold plating of all external copper surfaces
<b><i>REQUIRED DOCUMENTATION</i></b>
HSO-SBT-SP-044 (Définition des pièces à dorer)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
N/A
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Operation subcontracted – Under subcontractor responsibility
<b><i>TASK DESCRIPTION</i></b>
Gold plate all external copper surfaces (nota : to the exception of the surfaces indicated in HSO-SBT-SP-044) : - heat switches head and base Once switch is back at SBT : perform a leaktightness test : Leakrates level must not exceed $10^{-9}$ mB.Ls <sup>-1</sup>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Work performed in accordance with subcontractor quality program
<b><i>OUTPUT DOCUMENTS</i></b>
Certificate of conformity



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 60

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : HS 080</b>
<b><i>TASK NAME</i></b>
Baking and cleaning of switch
<b><i>OBJECTIVES</i></b>
Perform a baking to remove any trace of pollution from the charcoal pellet - Cleaning of switch external to be under cleanliness and contamination control
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR -026 (Nettoyage)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Heat switch partly assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room - Ambient conditions – Baking chamber equipped with primary pump
<b><i>TASK DESCRIPTION</i></b>
<ol style="list-style-type: none"><li>1. Bake out the heat switch at 80°C under primary vacuum for 12 hours minimum</li><li>2. Clean the switch (procedure HSO-SBT-PR-026)</li></ol>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Heat switch must then remains under clean environment (plastic bag under helium gas is acceptable) and the fill tube must be plugged with a rubber plug.
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB Fill in the “as run procedure”





**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 61

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : HS 90</b>
<b><i>TASK NAME</i></b>
Filling / Crimping of Heat Switch
<b><i>OBJECTIVES</i></b>
Fill the heat switch with $^3\text{He}$ gas and crimp it
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-036 (Remplissage de l'interrupteur) Procedure HSO-SBT-PR-030 (Quesottage)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Heat switch partly assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions. $^3\text{He}$ gas bottle with appropriate manometers and valves. Crimping tool. Soldering tool. Leak detector with the $^3\text{He}$ mass option. Test box (vacuum jacket)
<b><i>TASK DESCRIPTION</i></b>
Follow procedure HSO-SBT-PR-036 and HSO-SBT-PR-030. Summary : <ul style="list-style-type: none"><li>- Leakcheck and then fill the switch</li><li>- Crimp the fill tube / cut it / Soft solder plug it / Release crimp tool</li><li>- Leak test / glue Part ref. B308 on crimped tube</li><li>- Perform final leak test</li></ul>
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Visual check Leakrates level must not exceed $10^{-9}$ mB.Ls $^{-1}$ or vacuum box background measured prior to insertion of switch
<b><i>OUTPUT DOCUMENTS</i></b>
Report in the LLB – Report outcome in Inspection sheet (FI) Fill in the “as run procedure”



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 62

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

<b>TASK NUMBER : HS 100</b>
<b><i>TASK NAME</i></b>
Gluing of Thermometers and heaters / Pre wiring
<b><i>OBJECTIVES</i></b>
Instrument the heat switch with heaters and thermometers
<b><i>REQUIRED DOCUMENTATION</i></b>
Procedure HSO-SBT-PR-033 (Collage, thermalisation et soudure des composants)
<b><i>COOLER AND TEST CONFIGURATION</i></b>
Heat switch almost fully assembled
<b><i>FACILITY AND GROUND SUPPORT EQUIPMENT</i></b>
Clean room – Ambient conditions
<b><i>TASK DESCRIPTION</i></b>
Glue all required heaters and thermometers on the miniature sorption pump using Stycast 2850 FT (see procedure HSO-SBT-PR-033) Pre wire all components using twisted manganin wires 200 µm diameter.
<b><i>ACCEPTANCE CRITERIA AND COMMENTS</i></b>
Visual check Electrical resistance check (component resistance and electrical isolation with regards to switch).
<b><i>OUTPUT DOCUMENTS</i></b>
Report in LLB Fill in the “as run procedure”



**SPIRE & PACS**  
**Sorption Coolers**  
*AIV Plan*

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 63

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/GBT]**

<b>TASK NUMBER : HS 110</b>
<b>TASK NAME</b>
Thermal characterization of heat switch
<b>OBJECTIVES</b>
Thermally characterize the gas gap heat switch
<b>REQUIRED DOCUMENTATION</b>
N/A
<b>COOLER AND TEST CONFIGURATION</b>
Heat switch fully assembled and operational, mounted in test cryostat
<b>FACILITY AND GROUND SUPPORT EQUIPMENT</b>
Clean Room – Ambient conditions. Test cryostat with all relevant associated equipment : secondary vacuum pump, liquid helium level indicator, temperature bridges, power supplies, voltmeters, etc...
<b>TASK DESCRIPTION</b>
Summary of data recorded (two set of tests :bath cryostat (T0) at 4.2 K and 1.6 K): 1. Switch OFF : power transmitted between T0 and T up to 40 K. More data at T close to T0 2. Switch ON : power transmitted between T0 and T up to 10-12 K 3. 25 mW applied on switch hot end. Switch miniature pump heated to 20 K : decrease this temperature and record the associated heating power and corresponding switch thermal conductance (determination of switching temperature).
<b>ACCEPTANCE CRITERIA AND COMMENTS</b>
Results shall be consistent with predictions
<b>OUTPUT DOCUMENTS</b>
Report in LLB – Test report




**SPIRE & PACS  
Sorption Coolers  
AIV Plan**

DOC N° : HSO-SBT-PL-013  
Iss/Rev : 2.3  
DATE : 26/01/2004  
PAGE : 64

**SERVICE DES BASSES TEMPERATURES [CEA/DSM/DRFMC/SBT]**

## 5 Appendix

### 5.1 Health Check Report data sheet

		<p align="center"><b>SPIRE &amp; PACS Sorption Coolers HEALTH CHECK REPORT (HCR)</b> (Version 2.1)</p>		<b>Référence : HCR#</b>			
<b>Référence cryoréfrigérateur :</b> Raison du contrôle :				Date : Nom : Signature :			
<b>Contrôle mécanique / électrique</b> Visuel :							
<b>Tension des brins Kevlar (mesurée coté pompe)</b> Avant test Fil 1/8 :                      Fil 2/8 :                      Après test Fil 1/8 :                      Fil 2/8 :							
<b>Contrôle impédance thermomètres (T) et chauffages (C)</b> (à T ambiante, et comprenant les fils de mesures) (indiquer pour chaque composants les valeurs en Ohm prises au connecteur principal (P) et redondé (R))							
T pompe	C pompe	T inter P	C inter. P	T évaporat.	T inter évap.	C inter évap.	T shunt
/	/	/	/	/	/	/	/
Vérification isolation électrique : Remarques :							
<b>Contrôle de fuite</b>		Référence détecteur :					
Valeur de fuite mesurée / Avant :		Après :		Commentaires :			
<b>Contrôle thermique</b>							
<b>Cycle A – Phase de condensation :</b>							
T bain <sup>4</sup> He	T structure	T pompe/Puiss.	T évaporateur	T inter P	T inter E/Puiss.	T shunt	
<b>Phase basse température – T bain :</b>							
Orientation	+90° (Endroit)	0° (Horizontal)	- 90° (Envers)	Commentaires :			
T mini (mK)							
Courbe de puissance - Orientation : vertical évaporateur en bas (+90) et vertical évaporateur en haut (-90)							
Charge (µW)	0 (Tmini)	10	20	30	40	50	100
T (mK) / +90							
T (mK) / -90							
<b>Cycle B – Phase de condensation :</b>							
T bain <sup>4</sup> He	T structure	T pompe/Puiss.	T évaporateur	T inter P	T inter E/Puiss.	T shunt	
<b>Phase basse température – T bain :</b> Autonomie et température sous 200 µW de charge appliquée : Autonomie et température sous 30 µW de charge appliquée :							
<b>Conformité</b>		OUI NON					
<b>RAPPORT :</b>							
<b>Visa Projet</b> - Nom, date et signature :							