



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

<b>Ref:</b>	SPIRE-RAL-PRC-2704
<b>Issue:</b>	1.0
<b>Date:</b>	15 <sup>th</sup> August 2006
<b>Page:</b>	1 of 31

## 1.INTRODUCTION

This document sets out the procedures to be used during the SPIRE Specific Performance Test which will be carried out at system level as part of the Integrated System Test. The format of the document is identical to that used for the Warm Functional Test Procedures (RD1). In this document only the individual procedures are detailed; neither the timing nor the sequencing of the tests are given or should be implied from the order given in the document. AD01 gives a possible overall sequence and duration for the performance tests. The sequencing of the EMC and thermal tests will be detailed in separate documents.

### 1.1Change Record

Draft 0.1, 17<sup>th</sup> July 2006  
Issue 1.0 15<sup>th</sup> Aug 2006

Draft 0.1  
Issue 1.0 Included detailed procedure for BSM tuning operation  
Several updates for procedure naming  
Spectrometer SCAL check rearranged

### 1.2Applicable Documents

**AD01** Definition of SPIRE testing for FM IST and TV/TB SPIRE-RAL-NOT-002595

### 1.3Applicable Documents

**RD01** SPIRE IST Warm Functional Test Procedures SPIRE-RAL-PRC-002422

**RD02** SPIRE Instrument User Manual, Issue 1.0, SPIRE-RAL-PRJ-002395, 08/04/2005

### 1.4General instructions for executing test procedures

- Before executing any of the procedures please always check with the Instrument-EGSE staff
- Any text in **boldface** in the procedural steps generally indicates an action which has to be performed manually by the I-EGSE staff.
- The last row in a procedure table should be used to record the overall Pass/Fail result of each test.



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

<b>Ref:</b>	SPIRE-RAL-PRC-2704
<b>Issue:</b>	1.0
<b>Date:</b>	15 <sup>th</sup> August 2006
<b>Page:</b>	2 of 31

### 1.5 Assumptions

- The CCS is only required to check changes in instrument configuration related HK parameters.
- For each test the instrument will be in a pre-defined mode as listed in the IUM (**RD02**).
- For the SPIRE spectrometer mechanism (SMECm) tests it is assumed that the Herschel cryostat will be tilted such that the plane of the Herschel Optical Bench (HOB) is vertical and the SPIRE Optical Bench (SOB) is horizontal.
- For the SPIRE Cooler recycle it is assumed that the Herschel cryostat will be tilted such that the plane of the SOB is at, at least, 30 degrees from the vertical with the +Y Spacecraft axis downwards
- These procedures should be suitable for operation of both the Prime and Redundant side of the instrument (TBD).
- Several manual procedures are present in this document for which TCL scripts are used for command sequence generation. These procedures require minimal action from the CCS operator and will be clearly explained within this document.
- **The converted TM parameter values are extracted from the MIB in use for PFM ILT. These values are subject to change for both prime and redundant operations.**

### 1.6 Open Issues

- Sorption pump heat switch and Evaporator heat switch expected voltages for manual cooler recycle procedure are to be confirmed during ILT PFM4 test campaign at RAL,.
- The use of Spire Burst Mode during Photometer Most Sensitive mode is TBC.

### 1.7 Duration

The estimated duration for executing the entire sequence of procedures, including switch off of the SPIRE instrument afterwards is estimated to be about **5 days (see AD1)**



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

<b>Ref:</b>	SPIRE-RAL-PRC-2704
<b>Issue:</b>	1.0
<b>Date:</b>	15 <sup>th</sup> August 2006
<b>Page:</b>	3 of 31

## 2.TEST PROCEDURES

The following is a list of the test procedures that can be found in this document:

- Procedure: BSM Control Loop Setting
- Procedure: Cooler recycle (manual)
- Procedure: Cooler recycle (automatic)
- Procedure: Photometer bias optimisation
- Procedure: Photometer Ambient Background Verification
- Procedure: PTC Headroom Characterisation
- Procedure: Spectrometer bias optimisation
- Procedure: Spectrometer Ambient Background Verification
- Procedure: Photometer scan mode POF5
- Procedure: Photometer chop/jiggle mode POF2
- Procedure: SPEC high resolution mode SOF1
- Procedure: Spectrometer Micro vibration Test
- Procedure: Spectrometer SCAL check
- Procedure: Photometer Thermal Control Verification
- Procedure: EMC - Photometer most sensitive mode
- Procedure: EMC – Spectrometer most sensitive mode
- Procedure: EMC – SPIRE most Emissive mode
- Procedure: 300mK Stage Decontamination



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

<b>Ref:</b>	SPIRE-RAL-PRC-2704
<b>Issue:</b>	1.0
<b>Date:</b>	15 <sup>th</sup> August 2006
<b>Page:</b>	4 of 31

### 2.1 Procedure: BSM Control Loop Setting

**Version:** 1.0

**Date:** 17<sup>th</sup> July 2006

**Purpose:** To optimize the PID control loop for BSM best dynamic behaviour

**Duration:** 60 minutes

**Preconditions:**

- Functional tests SPIRE-IST-FUNC-BSM-01,02,03 have been carried out successfully
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal

**Initial Configuration:**

- SPIRE is in REDY mode

**Procedure Steps:**



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 5 of 31

Step#	Action	Comments										
1	Execute SPIRE-IST-BSM-ON.tcl template	This switches ON the BSM magneto resistive sensors										
2	Wait for SPIRE staff to update the default on/off source positions for the chop throw.											
3	Start chopping the BSM by pressing ok in the popup window with the message “ <i>Start Chopping</i> ”											
4	Update PID settings by manually commanding the instrument The SPIRE personnel will be passing to the operator the command parameters to input as part of the tuning process.	<p>All the commands used for the PID tuning have the following SPIRE MIB mnemonic:</p> <p>SPIRE_SEND_DRCU_COMMAND() The command parameters used for PID tuning are :</p> <p>Parameter 1: (ANY of the following):</p> <table><tr><td>Chop axis tuning:</td><td>Jiggle axis tuning</td></tr><tr><td>0x90C8xxxx</td><td>0x9148xxxx</td></tr><tr><td>0x90C9xxxx</td><td>0x9149xxxx</td></tr><tr><td>0x90CAxxxx</td><td>0x914Axxxx</td></tr><tr><td>0x90CFxxxx</td><td>0x9151xxxx</td></tr></table> <p>Where xxxx denotes the PID parameter value to be changed.</p> <p>Parameter 2: Override = 0</p> <p>e.g : SEND_DRCU_COMMAND(0x90C8xxxx,0)</p>	Chop axis tuning:	Jiggle axis tuning	0x90C8xxxx	0x9148xxxx	0x90C9xxxx	0x9149xxxx	0x90CAxxxx	0x914Axxxx	0x90CFxxxx	0x9151xxxx
Chop axis tuning:	Jiggle axis tuning											
0x90C8xxxx	0x9148xxxx											
0x90C9xxxx	0x9149xxxx											
0x90CAxxxx	0x914Axxxx											
0x90CFxxxx	0x9151xxxx											
5	Repeat steps 2 to 4 for another set of the chop on/off source positions.											
6	Press ok to stop the current test											
7	Switch OFF BSM mechanism Execute SPIRE-IST-BSM-OFF.tcl											

**Final Configuration:**  
SPIRE in REDY



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 6 of 31

## 2.2 Procedure: Cooler recycle (manual)

**Version:** 1.0

**Date:** 24<sup>th</sup> July 2006

**Purpose:**

Recycle the cooler to provide the correct operating temperature for the detectors.

This procedure is carried out with operator intervention to ensure the correct conditions are obtained during the recycle and to properly calibration the duration of each phase of the recycle. Once the calibration is obtained an automatic procedure will be used that does not require operator intervention (see section 2.3)

**Duration:**

**About 2 hours**

**Preconditions:**

- Functional test SPIRE-IST-FUNC-SCU-07 has been carried out successfully.
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- Herschel tilted such that SOB is tilted at at least 30 degrees from vertical towards +Y direction

**Initial Configuration:**

SPIRE in REDY mode

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script SPIRE-IST-CRECM.tcl <ul style="list-style-type: none"> <li>• Click on OK button to turn off Pump Heat Switch (whether it is on or off)</li> <li>• Apply 1.4 mA to the Evaporator Heat Switch</li> </ul>	STEP Time (UT)  EVHSV PUMPHSTEMP EVAPHSTEMP	1   TBC TBC TBC		
2	Wait for PUMPHSTEMP to go just below 12 K and then click on OK to	STEP	2		



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

Ref: SPIRE-RAL-PRC-2704  
Issue: 1.0  
Date: 15<sup>th</sup> August 2006  
Page: 7 of 31

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
	apply 300 mW power to Pump Heater	<i>Time (UT)</i> <i>ΔTime (minutes)</i>  SPHTRV	   TBC		
3	Wait for PUMPHTRTEMP to increase to 45 K and then click on OK to reduce power to Pump Heater to 40mW	STEP <i>Time (UT)</i> <i>ΔTime (minutes)</i>  SPHTRV PUMPHTRTEMP	3   TBC TBC		
4	Wait for SUBKTEMP to fall below 2 K and then click on OK to switch off power to the Pump Heater and Evaporator Heat Switch.  <b>IMPORTANT:</b> This step should be executed even if SUBKTEMP is above 2 K but more than an hour has elapsed since the start of the recycle procedure.	STEP <i>Time (UT)</i> <i>ΔTime (minutes)</i>  EVHSV SPHTRV PUMPHSTEMP EVAPHSTEMP	4   TBC TBC TBC TBC		
5	Wait for EVAPHSTEMP to fall below ~ 16 K and then click on OK to switch on power to the Pump Heat Switch  <i>The TCL script ends after execution of this step</i>	STEP <i>Time (UT)</i> <i>ΔTime (minutes)</i>  SPHSV SUBKTEMP PUMPHSTEMP	5   TBC TBC TBC		
6	<b>Monitor SUBKTEMP and PUMPHSTEMP.</b>  <i>Cooler recycle procedure completes when SUBKTEMP reaches ~ 0.285 K and PUMPHSTEMP reaches ~TBC K.</i>	<i>Time (UT)</i> <i>ΔTime (minutes)</i>  SUBKTEMP PUMPHSTEMP	   < 300mK TBC		



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 8 of 31

Step	Description	Parameters	Expected Values	Actual Values	Success/ Failure

**Final Configuration:**

SPIRE in REDY mode with cooler recycled and detectors at  $\leq 300$  mK





## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 9 of 31

### 2.3 Procedure: Cooler recycle (automatic)

**Version:** 1.0

**Date:** 24<sup>th</sup> July 2006

**Purpose:**

Recycle the cooler without operator intervention

**Duration:**

Approximately 2 hours

**Preconditions:**

- Functional test SPIRE-IST-FUNC-SCU-07 has been carried out successfully.
- Manual recycle carried out under nominal temperature and cryostat operational conditions
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- Herschel tilted such that SOB is tilted at at least 30 degrees from vertical towards +Y direction

**Initial Configuration:**

SPIRE in REDY mode

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script SPIRE-IST-CRECa.tcl	SUBKTEMP	AFTER RECYCLE < 300mK		

**Test Result (Pass/Fail):**

**Duration of SPIRE Cooler Recycle Procedure:**

**Final Configuration:**

SPIRE in REDY mode with cooler recycled and detectors at  $\leq 300$  mK



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 10 of 31

## 2.4 Procedure: Photometer

### bias optimisation

**Version:** 1.0

**Date:** 24<sup>th</sup> July 2006

**Purpose:**

Find the optimum bias level and frequency for operating the photometer under IST ground nominal conditions

**Duration:**

Approximately 4 hours

**Preconditions:**

- Functional tests SPIRE-IST-FUNC-DCU-04P,13P has been carried out successfully.
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible

**OPEN ISSUE – do we want the PTC operating during this test – see test 2.6?**

**Initial Configuration:**

SPIRE in PHOT STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script SPIRE-IST-PDET-ON.tcl <ul style="list-style-type: none"> <li>• Switch on detectors using ILT determined setting</li> <li>• Observe signals and ensure correct profile is observed during JFET switch on</li> </ul>	PLIABITSTAT	1	-	
2	Execute TCL script SPIRE-IST-PHASEUP-P.tcl <ul style="list-style-type: none"> <li>• Observe signal levels and determine optimum phase setting for ILT bias levels – this is the starting point</li> </ul>	N/A	N/A	N/A	
3	Execute TCL script SPIRE-IST-DNA-P.tcl	N/A	N/A	N/A	



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 11 of 31

Step	Description	Parameters	Expected Values	Actual Values	Success/ Failure
	<ul style="list-style-type: none"> <li>Set frequency to 70 Hz and ILT nominal</li> <li>Phase up</li> <li>Set Frequency to each predetermined level and phase up at each in turn - observe maximum signal at each level and measure noise</li> <li>Set frequency to 100 Hz and ILT nominal</li> <li>Phase up</li> <li>Set Frequency to each predetermined level and phase up at each in turn - observe maximum signal at each level and measure noise</li> <li>Set frequency to 130 Hz and ILT nominal</li> <li>Phase up</li> <li>Set Frequency to each predetermined level and phase up at each in turn - observe maximum signal at each level and measure noise</li> <li>Set frequency to 190 Hz and ILT nominal</li> <li>Phase up</li> <li>Set Frequency to each predetermined level and phase up at each in turn - observe maximum signal at each level and measure noise</li> <li>Set to ILT nominal values</li> </ul>				
4	Analyse data in real time to determine IST ground nominal operating parameters				
<b>Test Result (Pass/Fail):</b>					
<b>Approximate optimum bias settings each detector:</b> <div> <div>Bias Level</div> <div>Frequency</div> <div>Phase</div> </div> <div> <div>PSW</div> <div>PMW</div> <div>PLW</div> </div>					

### Final Configuration:

SPIRE in PHT STBY mode with bias set to ILT nominal values



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 12 of 31

### 2.5 Procedure: Photometer Ambient Background Verification

**Version:** 1.0

**Date:** 24<sup>th</sup> July 2006

**Purpose:**

Determine the optical power load onto the photometer detectors using a detector “loadcurve” at fixed frequency and phase to measure the detector temperature.

**Duration:**

Approximately 45 minutes

**Preconditions:**

- Photometer IST Ground Nominal bias setting have been determined by procedure “Photometer bias optimisation”
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible

**Initial Configuration:**

SPIRE is set to PHOT STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script SPIRE-IST-LC-P.tcl •	N/A	N/A	N/A	
<b>Test Result (Pass/Fail):</b>					

**Final Configuration:**

SPIRE in PHOT STBY mode with bias set to IST Ground Nominal

### 2.6 Procedure: PTC Headroom Characterisation

**Version:** 1.0



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 13 of 31

**Date:** 24<sup>th</sup> July 2006

**Purpose:** Determine the required PTC power setting required to enable stable operation of the photometer detectors under Ground Nominal conditions.

**Duration:** Approximately 4 hours

**Preconditions:**

- Functional test SPIRE-IST-FUNC-DCU-13P has been carried out successfully
- Photometer IST Ground Nominal bias settings have been determined by procedure "Photometer bias optimisation"
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible

**Initial Configuration:**

SPIRE is set to PHOT STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script SPIRE-IST-PTC-PWR.tcl <ul style="list-style-type: none"> <li>• Set PTC to first level</li> <li>• Wait 30 minutes (TBD) – observe PTC thermistor and detector signals</li> <li>• <i>Loop n-times</i></li> <li>• Set PTC heater power to n'th level +1</li> <li>• Wait 30 minutes (TBD) – observe PTC thermistor and detector signals</li> </ul>	N/A	N/A	N/A	
<b>Test Result (Pass/Fail):</b>					
<b>PTC power level required to stabilise typical thermal drift</b>					

**Final Configuration:**

SPIRE in PHOT STBY mode with bias set to IST Ground Nominal



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 14 of 31

## 2.7 Procedure: Spectrometer bias optimisation

**Version:** 1.0

**Date:** 24<sup>th</sup> July 2006

**Purpose:**

Find the optimum bias level and frequency for operating the spectrometer under IST ground nominal conditions

**Duration:**

Approximately 4 hours

**Preconditions:**

- Functional tests SPIRE-IST-FUNC-DCU-04S,13S been carried out successfully.
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible

**Initial Configuration:**

SPIRE in SPEC STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script SPIRE-IST-SDET-ON.tcl <ul style="list-style-type: none"> <li>• Switch on detectors using ILT determined setting</li> <li>• Observe signals and ensure correct profile is observed during JFET switch on</li> </ul>	SLIABISTAT	1	-	
2	Execute TCL script SPIRE-IST-PHASEUP-S.tcl <ul style="list-style-type: none"> <li>• Observe signal levels and determine optimum phase setting for ILT bias levels – this is the starting point</li> </ul>	N/A	N/A	N/A	
3	Execute TCL script SPIRE-IST-DNA-S.tcl <ul style="list-style-type: none"> <li>• Set frequency to 100 Hz and ILT nominal</li> <li>• Phase up</li> </ul>	N/A	N/A	N/A	



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 15 of 31

Step	Description	Parameters	Expected Values	Actual Values	Success/ Failure
	<ul style="list-style-type: none"> <li>Set Frequency to each predetermined level and phase up at each in turn - observe maximum signal at each level and measure noise</li> <li>Set frequency to 160 Hz and ILT nominal</li> <li>Phase up</li> <li>Set Frequency to each predetermined level and phase up at each in turn - observe maximum signal at each level and measure noise</li> <li>Set frequency to 240 Hz and ILT nominal</li> <li>Phase up</li> <li>Set Frequency to each predetermined level and phase up at each in turn - observe maximum signal at each level and measure noise</li> <li>Set to ILT nominal values</li> </ul>				
4	Analyse data in real time to determine IST ground nominal operating parameters	N/A	N/A	N/A	
<b>Test Result (Pass/Fail):</b>					
<b>Approximate optimum bias settings each detector:</b>					
	<b>Bias Level</b>	<b>Frequency</b>	<b>Phase</b>		
SSW					
SLW					

### Final Configuration:

SPIRE in SPEC STBY mode with bias set to ILT nominal values



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 16 of 31

## 2.8 Procedure: Spectrometer Ambient Background Verification

**Version:** 1.0

**Date:** 24<sup>th</sup> July 2006

**Purpose:**

Determine the optical power load onto the photometer detectors using a detector “loadcurve” at fixed frequency and phase to measure the detector temperature.

**Duration:**

Approximately 45 minutes

**Preconditions:**

- Spectrometer IST Ground Nominal bias setting have been determined by procedure “Spectrometer bias optimisation”
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible

**Initial Configuration:**

SPIRE is set to PHOT STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script SPIRE-IST-LC-S.tcl •	N/A	N/A		
<b>Test Result (Pass/Fail):</b>					

**Final Configuration:**

SPIRE in SPEC STBY mode with bias set to IST Ground Nominal





## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 17 of 31

## 2.9 Procedure: Photometer

### scan mode POF5

**Version:** 1.0

**Date:** 24th July 2006

**Purpose:** To exercise the photometer POF5 AOT – also sets photometer mode for thermal tests etc

**Duration:** Indeterminate – depends on master procedure

**Preconditions:**

- Photometer IST Ground Nominal bias setting have been determined by procedure “Photometer bias optimisation”
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible
- “PTC Headroom” procedure has been carried out and power setting has been determined

**Initial Configuration:**

SPIRE in PHOT STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script SPIRE-IST-PHOTO-LARGE-SCAN.tcl <i>Open issue do we use PTC Control Procedure here?</i>	N/A	N/A		
<b>Test Result (Pass/Fail):</b>					

**Final Configuration:**

SPIRE in PHOT STBY



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 18 of 31

### 2.10 Procedure: Photometer chop/jiggle mode POF2

**Version:** 1.0

**Date:** 24th July 2006

**Purpose:**

To exercise the photometer POF2 AOT – also sets photometer mode for thermal tests etc

**Duration:**

Indeterminate – depends on master procedure

**Preconditions:**

- Photometer IST Ground Nominal bias setting have been determined by procedure “Photometer bias optimisation”
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible
- “PTC Headroom” procedure has been carried out and power setting has been determined

**Initial Configuration:**

SPIRE in PHOT STBY

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script SPIRE-IST-AOT-PHOTO-POINT-JIGGLE.tcl	N/A	N/A		
<b>Test Result (Pass/Fail):</b>					

**Final Configuration:**

SPIRE in PHOT STBY



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 19 of 31

### 2.11 Procedure: SPEC high resolution mode SOF1

**Version:** 1.0

**Date:** 24th July 2006

**Purpose:**

To exercise the photometer SOF1 AOT – also sets photometer mode for thermal tests etc

**Duration:**

Indeterminate – depends on master procedure

**Preconditions:**

- Spectrometer IST Ground Nominal bias setting have been determined by procedure “Spectrometer bias optimisation”
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible
- Herschel tilted such that SOB is horizontal

**Initial Configuration:**

SPIRE in SPEC STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script SPIRE-IST-AOT-SPECTRO-SCAN-POINT.tcl	N/A	N/A		
<b>Test Result (Pass/Fail):</b>					

**Final Configuration:**

SPIRE in SPEC STBY



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 20 of 31

### 2.12 Procedure: Spectrometer Microvibration Test

**Version:** 1.0

**Date:** 24th July 2006

**Purpose:**

Evaluate the influence of space craft systems on the performance of the SPIRE spectrometer mechanism

**Duration:**

Approximately 2 hours

**Preconditions:**

- Spectrometer IST Ground Nominal bias setting have been determined by procedure “Spectrometer bias optimisation”
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible
- Herschel tilted such that SOB is horizontal
- Initially S/C reaction wheels are stationary
- Acoustic and vibrational environment is as quiet as possible – night time operation?

**Initial Configuration:**

SPIRE in SPEC STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute SPIRE-IST-SMEC-MICROVIBRATION.TCL Generate high rate SMEC science data – we are looking for fluctuations in SMEC velocity Scan SMEC at 0.1 mm/s over full range for four scans Scan SMEC at 0.2 mm/s over full range for four scans Scan SMEC at 0.3 mm/s over full range for four scans	N/A	N/A	N/A	



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 21 of 31

Step	Description	Parameters	Expected Values	Actual Values	Success/ Failure
	Scan SMEC at 0.5 mm/s over full range for four scans				
2	Switch on S/C reaction wheels at TBD Hz	N/A	N/A	N/A	
3	Repeat scan procedure	N/A	N/A	N/A	
4	Switch reaction wheels to TBD Hz	N/A	N/A	N/A	
5	Repeat scan procedure	N/A	N/A	N/A	
6					
<b>Test Result (Pass/Fail):</b>					

**Final Configuration:**  
SPIRE in SPEC STBY



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 22 of 31

### 2.13 Procedure: Spectrometer SCAL check

**Version:** 1.0

**Date:** 24th July 2006

**Purpose:**

Check calibration of spectrometer calibrator

**Duration:**

Approximately 2 hours

**Preconditions:**

- Spectrometer IST Ground Nominal bias setting have been determined by procedure “Spectrometer bias optimisation”
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible
- Herschel tilted such that SOB is horizontal

**Initial Configuration:**

SPIRE in SPEC STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Set SCAL4 to TBD K Execute SPIRE-IST-SCAL4-WARMUP.TCL Wait for SCAL4 to reach TBD K	N/A	N/A	N/A	
2	Execute TCL script SPIRE-IST-LC-S.tcl	N/A	N/A	N/A	
3	Execute TCL script to scan SMEC at nominal velocity at high resolution Execute SPIRE-IST-SMEC-SCAN.TCL	N/A	N/A	N/A	
4	Switch off SCAL4 Constantly scan SMEC at nominal velocity at high resolution while SCAL4	N/A	N/A	N/A	



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 23 of 31

Step	Description	Parameters	Expected Values	Actual Values	Success/ Failure
	<p>cools</p> <p>The next step will run a TCL script which performs these tasks: Execute SPIRE-IST-SCAL4-COOLDOWN.TCL</p> <ol style="list-style-type: none"> <li>1. Press ok to Switch off SCAL4</li> <li>2. Wait for SPIRE staff go ahead</li> <li>3. Press ok to to constantly scan SMEC at nominal velocity at high resolution while SCAL4 cools</li> <li>4. Wait for SPIRE staff go ahead</li> <li>5. Press ok to reset offsets</li> <li>6. Wait for SPIRE staff go ahead</li> <li>7. Repeat steps 5 and 6 within this subsequence for n times</li> </ol> <p>Press Ok to stop scanning</p>				
5	Wait until SCAL4 is <6 K (~15 minutes)	N/A	N/A	N/A	
6	<p>Set SCAL2 to TBD K</p> <p>Execute SPIRE-IST-SCAL2-WARMUP.TCL</p> <p>Wait for SCAL2 to reach TBD K</p>	N/A	N/A	N/A	
7	Execute TCL script SPIRE-IST-LC-S.tcl	N/A	N/A	N/A	
8	<p>Execute TCL script to scan SMEC at nominal velocity at high resolution</p> <p>Execute SPIRE-IST-SMEC-SCAN.TCL</p> <p>Press ok to stop scanning when prompted.</p>	N/A	N/A	N/A	
7	<p>The next step will run a TCL script which performs several tasks: Execute SPIRE-IST-SCAL2-COOLDOWN.TCL</p> <ol style="list-style-type: none"> <li>8. Press ok to Switch off SCAL2</li> <li>9. Wait for SPIRE staff go ahead</li> <li>10. Press ok to to constantly scan SMEC at nominal velocity at high resolution while SCAL2 cools</li> <li>11. Wait for SPIRE staff go ahead</li> <li>12. Press ok to reset offsets</li> <li>13. Wait for SPIRE staff go ahead</li> </ol>	N/A	N/A	N/A	



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 24 of 31

Step	Description	Parameters	Expected Values	Actual Values	Success/ Failure
	14. Repeat steps 5 and 6 within this subsequence for n times9Press Ok to stop scanning				
8					
<b>Test Result (Pass/Fail):</b>					

**Final Configuration:**  
SPIRE in SPEC STBY





## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 25 of 31

### 2.14 Procedure: Photometer Thermal Control Verification

**Version:** 1.0

**Date:** 24th July 2006

**Purpose:**

To test detector thermal stability whilst under PTC control – this can be carried out at any point

**Duration:**

Indeterminate - see AD1

**Preconditions:**

- Functional test SPIRE-IST-FUNC-DCU-13P has been carried out successfully
- Photometer IST Ground Nominal bias settings have been determined by procedure “Photometer bias optimisation”
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible
- The “PTC Headroom” procedure has been carried out and the optimum PTC power setting has been established

**Initial Configuration:**

SPIRE is in PHOT STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script to switch PTC to on and in VM control mode Execute SPIRE-IST-PTC-VM.tcl	N/A	N/A	N/A	
<b>Test Result (Pass/Fail):</b>					

**Final Configuration:**

SPIRE is in PHOT STBY with detector temperature under PTC control



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 26 of 31

### 2.15 Procedure: EMC - Photometer most sensitive mode

**Version:** 1.0

**Date:** 24th July 2006

**Purpose:**

Sets SPIRE into the mode used for EMC susceptibility testing for photometer

**Duration:**

Indeterminate see EMC test procedure

**Preconditions:**

- Photometer IST Ground Nominal bias setting have been determined by procedure “Photometer bias optimisation”
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible

**Initial Configuration:**

SPIRE is in PHOT STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script to set photometer bias frequency to highest compatible with low noise with corresponding phase set and detector sampling to as fast as practicable. <b>IEGSE staff: Specify this settings as default s for the Mode_ILT_PERF-DNS-P CUS mode in the database</b> Then Execute SPIRE-IST-DNS-P.tcl template	N/A	N/A	N/A	
<b>Test Result (Pass/Fail):</b>					

**Final Configuration:**



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 27 of 31

rate

SPIRE is in PHOT OBSV with high data



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 28 of 31

### 2.16 Procedure: EMC – Spectrometer most sensitive mode

**Version:** 1.0

**Date:** 24th July 2006

**Purpose:** Sets SPIRE into the mode used for EMC susceptibility testing for photometer

**Duration:** Indeterminate see EMC test procedure

**Preconditions:**

- Spectrometer IST Ground Nominal bias setting have been determined by procedure “Spectrometer bias optimisation”
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- The cooler is recycled, the detectors are at <300 mK and the detector temperatures are as stable as possible

**Initial Configuration:**

SPIRE is in SPEC STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute TCL script to set spectrometer bias frequency to highest compatible with low noise with corresponding phase set and detector sampling to as fast as practicable. <b>IEGSE staff: Specify this settings as default s for the Mode_ILT_PERF-DNS-S CUS mode in the database</b> Then Execute SPIRE-IST-DNS-S.tcl template	N/A	N/A	N/A	
<b>Test Result (Pass/Fail):</b>					

**Final Configuration:** SPIRE is in SPEC OBSV with detector sampling at high rate



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 29 of 31

## 2.17 Procedure: EMC – SPIRE

### most Emissive mode

**Version:** 1.0

**Date:** 24th July 2006

**Purpose:**

Sets SPIRE into what we assume will be the most emissive mode – i.e. scanning the spectrometer mechanism

**Duration:**

Indeterminate – see EMC test procedure

**Preconditions:**

- Spectrometer IST Ground Nominal bias setting have been determined by procedure “Spectrometer bias optimisation”
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- Herschel tilted such that SOB is horizontal
- It is not necessary to have the cooler recycled but if it is that is o.k. too

**Initial Configuration:**

SPIRE is in REDY or SPEC STBY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	If SPIRE is in SPECSTBY go to step 3. If SPIRE is in REDY Execute SPIRE-IST-SDET-ON.tcl , then go to step 2	MODE	REDY or SPECSTBY		
2	Execute procedure to initialise spectrometer mechanism if in REDY mode Execute SPIRE-IST-SMEC-INIT.tcl	N/A	N/A	N/A	
3	Execute procedure to set spectrometer mechanism to constant scanning over low resolution at nominal velocity Execute SPIRE-IST-SMEC-SCAN.tcl	N/A	N/A	N/A	



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 30 of 31

Step	Description	Parameters	Expected Values	Actual Values	Success/ Failure
3	Wait for operator instruction to stop scanning	N/A	N/A	N/A	
4	If SPIRE was in REDY mode Execute procedure to switch off spectrometer mechanism Execute SPIRE-IST-SMEC-OFF.tcl Then go to step 5	N/A	N/A	N/A	
5	Execute SPIRE-IST-SDET-OFF.tcl	N/A	N/A	N/A	
<b>Test Result (Pass/Fail):</b>					

### Final Configuration:

SPIRE is mode we started from – REDY or SPEC STBY



## Spire Procedure

SPIRE IST Specific Performance Test Procedures  
Prepared by B.M.Swinyard & A.A.Aramburu

**Ref:** SPIRE-RAL-PRC-2704  
**Issue:** 1.0  
**Date:** 15<sup>th</sup> August 2006  
**Page:** 31 of 31

## 2.18 Procedure: 300mk Stage

### Decontamination

**Version:** 1.0

**Date:** 15th August 2006

**Purpose:**

To remove any traces of Helium deposited over the 300mK stage during the SPT testing

**Duration:**

2hr- 4hr

**Preconditions:**

- Functional test SPIRE-IST-FUNC-SCU-07 has been carried out successfully.
- SPIRE is at ground nominal operating temperature and temperatures are as stable as possible
- Cryostat flow rates are at ground nominal
- Herschel tilted such that SOB is tilted at at least 30 degrees from vertical towards +Y direction

**Initial Configuration:** SPIRE is in REDY

**Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/Failure
1	Execute SPIRE-IST-DECONTAMINATE.tcl	MODE	REDY		
<b>Test Result (Pass/Fail):</b>					

**Final Configuration:**

SPIRE is mode we started from – REDY