



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref:	SPIRE-RAL-PRC-2422
Issue:	2.4
Date:	16 th October 2007
Page:	1 of 115

1. INTRODUCTION

This document describes the procedures to verify the correct functioning of all SPIRE FM subsystems at warm condition **before** instrument cool down. **Both PRIME and REDUNDANT instrument are to be tested within the sequence.** These procedures require the presence of the SPIRE personnel as the I-EGSE will be required to assess the results of part of test data.

1.1 Scope

This procedure has been designed for the checkout of the FM instrument.

1.2 Change Record

Doc	#	Changes	Date of Change
Issue	2.0	Changes included to transform into FM version	13/06/2006
	2.1	<ul style="list-style-type: none"> - Rearranged Section 1. - Inserted Section 2.1 to specify a general Pass/Fail Criterion. - Removed Functional Test FUNC-BSM-06 as this functionality check is already covered by FUNC-BSM-5b - Removed Functional Test FUNC-SMEC-04b as there is no extra functionality checked by this test that is not covered by the rest SMEC tests. - Corrected typo in Section 1.7: (CFT instead of WFT) - Corrected several typos/mismatches in Section 2: <ul style="list-style-type: none"> o <i>Procedure 2.3.8</i> : FUNC-SCU-07 voltages from EVHSV and SPHSV were swapped Minor updates in the steps of procedures. o <i>Procedure 2.3.20</i>: Typo on BSM-05b for template to execute. o <i>Procedure 2.3.34</i>: FUNC-DCU-03 frame count parameter value corrected o <i>Procedure 2.3.35</i>: Typo on FUNC-DCU-11P 	16/08/2006
	2.2	Several changes introduced for final version <ul style="list-style-type: none"> • Included manual commanding for functional test FUNC-SMEC-01 	02/01/2006
	2.3	<ul style="list-style-type: none"> • Removed all references to AVM tests • Removed all references to He I & He II conditions • Changed test sequence to group SMEC Prime & Redundant tests together. • Revised the duration of tests • Updated the safe switch off sequence in case of an anomaly. • Added the LPU test procedures 	5 th Sept 2007



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref:	SPIRE-RAL-PRC-2422
Issue:	2.4
Date:	16 th October 2007
Page:	2 of 115

	2.4	<ul style="list-style-type: none"> • Editorial changes following comments from Bernard Collaudin and the first WFT on 26th Sept 2007. • Table of contents updated • References to SCOS displays corrected for some procedures 	16 th Oct 2007
--	-----	---	---------------------------

1.3 Applicable Documents

AD#	Title	Reference	Issue#	Date
AD01	SPIRE Functional Test Specification	SPIRE-RAL-DOC-001652	1.4	22/07/2005
AD02	SPIRE ILT Warm Functional Test Procedure	SPIRE-RAL-PRC-002322	1.2	27/01/2006

1.4 Reference Documents

RD#	Title	Reference	Issue#	Date
RD01	SPIRE Instrument User Manual	SPIRE-RAL-PRJ-002395	1.1	10/04/2006

1.5 Open Issues

1.6 Duration

The estimated duration for executing the entire procedure, PRIME and REDUNDANT sequences, is approximately **8 hours**.

1.7 List of Acronyms

AND	Alpha Numeric Display
AVM	Avionics Model
BSM	Beam Steering Mirror
CCS	Central Checkout System
CDMU	Command and Data Management Unit
DCU	Detector Control Unit
DPU	Digital Processing Unit
DRCU	Detector Readout and Control Unit
EGSE	Electrical Ground Support Equipment
FM	Flight Model
FPU	Focal Plane Unit
I-EGSE	Instrument EGSE
IST	Integrated Systems Test
LCL	Latch Current Limiter
LIA	Lock In Amplifier
LPU	Latch Power Unit (External)
MCU	Mechanism Control Unit
MTL	Mission Time Line



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-
2422
Issue: 2.4
Date: 16th October 2007
Page: 3 of 115

OBT	On Board Time
OOL	Out Of Limit
RMS	Reference Mission Scenario
SMEC	Spectrometer Mechanism
VM	Virtual Machine



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-
2422
Issue: 2.4
Date: 16th October 2007
Page: 4 of 115

1.	INTRODUCTION	1
1.1	Scope.....	1
1.2	Change Record.....	1
1.3	Applicable Documents.....	2
1.4	Reference Documents	2
1.5	Open Issues	2
1.6	Duration	2
1.7	List of Acronyms	2
2.	Test Configuration.....	7
2.1	FM Test Configuration	7
3.	WARM FUNCTIONAL TEST PROCEDURES OVERVIEW	7
3.1	General instructions for executing test procedures	7
3.2	General Pass/Fail criterion	8
3.3	Constraints	8
3.4	Test Sequence	8
4.	DETAILED WARM FUNCTIONAL TEST PROCEDURES.....	13
4.1	PRIME Instrument.....	13
4.1.1	Procedure SPIRE-FM-WFT-DPU-ON-P	13
4.1.2	Procedure SPIRE-FM-WFT-DRCU-ON-P	15
4.1.3	Procedure SPIRE-FM-WFT-FUNC-SCU-01-P.....	16
4.1.4	Procedure SPIRE-FM-WFT-FUNC-SCU-03-P.....	17
4.1.5	Procedure SPIRE-FM-WFT-FUNC-SCU-06-P.....	18
4.1.6	Procedure SPIRE-FM-WFT-FUNC-SCU-02-P.....	19
4.1.7	Procedure SPIRE-FM-WFT-FUNC-SCU-07-P.....	20
4.1.8	Procedure SPIRE-FM-WFT-FUNC-SCU-04-P.....	21
4.1.9	Procedure SPIRE-FM-WFT-FUNC-SCU-05-P.....	22
4.1.10	Procedure SPIRE-FM-WFT-FUNC-SCU-08-P.....	23
4.1.11	Procedure SPIRE-FM-WFT-FUNC-MCU-01-P	24
4.1.12	Procedure: SPIRE-FM-WFT-FUNC-MCU-02-P	25
4.1.13	Procedure: SPIRE-FM-WFT-FUNC-MCU-03-P	26
4.1.14	Procedure: SPIRE-FM-WFT-FUNC-MCU-04-P	27
4.1.15	Procedure SPIRE-FM-WFT-FUNC-BSM-01-P.....	28
4.1.16	Procedure SPIRE-FM-WFT-FUNC-BSM-02C-P	29
4.1.17	Procedure SPIRE-FM-WFT-FUNC-BSM-02J-P	30
4.1.18	Procedure SPIRE-FM-WFT-FUNC-BSM-03-P.....	31
4.1.19	Procedure SPIRE-FM-WFT-FUNC-BSM-05A-P	32
4.1.20	Procedure SPIRE-FM-WFT-FUNC-BSM-05B-P	33
4.1.21	Procedure SPIRE-FM-WFT-FUNC-BSM-06-P.....	34
4.1.22	Procedure SPIRE-FM-WFT-BSM-OFF-P	35
4.1.23	Procedure SPIRE-FM-WFT-FUNC-SMEC-01-P	36
4.1.24	Procedure SPIRE-FM-WFT-FUNC-SMEC-03-P	37
4.1.25	Procedure SPIRE-FM-WFT-FUNC-SMEC-02A-P	38
4.1.26	Procedure SPIRE-FM-WFT-FUNC-SMEC-04A-P	39
4.1.27	Procedure SPIRE-FM-WFT-FUNC-SMEC-09-P	40
4.1.28	Procedure SPIRE-FM-WFT-FUNC-SMEC-07-P	41
4.1.29	Procedure SPIRE-FM-WFT-FUNC-SMEC-02B-P	42
4.1.30	Procedure SPIRE-FM-WFT-SMEC-OFF-P	43
4.1.31	Procedure SPIRE-FM-WFT-FUNC-DCU-01-P.....	44
4.1.32	Procedure SPIRE-FM-WFT-FUNC-DCU-02-P.....	45
4.1.33	Procedure SPIRE-FM-WFT-FUNC-DCU-03-P.....	47
4.1.34	Procedure SPIRE-FM-WFT-FUNC-DCU-04-PHOT-P	48
4.1.35	Procedure SPIRE-FM-WFT-FUNC-DCU-11-PHOT-P	49



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-
2422
Issue: 2.4
Date: 16th October 2007
Page: 5 of 115

4.1.36	Procedure SPIRE-FM-WFT-FUNC-DCU-13-PHOT-P	50
4.1.37	Procedure SPIRE-FM-WFT-FUNC-DCU-14-PHOT-P	51
4.1.38	Procedure SPIRE-FM-WFT-PDET-OFF-P	52
4.1.39	Procedure SPIRE-FM-WFT-FUNC-DCU-04-SPEC-P	53
4.1.40	Procedure SPIRE-FM-WFT-FUNC-DCU-11-SPEC-P	54
4.1.41	Procedure SPIRE-FM-WFT-FUNC-DCU-13-SPEC-P	55
4.1.42	Procedure SPIRE-FM-WFT-FUNC-DCU-14-SPEC-P	56
4.1.43	Procedure SPIRE-FM-WFT-SDET-OFF-P	57
4.1.44	Procedure SPIRE-FM-WFT-MCU-OFF-P	58
4.1.45	Procedure SPIRE-FM-WFT-SCU-OFF-P	59
4.1.46	Procedure SPIRE-FM-WFT-DRCU-OFF-P	60
4.1.47	Procedure SPIRE-FM-WFT-DPU-OFF-P	61
4.1.48	Procedure SPIRE-FM-WFT-LPU-01-P	62
4.2	REDUNDANT Instrument	63
4.2.1	Procedure SPIRE-FM-WFT-DPU-ON-R	63
4.2.2	Procedure SPIRE-FM-WFT-DRCU-ON-R	65
4.2.3	Procedure SPIRE-FM-WFT-FUNC-SCU-01-R	66
4.2.4	Procedure SPIRE-FM-WFT-FUNC-SCU-03-R	67
4.2.5	Procedure SPIRE-FM-WFT-FUNC-SCU-06-R	69
4.2.6	Procedure SPIRE-FM-WFT-FUNC-SCU-02-R	70
4.2.7	Procedure SPIRE-FM-WFT-FUNC-SCU-07-R	71
4.2.8	Procedure SPIRE-FM-WFT-FUNC-SCU-04-R	72
4.2.9	Procedure SPIRE-FM-WFT-FUNC-SCU-05-R	73
4.2.10	Procedure SPIRE-FM-WFT-FUNC-SCU-08-R	74
4.2.11	Procedure SPIRE-FM-WFT-FUNC-MCU-01-R	75
4.2.12	Procedure: SPIRE-FM-WFT-FUNC-MCU-02-R	76
4.2.13	Procedure: SPIRE-FM-WFT-FUNC-MCU-03-R	77
4.2.14	Procedure: SPIRE-FM-WFT-FUNC-MCU-04-R	78
4.2.15	Procedure SPIRE-FM-WFT-FUNC-BSM-01-R	79
4.2.16	Procedure SPIRE-FM-WFT-FUNC-BSM-02C-R	80
4.2.17	Procedure SPIRE-FM-WFT-FUNC-BSM-02J-R	81
4.2.18	Procedure SPIRE-FM-WFT-FUNC-BSM-03-R	82
4.2.19	Procedure SPIRE-FM-WFT-FUNC-BSM-05A-R	83
4.2.20	Procedure SPIRE-FM-WFT-FUNC-BSM-05B-R	84
4.2.21	Procedure SPIRE-FM-WFT-FUNC-BSM-06-R	85
4.2.22	Procedure SPIRE-FM-WFT-BSM-OFF-R	86
4.2.23	Procedure SPIRE-FM-WFT-FUNC-SMEC-01-R	87
4.2.24	Procedure SPIRE-FM-WFT-FUNC-SMEC-03-R	88
4.2.25	Procedure SPIRE-FM-WFT-FUNC-SMEC-02A-R	89
4.2.26	Procedure SPIRE-FM-WFT-FUNC-SMEC-04A-R	90
4.2.27	Procedure SPIRE-FM-WFT-FUNC-SMEC-09-R	91
4.2.28	Procedure SPIRE-FM-WFT-FUNC-SMEC-07-R	92
4.2.29	Procedure SPIRE-FM-WFT-FUNC-SMEC-02B-R	93
4.2.30	Procedure SPIRE-FM-WFT-SMEC-OFF-R	94
4.2.31	Procedure SPIRE-FM-WFT-FUNC-DCU-01-R	95
4.2.32	Procedure SPIRE-FM-WFT-FUNC-DCU-02-R	96
4.2.33	Procedure SPIRE-FM-WFT-FUNC-DCU-03-R	98
4.2.34	Procedure SPIRE-FM-WFT-FUNC-DCU-04-PHOT-R	99
4.2.35	Procedure SPIRE-FM-WFT-FUNC-DCU-11-PHOT-R	100
4.2.36	Procedure SPIRE-FM-WFT-FUNC-DCU-13-PHOT-R	101
4.2.37	Procedure SPIRE-FM-WFT-FUNC-DCU-14-PHOT-R	102
4.2.38	Procedure SPIRE-FM-WFT-PDET-OFF-R	103



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 6 of 115

4.2.39	Procedure SPIRE-FM-WFT-FUNC-DCU-04-SPEC-R.....	104
4.2.40	Procedure SPIRE-FM-WFT-FUNC-DCU-11-SPEC-R.....	105
4.2.41	Procedure SPIRE-FM-WFT-FUNC-DCU-13-SPEC-R.....	106
4.2.42	Procedure SPIRE-FM-WFT-FUNC-DCU-14-SPEC-R.....	107
4.2.43	Procedure SPIRE-FM-WFT-SDET-OFF-R	108
4.2.44	Procedure SPIRE-FM-WFT-MCU-OFF-R	109
4.2.45	Procedure SPIRE-FM-WFT-SCU-OFF-R.....	110
4.2.46	Procedure SPIRE-FM-WFT-DRCU-OFF-R	111
4.2.47	Procedure SPIRE-FM-WFT-DPU-OFF-R	112
4.2.48	Procedure SPIRE-FM-WFT-LPU-01-R	113
5.	Safe switch off.....	114
5.1	SPIRE-SAFE-SWITCH-OFF	114



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-
2422
Issue: 2.4
Date: 16th October 2007
Page: 7 of 115

2. Test Configuration

The following sections describe the required hardware and I-EGSE configuration for the test.

2.1 FM Test Configuration

This is the required hw/sw configuration prior to the start of the test:

SPIRE WU:

- The SPIRE FM FPU should be interconnected through cryoharnesses to the SPIRE FM DRCU
- The SPIRE FM DRCU should be interconnected with the SPIRE FM DPU, both PRIME and REDUNDANT interfaces.
- The SPIRE FM DRCU PRIME and REDUNDANT power interfaces to the Herschel satellite should be connected.
- The SPIRE FM DPU PRIME and REDUNDANT 1553 interfaces to the Herschel satellite should be connected.
- The SPIRE FM DPU PRIME and REDUNDANT power interfaces to the Herschel satellite should be connected.

HCDMU:

- The Bus list selected on the HCDMU should be for SPIRE PRIME Instrument, (i.e., 27 TM slots allocated for SPIRE telemetry). For the PRIME side tests the BUS Configuration should be SPIRE Prime (i.e, RT=21) and for the REDUNDANT side test the BUS Configuration should be SPIRE Redundant (i.e, RT=22)
- The HCDMU and CCS should be interconnected.

CCS & I-EGSE:

- The CCS and the I-EGSE should be interconnected via the Pipe GW.
- The SPIRE MIB should be imported on the CCS.
- The CCSHandler application software should be running on the I-EGSE.
- I-EGSE system is up and running.(Database, SCOS , QLA, EGSE Router and Gateway, TM ingestion)

3. WARM FUNCTIONAL TEST PROCEDURES OVERVIEW

3.1 General instructions for executing test procedures

- Before carrying out the next procedure within the test sequence always ask for the go ahead by the SPIRE staff.
- Section 3.4 of this document specifies the sequence to be executed. Each of the steps in the sequence corresponds to procedures in sections 4.1 and 4.2.
- The procedure tables in section 4.1 and 4.2 include blank boxes where the actual values of parameters can be noted. Based on the comparison with the expected values the success or failure of a step should be recorded in the final column of the table.
- The last row in a procedure table should be used to record the overall Pass/Fail result of each test.
- Any text in boldface in the procedural steps generally indicates an action which may have to be performed manually by the CCS staff.



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 8 of 115

3.2 General Pass/Fail criterion

A test procedure can be declared as failed if there are two consecutive execution failures. If the repetition of the procedure is successful then it should be repeated once again as a 'health' check. **In case of overall failure see section 5** of the document which addresses the safe switch OFF of the instrument under different scenarios.

3.3 Constraints

- The SPIRE Warm Electronics need to be electrically integrated with the Herschel Satellite and the FPU needs to be integrated with SPIRE Warm Electronics.
- All tests which involve moving the Spectrometer Mechanism (SMECM) are highlighted yellow in section 3.4. These tests must be performed with the Herschel Cryostat horizontal and the SMEC unlatched.
- The test sequence in section 3.4 assumes that the Herschel cryostat is vertical initially and that the Prime side of the instrument will be tested first.
- The Herschel cryostat should not be tilted during the SMEC functional tests and while the SMEC is unlatched.
- **The duration of the tests will be significantly increased as a consequence of the unresolved NCR HP-130000-ASED-NC-3276 (Packet reception occurs in bursts and not at the rate generated by the instrument). It may not prove possible to analyse the test results in real time on the I-EGSE.**
- The converted TM parameter values are extracted from the MIB in use for PFM ILT. These values are subject to change for both prime and redundant operations.
- For these functional tests the instrument will not always be in a pre-defined mode as listed in the IUM (**RD04**). This does NOT compromise the instrument integrity.

3.4 Test Sequence

This section specifies the sequence to be executed with estimated times for each execution. The sequence assumes that the tests will be started on the Prime Side of the instrument with the Herschel Cryostat in the vertical configuration.

The functional tests which move the SMEC are highlighted yellow. **These tests, which include opening and closing the internal SMEC Launch Latch, should only be performed with the Herschel Cryostat horizontal.**

Step #	Procedure Name	Purpose	Duration
1.	SPIRE-FM-WFT-DPU-ON-P	DPU PRIME Power up and OBS start	5 min
2.	SPIRE-FM-WFT-DRCU-ON-P	DRCU PRIME Power up	4 min
3.	SPIRE-FM-WFT-FUNC-SCU-01-P	SCU Nominal Science Packet Generation Check PRIME	3 min
4.	SPIRE-FM-WFT-FUNC-SCU-03-P	SCU DC Thermometry Check PRIME	8 min
5.	SPIRE-FM-WFT-FUNC-SCU-06-P	SCU AC Thermometry Check PRIME	2 min
6.	SPIRE-FM-WFT-FUNC-SCU-02-P	SCU Nominal Science Contents Check PRIME	5 min
7.	SPIRE-FM-WFT-FUNC-SCU-04-P	Photometer Calibrator Check PRIME	3 min
8.	SPIRE-FM-WFT-FUNC-SCU-05-P	Spectrometer Calibrator Check PRIME	5 min
9.	SPIRE-FM-WFT-FUNC-SCU-07-P	Sorption Cooler Heaters Check PRIME	5 min



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 9 of 115

Step #	Procedure Name	Purpose	Duration
10.	SPIRE-FM-WFT-FUNC-SCU-08-P	SCU Test Pattern Check PRIME	5 min
11.	SPIRE-FM-WFT-FUNC-MCU-01-P	MCU Boot Check PRIME	5 min
12.	SPIRE-FM-WFT-FUNC-MCU-02-P	MCU Nominal Science Packet Generation Check PRIME	5 min
13.	SPIRE-FM-WFT-FUNC-MCU-03-P	MCU Nominal Science Contents Check PRIME	5 min
14.	SPIRE-FM-WFT-FUNC-MCU-04-P	MCU Test Pattern Check PRIME	5 min
15.	SPIRE-FM-WFT-FUNC-BSM-01-P	BSM Chop/Jiggle Sensors Check PRIME	5 min
16.	SPIRE-FM-WFT-FUNC-BSM-02C-P	BSM Chop Sensor Polarity Check PRIME	5 min
17.	SPIRE-FM-WFT-FUNC-BSM-02J-P	BSM Jiggle Sensor Polarity Check PRIME	5 min
18.	SPIRE-FM-WFT-FUNC-BSM-03-P	BSM Open Loop Dynamics Check PRIME	5 min
19.	SPIRE-FM-WFT-FUNC-BSM-05A-P	BSM Open Loop Chop Test PRIME	5 min
20.	SPIRE-FM-WFT-FUNC-BSM-05B-P	BSM Close Loop Chop Test PRIME	5 min
21.	SPIRE-FM-WFT-FUNC-BSM-06-P	BSM Operational Mode Check PRIME	5 min
22.	SPIRE-FM-WFT-BSM-OFF-P	BSM Switch OFF PRIME	3 min
23.	SPIRE-FM-WFT-FUNC-DCU-01-P	DCU Nominal Science Packet Generation Check PRIME	5 min
24.	SPIRE-FM-WFT-FUNC-DCU-02-P	DCU High Speed Link Check PRIME	5 min
25.	SPIRE-FM-WFT-FUNC-DCU-03-P	DCU Test pattern Check PRIME	5 min
26.	SPIRE-FM-WFT-FUNC-DCU-04-PHOT-P	Photometer LIAs Check PRIME	5 min
27.	SPIRE-FM-WFT-FUNC-DCU-11-PHOT-P	Photometer BDAs Switch ON Check PRIME	5 min
28.	SPIRE-FM-WFT-FUNC-DCU-13-PHOT-P	Photometer BDAs Integrity Check PRIME	15 min
29.	SPIRE-FM-WFT-FUNC-DCU-14-PHOT-P	Photometer BDAs Noise Check PRIME	5 min
30.	SPIRE-FM-WFT-PDET-OFF-P	Photometer BDAs Switch OFF PRIME	3 min
31.	SPIRE-FM-WFT-FUNC-DCU-04-SPEC-P	Spectrometer LIAs Check PRIME	5 min
32.	SPIRE-FM-WFT-FUNC-DCU-11-SPEC-P	Spectrometer BDAs Integrity Check PRIME	5 min
33.	SPIRE-FM-WFT-FUNC-DCU-13-SPEC-P	Spectrometer BDAs Integrity Check PRIME	12 min
34.	SPIRE-FM-WFT-FUNC-DCU-14-SPEC-P	Spectrometer BDAs Noise Check PRIME	5 min
35.	SPIRE-FM-WFT-SDET-OFF-P	Spectrometer BDAs Switch OFF PRIME	3 min
36.	SPIRE-FM-WFT-MCU-OFF-P	MCU Switch OFF PRIME	2 min
37.	SPIRE-FM-WFT-SCU-OFF-P	SCU Switch OFF PRIME	2 min
38.	SPIRE-FM-WFT-DRCU-OFF-P	DRCU Power OFF PRIME	5 min
39.	SPIRE-FM-WFT-DPU-OFF-P	DPU Power OFF PRIME	5 min
40.	The Herschel cryostat has to be tilted horizontal for the following		To be specified by



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 10 of 115

Step #	Procedure Name	Purpose	Duration
	SMEC tests		industry
41.	SPIRE-FM-WFT-DPU-ON-P	DPU PRIME Power up and OBS start	5 min
42.	SPIRE-FM-WFT-DRCU-ON-P	DRCU PRIME Power up	5 min
43.	SPIRE-FM-WFT-FUNC-MCU-01-P	MCU Boot Check PRIME	5 min
44.	SPIRE-FM-WFT-FUNC-SMEC-01-P	SMEC Encoder and LVDT check PRIME	5 min
45.	SPIRE-FM-WFT-FUNC-SMEC-03-P	SMEC Encoder Levels Check PRIME	5 min
46.	SPIRE-FM-WFT-FUNC-SMEC-02A-P	SMEC Open Launch Latch PRIME	5 min
47.	SPIRE-FM-WFT-FUNC-SMEC-04A-P	SMEC Open Loop Position check PRIME	5 min
48.	SPIRE-FM-WFT-FUNC-SMEC-09-P	SMEC Open Loop Scan check PRIME	5 min
49.	SPIRE-FM-WFT-FUNC-SMEC-07-P	SMEC Closed Loop Scan check PRIME	5 min
50.	SPIRE-FM-WFT-FUNC-SMEC-02B-P	SMEC Close Launch Latch PRIME	5 min
51.	SPIRE-FM-WFT-SMEC-OFF-P	SMEC Switch OFF PRIME	3 min
52.	SPIRE-FM-WFT-MCU-OFF-P	MCU Switch OFF PRIME	2 min
53.	SPIRE-FM-WFT-SCU-OFF-P	SCU Switch OFF PRIME	2 min
54.	SPIRE-FM-WFT-DRCU-OFF-P	DRCU Power OFF PRIME	5 min
55.	SPIRE-FM-WFT-DPU-OFF-P	DPU Power OFF PRIME	5 min
56.	SPIRE-FM-WFT-LPU-01-P	Checkout of LPU PRIME	5 min
57.	Change to SPIRE Redundant MIB on the CCS (If required)		5 min
58.	Change to SPIRE Redundant MIB on the I-EGSE (If required)		~5-10 min
59.	Configure 1553 Spacecraft bus from SPIRE DPU PRIME to SPIRE DPU REDUNDANT.		5 min
60.	SPIRE-FM-WFT-DPU-ON-R	DPU REDUNDANT Power up and OBS start	5 min
61.	SPIRE-FM-WFT-DRCU-ON-R	DRCU REDUNDANT Power up	4 min
62.	SPIRE-FM-WFT-FUNC-MCU-01-R	MCU Boot Check REDUN.	5 min
63.	SPIRE-FM-WFT-FUNC-SMEC-01-R	SMEC Encoder and LVDT Check REDUN.	5 min
64.	SPIRE-FM-WFT-FUNC-SMEC-03-R	SMEC Encoder Levels Check REDUN.	5 min
65.	SPIRE-FM-WFT-FUNC-SMEC-02A-R	SMEC Open Launch Latch REDUN.	5 min
66.	SPIRE-FM-WFT-FUNC-SMEC-04A-R	SMEC Open Loop Position Check REDUN.	5 min
67.	SPIRE-FM-WFT-FUNC-SMEC-09-R	SMEC Open Loop Scan Check REDUN.	5 min
68.	SPIRE-FM-WFT-FUNC-SMEC-07-R	SMEC Closed Loop Scan Check REDUN.	5 min
69.	SPIRE-FM-WFT-FUNC-SMEC-02B-R	SMEC Close Launch Latch REDUN.	5 min
70.	SPIRE-FM-WFT-SMEC-OFF-R	SMEC Switch OFF REDUN.	3 min
71.	SPIRE-FM-WFT-MCU-OFF-R	MCU Switch OFF REDUN.	2 min
72.	SPIRE-FM-WFT-DRCU-OFF-R	DRCU Power OFF REDUN.	5 min



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 11 of 115

Step #	Procedure Name	Purpose	Duration
73.	SPIRE-FM-WFT-DPU-OFF-R	DPU Power OFF REDUN.	5 min
74.	The Herschel cryostat should now be tilted back to vertical for the remainder of WFTs		To be specified by industry
75.	SPIRE-FM-WFT-DPU-ON-R	DPU REDUNDANT Power up and OBS start	5 min
76.	SPIRE-FM-WFT-DRCU-ON-R	DRCU REDUNDANT Power up	4 min
77.	SPIRE-FM-WFT-FUNC-SCU-01-R	SCU Nominal Science Packet Generation Check REDUN.	3 min
78.	SPIRE-FM-WFT-FUNC-SCU-03-R	SCU DC Thermometry Check REDUN.	8 min
79.	SPIRE-FM-WFT-FUNC-SCU-06-R	SCU AC Thermometry Check REDUN.	2 min
80.	SPIRE-FM-WFT-FUNC-SCU-02-R	SCU Nominal Science Contents Check REDUN.	5 min
81.	SPIRE-FM-WFT-FUNC-SCU-04-R	Photometer Calibrator Check REDUN.	3 min
82.	SPIRE-FM-WFT-FUNC-SCU-05-R	Spectrometer Calibrator Check REDUN.	5 min
83.	SPIRE-FM-WFT-FUNC-SCU-07-R	Sorption Cooler Heaters Check REDUN.	5 min
84.	SPIRE-FM-WFT-FUNC-SCU-08-R	SCU Test Pattern Check REDUN.	5 min
85.	SPIRE-FM-WFT-FUNC-MCU-01-R	MCU Boot Check REDUN.	5 min
86.	SPIRE-FM-WFT-FUNC-MCU-02-R	MCU Nominal Science Packet Generation Check REDUN.	5 min
87.	SPIRE-FM-WFT-FUNC-MCU-03-R	MCU Nominal Science Contents Check REDUN.	5 min
88.	SPIRE-FM-WFT-FUNC-MCU-04-R	MCU Test Pattern Check REDUN	5 min
89.	SPIRE-FM-WFT-FUNC-BSM-01-R	BSM Chop/Jiggle Sensors Check REDUN.	5 min
90.	SPIRE-FM-WFT-FUNC-BSM-02c-R	BSM Chop Sensor Polarity Check REDUN.	5 min
91.	SPIRE-FM-WFT-FUNC-BSM-02j-R	BSM Jiggle Sensor Polarity Check REDUN.	5 min
92.	SPIRE-FM-WFT-FUNC-BSM-03-R	BSM Open Loop Dynamics Check REDUN.	5 min
93.	SPIRE-FM-WFT-FUNC-BSM-05A-R	BSM Open Loop Chop Test REDUN.	5 min
94.	SPIRE-FM-WFT-FUNC-BSM-05B-R	BSM Closed Loop Chop Test REDUN.	5 min
95.	SPIRE-FM-WFT-FUNC-BSM-06-R	BSM Operational Mode Check REDUN	5 min
96.	SPIRE-FM-WFT-FUNC-BSM-OFF-R	BSM Switch OFF REDUN.	5 min
97.	SPIRE-FM-WFT-FUNC-SMEC-03-R	SMEC Encoder Levels Check REDUN.	5 min
98.	SPIRE-FM-WFT-FUNC-SMEC-01-R	SMEC Encoder and LVDT Check REDUN.	5 min
99.	SPIRE-FM-WFT-FUNC-DCU-01-R	DCU Nominal Science Packet Generation Check REDUN.	5 min
100.	SPIRE-FM-WFT-FUNC-DCU-02-R	DCU High Speed Link Check REDUN.	5 min
101.	SPIRE-FM-WFT-FUNC-DCU-03-R	DCU Test pattern Check REDUN.	5 min
102.	SPIRE-FM-WFT-FUNC-DCU-04-PHOT-R	Photometer LIAs Check REDUN.	5 min
103.	SPIRE-FM-WFT-FUNC-DCU-11-	Photometer BDAs Switch ON Check	5 min



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 12 of 115

Step #	Procedure Name	Purpose	Duration
	PHOT-R	REDUN.	
104.	SPIRE-FM-WFT-FUNC-DCU-13-PHOT-R	Photometer BDAs Integrity Check REDUN.	15 min
105.	SPIRE-FM-WFT-FUNC-DCU-14-PHOT-R	Photometer BDAs Noise Check REDUN.	5 min
106.	SPIRE-FM-WFT-PDET-OFF-R	Photometer BDAs Switch OFF REDUN.	3 min
107.	SPIRE-FM-WFT-FUNC-DCU-04-SPEC-R	Spectrometer LIAs Check REDUN.	5 min
108.	SPIRE-FM-WFT-FUNC-DCU-11-SPEC-R	Spectrometer BDAs Integrity Check REDUN.	5 min
109.	SPIRE-FM-WFT-FUNC-DCU-13-SPEC-R	Spectrometer BDAs Integrity Check REDUN.	12 min
110.	SPIRE-FM-WFT-FUNC-DCU-14-SPEC-R	Spectrometer BDAs Noise Check REDUN.	5 min
111.	SPIRE-FM-WFT-SDET-OFF-R	Spectrometer BDAs switch OFF REDUN.	3 min
112.	SPIRE-FM-WFT-MCU-OFF-R	MCU Switch OFF REDUN.	2 min
113.	SPIRE-FM-WFT-SCU-OFF-R	SCU Switch OFF REDUN.	2 min
114.	SPIRE-FM-WFT-DRCU-OFF-R	DRCU Power OFF REDUN.	5 min
115.	SPIRE-FM-WFT-DPU-OFF-R	DPU Power OFF REDUN.	5 min
116.	SPIRE-FM-WFT-LPU-01-R	Checkout of LPU REDUN	5 min
		Total Duration	~ 9-10 hrs plus times needed to tilt the cryostat horizontal and back to vertical.



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 13 of 115

4. DETAILED WARM FUNCTIONAL TEST PROCEDURES

4.1 PRIME Instrument

4.1.1 Procedure SPIRE-FM-WFT-DPU-ON-P

Version	2.4
Date	16 th Oct. 2007
Purpose	To switch on the SPIRE DPU PRIME and start generating housekeeping
Initial configuration	SPIRE DPU and DRCU PRIME are switched off
Final configuration	SPIRE DPU PRIME is ON and SPIRE HK is being produced , SPIRE DRCU PRIME is OFF
Preconditions	<ul style="list-style-type: none">• SPIRE FM DPU is electrically integrated with the Herschel Satellite• SPIRE MIB PRIME is imported in the CCS database.• CCS is up and running• DPU AND OBS PARAMETERS & FUNCTIONAL TEST PARAMETERS displays are selected on the CCS
Duration	5 minutes
Pass/Fail Criteria	Nominal and critical HK reports start being generated at their nominal rates of 1Hz and 0.5Hz respectively.



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 14 of 115

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/Fail
1	Select DPU AND OBS PARAMETERS display is on the CCS	—	—	—	
2	Power ON the SPIRE DPU PRIME unit using the dedicated spacecraft LCL line and configure 1553 Spacecraft bus for SPIRE DPU PRIME (RT = 21)	—	—	—	
3	Wait for the boot software to produce at least 2 event packets (5,1)				
4	Execute TCL script SPIRE-FM-WFT-DPU-START-P-SP.tcl	—	—	—	
5	Check that Nominal and Critical HK packets are arriving at the CCS: SPIRE Nominal HK: <ul style="list-style-type: none"> • (type ,subtype) : (3,25) • APID : 0x502 SPIRE Critical HK: <ul style="list-style-type: none"> • (type ,subtype) : (3,25) • APID: 0x500 				
6	Check that THSK parameter is refreshing every second	THSK	Refreshing @ 1 Hz	—	
7	Check that TM2N parameter is incrementing by 1 every second	TM2N	Incrementing by 1 @ 1Hz	—	
8	Check that TM1N parameter is incrementing by 1 every 2 second	TM1N	Incrementing by 1 @ 0.5Hz		
9	On CCS check the consistency of the SPIRE on board time to the HCDMU time and the CCS. *	—	—		
10	On I-EGSE check the consistency between SCOS time and THSK and QLA time.	THSK	Incrementing once per second		
Test Result (Pass/Fail):					

* Assuming that OBT is provided by the HCDMU following RD02, i.e, OBT is TAI, there should be a 33 second difference between OBS and CCS time (assuming CCS is using UTC). In the case the HCDMU is using UTC to specify the on board time, there should be no difference between THSK and the CCS/I-EGSE system time.



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 15 of 115

4.1.2 Procedure SPIRE-FM-WFT-DRCU-ON-P

Version	2.4
Date	16 th Oct. 2007
Purpose	To switch on the SPIRE DRCU PRIME and start generating housekeeping
Initial configuration	SPIRE DPU PRIME is ON and DRCU PRIME is switched OFF
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced
Preconditions	<ul style="list-style-type: none"> • SPIRE FM DRCU is electrically integrated with the Herschel Satellite • SPIRE DRCU is switched OFF • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	4 minutes
Pass/Fail Criteria	DRCU voltages show expected 'ON' values

Procedure steps:

Step	Description	Parameter - Unit	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-DRCU-START-P-STEP1.tcl	---	---	---	
2	Check that THSK parameter is not refreshing anymore	THSK	Not refreshing	---	
3	Check that TM2N parameter is not incrementing anymore	TM2N	Not incrementing	---	
4	Power ON the SPIRE DRCU PRIME unit using the dedicated spacecraft LCL line.	---	---	---	
5	Execute TCL script SPIRE-FM-WFT-DRCU-START-P-STEP2.tcl	---	---	---	
6	Check that THSK parameter is again refreshing every second	THSK	Refreshing @ 1Hz		
7	Check that TM2N parameter is again incrementing every second	TM2N	Incrementing by 1 @ 1Hz	---	
8	Check that the SCU/DCU voltages show nominal values	SCUP5V - V SCUP9V - V SCUM9V - V BIASP5V - V BIASP9V - V BIASM9V - V	~ 5.2 ± 0.5 ~ 9.0 ± 0.2 ~ -9.0 ± 0.2 ~ 5.1 ± 0.5 ~ 9.0 ± 0.2 ~ -9.0 ± 0.2	---	

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 16 of 115

4.1.3 Procedure SPIRE-FM-WFT-FUNC-SCU-01-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU science packet generation check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • DPU AND OBS PARAMETERS & FUNCTIONAL TEST PARAMETERS displays are selected on the CCS
Duration	3 minutes
Pass/Fail Criteria	Specified SCU HK parameters show expected increment.

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-01-P.tcl	SCUFRAMECNT TM5N	0/31 0x3FFF/1		
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 17 of 115

4.1.4 Procedure SPIRE-FM-WFT-FUNC-SCU-03-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU DC thermometry check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and DC thermometry is ON
Constraints	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • SFT PARAMETERS display is selected on the CCS
Duration	8 minutes
Pass/Fail Criteria	DC Thermometry channels show temperature readings according to the actual instrument temperature* *: At warm temperatures all channels should show short circuit RAW readings of -32768

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-03-P.tcl	—	—	—	—
2	Wait for the parameter BBFULLTYPE to get set to SCU_DC_Therm				
3	A few seconds later record the value of parameter SCUTEMPSTAT	SCUTEMPSTAT	0/0xFFFF/0xFFFF		
4	<p>Configure the SFT PARAMETERS display to show the RAW values of SCU DC thermometry channels.</p> <p>Record the values of SCU DC thermometry channels. Nominal values should show a short circuit status (or RAW -32768)</p> <p>Non Nominal (Open Circuit Criterion): RAW reading in the range [0, -100]</p>	PUMPHTRTEMP PUMPHSTEMP EVAPHSTEMP SHUNTTEMP EMCFILTEMP SLOTTEMP PLOTTEMP OPTTEMP BAFTEMP BSMIFTEMP SCAL2TEMP SCAL4TEMP SCALTEMP SMECIFTEMP SMECTEMP BSMTEMP	— —		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 18 of 115

4.1.5 Procedure SPIRE-FM-WFT-FUNC-SCU-06-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU AC thermometry check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and DC thermometry is ON
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON
Constraints	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • SFT PARAMETERS display is selected on the CCS
Duration	2 minutes
Pass/Fail Criteria	AC Thermometry channel shows temperature readings according to the actual instrument temperature

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-06-P.tcl	—	—	—	—
2	Wait for the parameter BBFULLTYPE to get set to SCU_AC_Therm				
3	A few seconds later record the value of parameter SUBKSTAT	SUBKSTAT	0/1/1		
4	<p>Configure the SFT PARAMETERS display to show the RAW values of SCU AC thermometry channel.</p> <p>Record the value of SCU AC thermometry channel.</p> <p>Nominal value should show a short circuit status (or RAW ~ -32768) Non Nominal (Open Circuit Criterion): RAW reading in the range [0, -100]</p>	SUBKTEMP	—		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 19 of 115

4.1.6 Procedure SPIRE-FM-WFT-FUNC-SCU-02-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU Nominal Science Contents Check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • DPU AND OBS PARAMETERS & FUNCTIONAL TEST PARAMETERS displays are selected on the CCS
Duration	5 minutes
Pass/Fail Criteria	Specified SCU HK parameters show expected increment.

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-02-P.tcl	SCUFRAMECNT TM5N	31/62 1/3		
2	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 20 of 115

4.1.7 Procedure SPIRE-FM-WFT-FUNC-SCU-07-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Sorption Cooler Heater Check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and DC thermometry is ON
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail Criteria	Sorption cooler heat switches and pump heater show expected voltages

Procedure Steps:

Test Result (Pass/Fail):					
Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-07-P.tcl	—	—	—	—
2	Wait for the parameter BBFULLTYPE to get set to Cooler_Htr_Chk	BBFULLTYPE	Cooler_Htr_Chk		
3	Record the value of parameter SPHSV – the Sorption Pump Heat Switch Voltage. <i>This voltage stays on for ~20 seconds. Wait for the voltage to go to zero to continue.</i>	SPHSV – mV	0/~323/0		
4	Record the value of parameter EVHSV – the Evaporator Heat Switch Voltage. <i>This voltage stays on for ~20 seconds. Wait for the voltage to go to zero to continue.</i>	EVHSV – mV	0/~323/0		
5	Record the value of parameter SPHTRV – the Sorption Pump Heater Voltage. <i>This voltage stays on for ~20 seconds. Wait for the voltage to go to zero to continue.</i>	SPHTRV – V	0/~8.8/0		
6	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 21 of 115

4.1.8 Procedure SPIRE-FM-WFT-FUNC-SCU-04-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer Calibration Check (PRIME)
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	3 minutes
Pass/Fail Criteria	PCAL voltage and current agree with expected values

Procedure Steps:

Step	Description	Parameter Name – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-04-P.tcl The expected values during the test should be monitored when parameter BBFULLTYPE in the FUNCTIONAL TEST PARAMETERS display is set to PCAL_Check This usually happens about 30 seconds from the start of test execution.	PCALCURR - mA PCALV – V BBFULLTYPE	0.0/0.1/0.0 0.0/0.02/0.0 PCAL_Check		
2	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					

Final Configuration: Unchanged



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref:	SPIRE-RAL-PRC-2422
Issue:	2.4
Date:	16 th October 2007
Page:	22 of 115

4.1.9 Procedure SPIRE-FM-WFT-FUNC-SCU-05-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer Calibration Check (PRIME)
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	SCAL2 and SCAL4 voltage and currents agree with expected values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-05-P.tcl	—	—	—	
2	Wait for the parameter BBFULLTYPE to get set to SCAL4_Check	BBFULLTYPE	SCAL4_Check	—	
3	A few seconds later record the value of parameters SCAL4CURR and SCAL4V <i>These parameters are set back to 0 after ~20 seconds</i>	SCAL4CURR – mA SCAL4V – V	0.0/0.10/0.0 0.0/0.05/0.0	—	
4	Wait for the parameter BBFULLTYPE to get set to SCAL2_Check	BBFULLTYPE	SCAL2_Check	—	
5	A few seconds later record the values of parameters SCAL2CURR and SCAL2V <i>These parameters are set back to 0 after ~20 seconds</i>	SCAL2CURR – mA SCAL2V – V	0.0/0.10/0.0 0.0/0.05/0.0	—	
6	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 23 of 115

4.1.10 Procedure SPIRE-FM-WFT-FUNC-SCU-08-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU test pattern check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • DPU AND OBS PARAMETERS & FUNCTIONAL TEST PARAMETERS displays are selected on the CCS
Duration	5 minutes
Pass/Fail Criteria	SCU Test Pattern generated agrees with the one generated on a previous execution.

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-08-P.tcl	SCUFRAMECNT TM5N	62/93 3/5		
2	Wait for the I-EGSE staff to confirm the success of the test.				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 24 of 115

4.1.11 Procedure SPIRE-FM-WFT-FUNC-MCU-01-P

Version	2.4
Date	16 th Oct. 2007
Purpose	MCU (PRIME) Boot Check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	MCU voltages and board temperatures show expected 'ON' values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-MCU-01-P.tcl	—	—	—	—
2	Check that the MCU is booted up successfully	MCUBITSTAT	0/1/1		
3	Check MCU HK parameter values and ensure that the values are refreshing	MCUP5V - V MCUP14V - V MCUM14V - V MCUP15V - V MCUM15V- V MCUMACTEMP - K MCUSMECTEMP - K MCUBSMTEMP - K	~ 5.0 ± 0.2 ~ 14.0 ± 0.6 ~ -14.0 ± 0.6 ~ 15.0 ± 0.6 ~ -15.0 ± 0.7 ~300 ~300 ~300		
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 25 of 115

4.1.12 Procedure: SPIRE-FM-WFT-FUNC-MCU-02-P

Version	2.4
Date	16 th Oct. 2007
Purpose	MCU Nominal Frame Generation Check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	Unchanged.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Specified MCU HK parameters show expected increment

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-MCU-02-P.tcl	MCUFRAMECNT	0/~ 6000	—	—

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 26 of 115

4.1.13 Procedure: SPIRE-FM-WFT-FUNC-MCU-03-P

Version	2.4
Date	16 th Oct. 2007
Purpose	MCU Nominal Science Contents Check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	Unchanged.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Specified MCU HK parameters show expected increment

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-MCU-03-P.tcl	MCUFRAMECNT	~6000/~ 6297 Should increment by 297	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 27 of 115

4.1.14 Procedure: SPIRE-FM-WFT-FUNC-MCU-04-P

Version	2.4
Date	16 th Oct. 2007
Purpose	MCU Test Pattern Check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	Unchanged.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	MCU Test Pattern generated agrees with the one generated on a previous execution.

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-MCU-04-P.tcl	MCUFRAMECNT	N/N+99	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 28 of 115

4.1.15 Procedure SPIRE-FM-WFT-FUNC-BSM-01-P

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (PRIME) Chop/Jiggle Sensor Check.
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. BSM Chop/Jiggle sensors are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	HK Parameters CHOPSENSPWR and JIGGSENSPWR show expected ON values.

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-01-P.tcl	—	—	—	—
2	Check that the Chop and Jiggle sensors have switched on	CHOPSENSPWR JIGGSENSPWR	0/1/1 0/1/1		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 29 of 115

4.1.16 Procedure SPIRE-FM-WFT-FUNC-BSM-02C-P

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (PRIME) Chop Sensor Polarity Check.
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. BSM Chop/Jiggle sensors are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	CHOPSENSSIG HK parameter increments in the same direction as the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-02C-P.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 30 of 115

4.1.17 Procedure SPIRE-FM-WFT-FUNC-BSM-02J-P

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (PRIME) Jiggle Sensor Polarity Check.
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. BSM Chop/Jiggle sensors are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	JIGGSENSSIG HK parameter increments in the same direction as the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-02J-P.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 31 of 115

4.1.18 Procedure SPIRE-FM-WFT-FUNC-BSM-03-P

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (PRIME) Open Loop Dynamics Check.
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. BSM Chop/Jiggle sensors are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	CHOPSENSSIG/JIGGSENSIG HK parameter evolve in the same direction as the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-03-P.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 32 of 115

4.1.19 Procedure SPIRE-FM-WFT-FUNC-BSM-05A-P

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (PRIME) Open Loop Chop Test
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. BSM Chop/Jiggle sensors are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	The BSM Chops in between the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-05A-P.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 33 of 115

4.1.20 Procedure SPIRE-FM-WFT-FUNC-BSM-05B-P

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (PRIME) Closed Loop Chop Test
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. BSM Chop/Jiggle sensors are ON.
Final configuration	BSM is in closed loop mode
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • CHOP PARAMETERS and JIGGLE PARAMETERS displays are selected on the CCS
Duration	5 minutes
Pass/Fail criteria	The BSM Chops in between the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute SPIRE-FM-WFT-BSM-INIT-P.tcl	CHOPLOOPMODE JIGGLOOPMODE	3/-/1 3/-/1		
2	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-05B-P.tcl	—	—	—	—
3	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 34 of 115

4.1.21 Procedure SPIRE-FM-WFT-FUNC-BSM-06-P

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (PRIME) Operational Mode Check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. BSM Chop/Jiggle sensors are ON. BSM is in closed loop.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • CHOP PARAMETERS and JIGGLE PARAMETERS displays are selected on the CCS
Duration	5 minutes
Pass/Fail criteria	The BSM Chops in between the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-06-P.tcl	CHOPLOOPMODE JIGGLOOPMODE	1 1		
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 35 of 115

4.1.22 Procedure SPIRE-FM-WFT-BSM-OFF-P

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (PRIME) Switch OFF
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. BSM Chop/Jiggle sensors are ON
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. BSM Chop/Jiggle sensors are OFF.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	3 minutes
Pass/Fail criteria	HK Parameters CHOPSENSPWR and JIGGSENSPWR show expected OFF values.

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute SPIRE-FM-WFT-BSM-OFF-P.tcl	—	—	—	—
2	Check that the power to the BSM sensors is switched off	CHOPSENSPWR JIGGSENSPWR	1/-/0 1/-/0		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 36 of 115

4.1.23 Procedure SPIRE-FM-WFT-FUNC-SMEC-01-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (PRIME) Encoder/LVDT Sensor Check.
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. SMEC Encoder and LVDT are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	HK Parameters SMECENCPWR and SMECLVDTPWR show expected ON values.

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-01-P.tcl	—	—	—	—
2	Check that power to the SMEC LED and LVDT sensor is on	SMECENCPWR SMECLVDTPWR	0/-/6 0/1/1		
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 37 of 115

4.1.24 Procedure SPIRE-FM-WFT-FUNC-SMEC-03-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (PRIME) Encoder Integrity Check.
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. SMEC Encoder and LVDT are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	MCUENGSMECENCNSIG1/2 increase as the encoder power is increased

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-03-P.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 38 of 115

4.1.25 Procedure SPIRE-FM-WFT-FUNC-SMEC-02A-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Open the SMEC Launch Latch (Unlatch it)
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and SMEC is latched
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and SMEC is ON and Unlatched
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS • The Herschel Cryostat should be tilted horizontal
Duration	5 minutes
Pass/Fail criteria	TBD

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-02A-P.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 39 of 115

4.1.26 Procedure SPIRE-FM-WFT-FUNC-SMEC-04A-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (PRIME) Open Loop Positioning Test.
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. SMEC Encoder and LVDT are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS • The Herschel Cryostat should be tilted horizontal
Duration	5 minutes
Pass/Fail criteria	SMEC moves to the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-04A-P.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 40 of 115

4.1.27 Procedure SPIRE-FM-WFT-FUNC-SMEC-09-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (PRIME) Open Loop Scan Test.
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. SMEC Encoder and LVDT are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS • The Herschel Cryostat should be tilted horizontal
Duration	5 minutes
Pass/Fail criteria	SMEC performs a scan between the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	<p>A manual reset of the encoder signals 1 and 2 offsets may be required. If this is the case Two MANUAL commands will be required to be sent from the CCS:</p> <p>SPIRE_SEND_DRCU_COMMAND</p> <ul style="list-style-type: none"> • param 1 = 0x9058xxxx • param 2 = 0 <p>SPIRE_SEND_DRCU_COMMAND</p> <ul style="list-style-type: none"> • param 1 = 0x905Axxxx • param 2 = 0 <p>The 16 bit parameters xxxx will be provided by SPIRE staff</p>	SMECENC SIG1OFF SMECENC SIG2OFF			
2	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-09-P.tcl	—	—	—	—
3	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 41 of 115

4.1.28 Procedure SPIRE-FM-WFT-FUNC-SMEC-07-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (PRIME) Close Loop Scan Test.
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. SMEC Encoder and LVDT are ON.
Final configuration	SMEC is in closed loop
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS • The Herschel Cryostat should be tilted horizontal
Duration	5 minutes
Pass/Fail criteria	SMEC performs a scan between the commanded positions and the loop remains closed

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-SMEC-INIT-P.tcl	SMECLOOPMODE	6/-/1		
2	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-07-P.tcl	—	—	—	—
3	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 42 of 115

4.1.29 Procedure SPIRE-FM-WFT-FUNC-SMEC-02B-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Close the SMEC Launch Latch (Latch it)
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and SMEC is ON and unlatched
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and SMEC is ON and Latched
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	TBD

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-02B-P.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 43 of 115

4.1.30 Procedure SPIRE-FM-WFT-SMEC-OFF-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (PRIME) Switch OFF
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. SMEC Encoder and LVDT are ON.
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted. SMEC Encoder and LVDT are OFF.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is booted. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	3 minutes
Pass/Fail criteria	HK Parameters SMECENC PWR and SMECLVDT PWR show expected OFF values.

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute SPIRE-FM-WFT-SMEC-OFF-P.tcl	—	—	—	—
2	Check that the power to the SMEC sensors is switched off	SMECENC PWR SMECLVDT PWR	6/-/0 1/-/0		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 44 of 115

4.1.31 Procedure SPIRE-FM-WFT-FUNC-DCU-01-P

Version	2.4
Date	16 th Oct. 2007
Purpose	DCU science packet generation check for all Photometer and Spectrometer packet types (PF, PSW, PMW, PLW, SF, SSW and SLW)
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Specified DCU HK parameter shows expected increment

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-01-P.tcl	DCUFRAMECNT	n/n+700		
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref:	SPIRE-RAL-PRC-2422
Issue:	2.4
Date:	16 th October 2007
Page:	45 of 115

4.1.32 Procedure SPIRE-FM-WFT-FUNC-DCU-02-P

Version	2.4
Date	16 th Oct. 2007
Purpose	To check the correct functioning of the DCU PRIME High Speed Link
Initial configuration	SPIRE DPU and DRCU PRIME are switched ON, SPIRE HK is being produced and MCU is booted.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • I-EGSE is up and running • DCU PARAMETERS display is selected on the CCS • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	<p>The following DCU telemetry packet types are received at CCS with :</p> <p>Full Photometer:</p> <ul style="list-style-type: none"> - (type,subtype): (21,1). - APID 0x504 <p>PSW</p> <ul style="list-style-type: none"> - (type,subtype): (21,2). - APID 0x504 <p>PMW</p> <ul style="list-style-type: none"> -(type,subtype): (21,2). - APID 0x504 <p>PLW</p> <ul style="list-style-type: none"> -(type,subtype): (21,2). - APID 0x504 <p>Full Spectrometer:</p> <ul style="list-style-type: none"> - (type,subtype): (21,1). - APID 0x506 <p>SSW</p> <ul style="list-style-type: none"> - (type,subtype): (21,2). - APID 0x506 <p>SLW</p> <ul style="list-style-type: none"> -(type,subtype): (21,2). - APID 0x506



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 46 of 115

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FM-DCU-02-P.tcl	DCUFRAMECNT	n/n+700		
2	Verify that the following type of DCU science telemetry packets have been received at the CCS : Full Photometer: - (type,subtype): (21,1). - APID 0x504 PSW - (type,subtype): (21,2). - APID 0x504 PMW -(type,subtype): (21,2). - APID 0x504 PLW -(type,subtype): (21,2). - APID 0x504 Full Spectrometer: - (type,subtype): (21,1). - APID 0x506 SSW - (type,subtype): (21,2). - APID 0x506 SLW -(type,subtype): (21,2). - APID 0x506	—	—	—	
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 47 of 115

4.1.33 Procedure SPIRE-FM-WFT-FUNC-DCU-03-P

Version	2.4
Date	16 th Oct. 2007
Purpose	DCU Test Pattern Check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU (Photometer/Spectrometer) Test Pattern generated agrees with the one generated on a previous execution.

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-03-P.tcl	DCUFRAMECNT	n/n+700		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 48 of 115

4.1.34 Procedure SPIRE-FM-WFT-FUNC-DCU-04-PHOT-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer LIAs check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Photometer LIAs are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-04-PHOT-P.tcl	—	—	—	—
2	Check that the Photometer LIAs are switched on	PLIAP5V PLIAP9V PLIAM9V	~0/ ~+5.17 ± 0.1V ~0/ ~+11.53 ± 0.1V ~0/ ~-11.53 ± 0.1V		
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 49 of 115

4.1.35 Procedure SPIRE-FM-WFT-FUNC-DCU-11-PHOT-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer BDAs switch ON check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Photometer BDAs are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-11-PHOT-P.tcl	—	—	—	—
2	Check that the Photometer detectors and LIAs are switched on	PSWJFETSTAT PMLWJFETSTAT PLIABITSTAT	0/-/0x3F 0/-/0x7F 1		
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 50 of 115

4.1.36 Procedure SPIRE-FM-WFT-FUNC-DCU-13-PHOT-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer BDAs integrity check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Photometer BDAs are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	15 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Check that Photometer LIAs and detectors are switched on	PLIABITSTAT PSWJFETSTAT PMLWJFETSTAT	1 0x3F 0x7F		
2	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-13-PHOT-P.tcl	—	—	—	
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 51 of 115

4.1.37 Procedure SPIRE-FM-WFT-FUNC-DCU-14-PHOT-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer BDAs noise level check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Photometer BDAs are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Photometer BDAs signal show no excess noise

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Check that Photometer LIAs and detectors are switched on	PLIABITSTAT PSWJFETSTAT PMLWJFETSTAT	1 0x3F 0x7F		
2	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-14-PHOT-P.tcl	—	—	—	
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 52 of 115

4.1.38 Procedure SPIRE-FM-WFT-PDET-OFF-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer BDAs Switch OFF
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Photometer BDAs are ON
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Photometer BDAs are OFF
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	3 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-PDET-OFF-P.tcl	—	—		
2	Check that the Photometer detectors are switched off	PSWJFETSTAT PMLWJFETSTAT	0x3F/-/0 0x7F/-/0		
3	Check that the Photometer LIAs are switched off	PLIABITSTAT	1/-/0		
4	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 53 of 115

4.1.39 Procedure SPIRE-FM-WFT-FUNC-DCU-04-SPEC-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer LIAs check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Spectrometer LIAs are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-04-SPEC-P.tcl	—	—	—	—
2	Check that the Spectrometer LIAs are switched on	SLIAP5V - V SLIAP9V - V SLIAM9V - V	~0/ ~+5.23 ± 0.1 ~0/ ~+11.57 ± 0.1 ~0/ ~-11.54 ± 0.1		
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 54 of 115

4.1.40 Procedure SPIRE-FM-WFT-FUNC-DCU-11-SPEC-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer BDAs switch ON check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Spectrometer BDAs are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-11-SPEC-P.tcl	—	—	—	—
2	Check that the Spectrometer detectors are switched on	SPECJFETSTAT SLIABITSTAT	0/-/7 1		
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 55 of 115

4.1.41 Procedure SPIRE-FM-WFT-FUNC-DCU-13-SPEC-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer BDAs integrity check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Spectrometer BDAs are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	12 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Check that the Spectrometer detectors and LIAs are switched on	SPECJFETSTAT SLIABITSTAT	7 1		
2	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-13-SPEC-P.tcl	—	—	—	
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 56 of 115

4.1.42 Procedure SPIRE-FM-WFT-FUNC-DCU-14-SPEC-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer BDAs noise check
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Spectrometer BDAs are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Spectrometers BDAs signal show no excess noise

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Check that the Spectrometer detectors and LIAs are switched on	SPECJFETSTAT SLIABITSTAT	7 1		
2	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-14-SPEC-P.tcl	—	—	—	
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 57 of 115

4.1.43 Procedure SPIRE-FM-WFT-SDET-OFF-P

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer BDAs Switch OFF
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Spectrometer BDAs are ON
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted and Spectrometer BDAs are OFF
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-SDET-OFF-P.tcl	—	—		
2	Check that the Spectrometer detectors are switched off	SPECJFETSTAT	7/-/0		
3	Check that the Spectrometer LIAs are switched off	SLIABITSTAT	1/-/0		
4	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 58 of 115

4.1.44 Procedure SPIRE-FM-WFT-MCU-OFF-P

Version	2.4
Date	16 th Oct. 2007
Purpose	MCU PRIME Switch OFF
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is booted.
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU PRIME is OFF.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MCU PRIME is ON. • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	2 minutes
Pass/Fail criteria	Specified MCU HK Parameter shows expected value.

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute SPIRE-FM-WFT-MCU-OFF-P.tcl	—	—	—	—
2	Check that the MCU is switched off	MCUBITSTAT	1/-/0		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 59 of 115

4.1.45 Procedure SPIRE-FM-WFT-SCU-OFF-P

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU PRIME Switch OFF
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON.
Final configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is OFF
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	2 minutes
Pass/Fail criteria	Specified SCU HK Parameters show expected value.

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-SCU-OFF-P.tcl	—	—	—	—
2	A few seconds later record the value of parameter SCUTEMPSTAT	SCUTEMPSTAT	0xFFFF/-/0		
3	A few seconds later record the value of parameter SUBKSTAT	SUBKSTAT	1/-/0		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 60 of 115

4.1.46 Procedure SPIRE-FM-WFT-DRCU-OFF-P

Version	2.4
Date	16 th Oct. 2007
Purpose	DRCU PRIME Switch OFF
Initial configuration	SPIRE DPU and DRCU PRIME are ON and SPIRE HK is being produced and AC/DC thermometry is ON.
Final configuration	SPIRE DPU PRIME is ON, SPIRE DRCU PRIME is OFF and SPIRE HK is not being produced.
Preconditions	<ul style="list-style-type: none"> • SPIRE-FM-WFT-SCU-OFF has been executed. • SPIRE DRCU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	THSK and TM2N stop refreshing/incrementing

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-DRCU-OFF-P.tcl	—	—	—	
2	Check that THSK parameter is not refreshing anymore	THSK	Not refreshing	—	
3	Check that TM2N parameter is not incrementing anymore	TM2N	Not incrementing	—	
4	Power OFF the SPIRE DRCU PRIME unit.	—	—	—	
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 61 of 115

4.1.47 Procedure SPIRE-FM-WFT-DPU-OFF-P

Version	2.4
Date	16 th Oct. 2007
Purpose	DPU PRIME Switch OFF
Initial configuration	SPIRE DPU PRIME is ON but not generating HK.
Final configuration	SPIRE DPU PRIME is OFF.
Preconditions	<ul style="list-style-type: none"> • SPIRE-FM-WFT-DRCU-OFF has been executed. • SPIRE DPU PRIME is switched ON • SPIRE MIB PRIME is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Power to SPIRE DPU PRIME is OFF

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Power OFF the SPIRE DPU PRIME unit.	---	---	---	

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 62 of 115

4.1.48 Procedure SPIRE-FM-WFT-LPU-01-P

Version	1.0
Date	Tuesday, 28 August 2007
Purpose	DPU PRIME Switch OFF
Initial configuration	Prime and redundant DPU and DRCU are off
Final configuration	Prime and redundant DPU and DRCU are off
Constraints	<ul style="list-style-type: none"> • Cryostat is vertical to within $\pm 45^\circ$ • Prime and redundant DPU and DRCU are off
Duration	5 minutes
Pass/Fail criteria	The specified current is drawn when the LPU is enabled and is switched off when the LPU is disabled

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Power on Prime LPU LCL (LCL #25)	LCL status	OFF/ /ON		State of LCL #25 switches to ON
2	Send HL command #5 (LPU Enable Prime)	LCL #25 current	0mA/ /130-180mA		Current between 130-180mA
4	Send HL command #6 (LPU Disable Prime)	LCL #25 current	130-180mA/ /0mA		Current off
5	Un-power Prime LPU LCL (LCL # 25)	LCL status	ON/ / OFF		State of LCL #25 switches to OFF

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 63 of 115

4.2 REDUNDANT Instrument

4.2.1 Procedure SPIRE-FM-WFT-DPU-ON-R

Version	2.4
Date	16 th Oct. 2007
Purpose	To switch on the SPIRE DPU REDUNDANT and start generating housekeeping
Initial configuration	SPIRE DPU and DRCU REDUNDANT are switched off
Final configuration	SPIRE DPU REDUNDANT is ON and SPIRE HK is being produced , SPIRE DRCU REDUNDANT is OFF
Preconditions	<ul style="list-style-type: none">• SPIRE FM DPU is electrically integrated with the Herschel Satellite• SPIRE MIB REDUNDANT is imported in the CCS database.• CCS is up and running• DPU AND OBS PARAMETERS & FUNCTIONAL TEST PARAMETERS displays are selected on the CCS
Duration	5 minutes
Pass/Fail Criteria	Nominal and critical HK reports start being generated at their nominal rates of 1Hz and 0.5Hz respectively.



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 64 of 115

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/Fail
1	Select DPU AND OBS PARAMETERS display is on the CCS	—	—	—	
2	Power ON the SPIRE DPU REDUNDANT unit using the dedicated spacecraft LCL line and configure 1553 Spacecraft bus for SPIRE DPU REDUNDANT (RT = 22)	—	—	—	
3	Wait for the boot software to produce at least 2 event packets (5,1)				
4	Execute TCL script SPIRE-FM-WFT-DPU-START-R-PP.tcl	—	—	—	
5	Check that Nominal and Critical HK packets are arriving at the CCS: SPIRE Nominal HK: <ul style="list-style-type: none"> • (type ,subtype) : (3,25) • APID : 0x503 SPIRE Critical HK: <ul style="list-style-type: none"> • (type ,subtype) : (3,25) • APID: 0x501 				
6	Check that THSK parameter is refreshing every second	THSK	Refreshing @ 1 Hz	—	
7	Check that TM2N parameter is incrementing by 1 every second	TM2N	Incrementing by 1 @ 1Hz	—	
8	Check that TM1N parameter is incrementing by 1 every 2 second	TM1N	Incrementing by 1 @ 0.5Hz		
9	On CCS check the consistency of the SPIRE on board time to the HCDMU time and the CCS. *	—	—		
10	On I-EGSE check the consistency between SCOS time and THSK and QLA time.	THSK	Incrementing once per second		

Test Result (Pass/Fail):

* Assuming that OBT is provided by the HCDMU following RD02, i.e, OBT is TAI, there should be a 33 second difference between OBS and CCS time (assuming CCS is using UTC). In the case the HCDMU is using UTC to specify the on board time, there should be no difference between THSK and the CCS/I-EGSE system time.



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 65 of 115

4.2.2 Procedure SPIRE-FM-WFT-DRCU-ON-R

Version	2.4
Date	16 th Oct. 2007
Purpose	To switch on the SPIRE DRCU REDUNDANT and start generating housekeeping
Initial configuration	SPIRE DPU REDUNDANT is ON and DRCU REDUNDANT is switched OFF
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced
Preconditions	<ul style="list-style-type: none"> • SPIRE FM DRCU is electrically integrated with the Herschel Satellite • SPIRE DRCU is switched OFF • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	4 minutes
Pass/Fail Criteria	DRCU voltages show expected 'ON' values

Procedure steps:

Step	Description	Parameter - Unit	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-DRCU-START-R-STEP1.tcl	—	—	—	
2	Check that THSK parameter is not refreshing anymore	THSK	Not refreshing	—	
3	Check that TM2N parameter is not incrementing anymore	TM2N	Not incrementing	—	
4	Power ON the SPIRE DRCU REDUNDANT unit using the dedicated spacecraft LCL line.	—	—	—	
5	Execute TCL script SPIRE-FM-WFT-DRCU-START-R-STEP2.tcl	—	—	—	
6	Check that THSK parameter is again refreshing every second	THSK	Refreshing @ 1Hz		
7	Check that TM2N parameter is again incrementing every second	TM2N	Incrementing by 1 @ 1Hz	—	
8	Check that the SCU/DCU voltages show nominal values	SCUP5V - V SCUP9V - V SCUM9V - V BIASP5V - V BIASP9V - V BIASM9V - V	~ 5.2 ± 0.5 ~ 9.0 ± 0.2 ~ -9.0 ± 0.2 ~ 5.1 ± 0.5 ~ 9.0 ± 0.2 ~ -9.0 ± 0.2	—	

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 66 of 115

4.2.3 Procedure SPIRE-FM-WFT-FUNC-SCU-01-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU science packet generation check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • DPU AND OBS PARAMETERS & FUNCTIONAL TEST PARAMETERS displays are selected on the CCS
Duration	3 minutes
Pass/Fail Criteria	Specified SCU HK parameters show expected increment.

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-01-R.tcl	SCUFRAMECNT TM5N	0/31 0x3FFF/1		
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 67 of 115

4.2.4 Procedure SPIRE-FM-WFT-FUNC-SCU-03-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU DC thermometry check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and DC thermometry is ON
Constraints	<ul style="list-style-type: none"> SPIRE DRCU REDUNDANT is switched ON SPIRE MIB REDUNDANT is imported in the CCS database. CCS is up and running SFT PARAMETERS display is selected on the CCS
Duration	8 minutes
Pass/Fail Criteria	DC Thermometry channels show temperature readings according to the actual instrument temperature* *: At warm temperatures all channels should show short circuit RAW readings of -32768

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-03-R.tcl	—	—	—	—
2	Wait for the parameter BBFULLTYPE to get set to SCU_DC_Therm				
3	A few seconds later record the value of parameter SCUTEMPSTAT	SCUTEMPSTAT	0/0xFFFF/0xFFFF		
4	<p>Configure the SFT PARAMETERS display to show the RAW values of SCU DC thermometry channels.</p> <p>Record the values of SCU DC thermometry channels. Nominal values should show a short circuit status (or RAW -32768)</p> <p>Non Nominal (Open Circuit Criterion): RAW reading in the</p>	PUMPHTRTEMP PUMPHSTEMP EVAPHSTEMP SHUNTTEMP EMCFILTEMP SLOTEMP PLOTEMP OPTTEMP BAFTEMP BSMIFTEMP SCAL2TEMP SCAL4TEMP SCALTEMP SMECIFTEMP SMECTEMP	— — — — — — — — — — — — — — —		



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 68 of 115

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
	range [0, -100]	BSMTEMP	—		
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 69 of 115

4.2.5 Procedure SPIRE-FM-WFT-FUNC-SCU-06-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU AC thermometry check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and DC thermometry is ON
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON
Constraints	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • SFT PARAMETERS display is selected on the CCS
Duration	2 minutes
Pass/Fail Criteria	AC Thermometry channel shows temperature readings according to the actual instrument temperature

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-06-R.tcl	—	—	—	—
2	Wait for the parameter BBFULLTYPE to get set to SCU_AC_Therm				
3	A few seconds later record the value of parameter SUBKSTAT	SUBKSTAT	0/1/1		
4	<p>Configure the SFT PARAMETERS display to show the RAW values of SCU AC thermometry channel.</p> <p>Record the value of SCU AC thermometry channel.</p> <p>Nominal value should show a short circuit status (or RAW ~ -32768)</p> <p>Non Nominal (Open Circuit Criterion): RAW reading in the range [0, -100]</p>	SUBKTEMP	—		
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 70 of 115

4.2.6 Procedure SPIRE-FM-WFT-FUNC-SCU-02-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU Nominal Science Contents Check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • DPU AND OBS PARAMETERS & FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail Criteria	Specified SCU HK parameters show expected increment.

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-02-R.tcl	SCUFRAMECNT TM5N	31/62 1/3		
2	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 71 of 115

4.2.7 Procedure SPIRE-FM-WFT-FUNC-SCU-07-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Sorption Cooler Heater Check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and DC thermometry is ON
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail Criteria	Sorption cooler heat switches and pump heater show expected voltages

Procedure Steps:

Test Result (Pass/Fail):					
Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-07-R.tcl	—	—	—	—
2	Wait for the parameter BBFULLTYPE to get set to Cooler_Htr_Chk	BBFULLTYPE	Cooler_Htr_Chk		
3	Record the value of parameter SPHSV – the Sorption Pump Heat Switch Voltage. <i>This voltage stays on for ~20 seconds. Wait for the voltage to go to zero to continue.</i>	SPHSV – mV	0/~323/0		
4	Record the value of parameter EVHSV – the Evaporator Heat Switch Voltage. <i>This voltage stays on for ~20 seconds. Wait for the voltage to go to zero to continue.</i>	EVHSV – mV	0/~323/0		
5	Record the value of parameter SPHTRV – the Sorption Pump Heater Voltage. <i>This voltage stays on for ~20 seconds. Wait for the voltage to go to zero to continue.</i>	SPHTRV – V	0/~8.8/0		
6	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 72 of 115

4.2.8 Procedure SPIRE-FM-WFT-FUNC-SCU-04-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer Calibration Check (REDUNDANT)
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	3 minutes
Pass/Fail Criteria	PCAL voltage and current agree with expected values

Procedure Steps:

Step	Description	Parameter Name – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-04-R.tcl The expected values during the test should be monitored when parameter BBFULLTYPE in the FUNCTIONAL TEST PARAMETERS display is set to PCAL_Check This usually happens about 30 seconds from the start of test execution.	PCALCURR - mA PCALV – V BBFULLTYPE	0.0/0.1/0.0 0.0/0.02/0.0 PCAL_Check		
2	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					

Final Configuration: Unchanged



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 73 of 115

4.2.9 Procedure SPIRE-FM-WFT-FUNC-SCU-05-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer Calibration Check (REDUNDANT)
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	SCAL2 and SCAL4 voltage and currents agree with expected values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-05-R.tcl	—	—	—	
2	Wait for the parameter BBFULLTYPE to get set to SCAL4_Check	BBFULLTYPE	SCAL4_Check	—	
3	A few seconds later record the value of parameters SCAL4CURR and SCAL4V <i>These parameters are set back to 0 after ~20 seconds</i>	SCAL4CURR – mA SCAL4V – V	0.0/0.10/0.0 0.0/0.05/0.0	—	
4	Wait for the parameter BBFULLTYPE to get set to SCAL2_Check	BBFULLTYPE	SCAL2_Check	—	
5	A few seconds later record the values of parameters SCAL2CURR and SCAL2V <i>These parameters are set back to 0 after ~20 seconds</i>	SCAL2CURR – mA SCAL2V – V	0.0/0.10/0.0 0.0/0.05/0.0	—	
6	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 74 of 115

4.2.10 Procedure SPIRE-FM-WFT-FUNC-SCU-08-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU test pattern check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none">• SPIRE DRCU REDUNDANT is switched ON• SPIRE MIB REDUNDANT is imported in the CCS database.• CCS is up and running• FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail Criteria	SCU Test Pattern generated agrees with the one generated on a previous execution.

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SCU-08-R.tcl	SCUFRAMECNT TM5N	62/93 3/5		
2	Wait for the I-EGSE staff to confirm the success of the test.				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 75 of 115

4.2.11 Procedure SPIRE-FM-WFT-FUNC-MCU-01-R

Version	2.4
Date	16 th Oct. 2007
Purpose	MCU (REDUNDANT) Boot Check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	MCU voltages and board temperatures show expected 'ON' values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-MCU-01-R.tcl	—	—	—	—
2	Check that the MCU is booted up successfully	MCUBITSTAT	0/1/1		
3	Check MCU HK parameter values and ensure that the values are refreshing	MCUP5V - V MCUP14V - V MCUM14V - V MCUP15V - V MCUM15V - V MCUMACTEMP - K MCUSMECTEMP - K MCUBSMTEMP - K	~ 5.0 ± 0.2 ~ 14.0 ± 0.6 ~ -14.0 ± 0.6 ~ 15.0 ± 0.6 ~ -15.0 ± 0.7 ~300 ~300 ~300		
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 76 of 115

4.2.12 Procedure: SPIRE-FM-WFT-FUNC-MCU-02-R

Version	2.4
Date	16 th Oct. 2007
Purpose	MCU Nominal Frame Generation Check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	Unchanged.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Specified MCU HK parameters show expected increment

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-MCU-02-R.tcl	MCUFRAMECNT	0/~ 6000	—	—

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 77 of 115

4.2.13 Procedure: SPIRE-FM-WFT-FUNC-MCU-03-R

Version	2.4
Date	16 th Oct. 2007
Purpose	MCU Nominal Science Contents Check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	Unchanged.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Specified MCU HK parameters show expected increment

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-MCU-03-R.tcl	MCUFRAMECNT	~6000/~ 6297 Should increment by 297	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 78 of 115

4.2.14 Procedure: SPIRE-FM-WFT-FUNC-MCU-04-R

Version	2.4
Date	16 th Oct. 2007
Purpose	MCU Test Pattern Check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	Unchanged.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	MCU Test Pattern generated agrees with the one generated on a previous execution.

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-MCU-04-R.tcl	MCUFRAMECNT	N/N+99	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 79 of 115

4.2.15 Procedure SPIRE-FM-WFT-FUNC-BSM-01-R

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (REDUNDANT) Chop/Jiggle Sensor Check.
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. BSM Chop/Jiggle sensors are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	HK Parameters CHOPSENSPWR and JIGGSENSPWR show expected ON values.

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-01-R.tcl	—	—	—	—
2	Check that the Chop and Jiggle sensors have switched on	CHOPSENSPWR JIGGSENSPWR	0/1/1 0/1/1		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 80 of 115

4.2.16 Procedure SPIRE-FM-WFT-FUNC-BSM-02C-R

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (REDUNDANT) Chop Sensor Polarity Check.
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. BSM Chop/Jiggle sensors are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	CHOPSENSSIG HK parameter increments in the same direction as the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-02C-R.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 81 of 115

4.2.17 Procedure SPIRE-FM-WFT-FUNC-BSM-02J-R

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (REDUNDANT) Jiggle Sensor Polarity Check.
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. BSM Chop/Jiggle sensors are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	JIGGSENSSIG HK parameter increments in the same direction as the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-02J-R.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 82 of 115

4.2.18 Procedure SPIRE-FM-WFT-FUNC-BSM-03-R

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (REDUNDANT) Open Loop Dynamics Check.
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. BSM Chop/Jiggle sensors are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	CHOPSENSSIG/JIGGSENSIG HK parameter evolve in the same direction as the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-03-R.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 83 of 115

4.2.19 Procedure SPIRE-FM-WFT-FUNC-BSM-05A-R

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (REDUNDANT) Open Loop Chop Test
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. BSM Chop/Jiggle sensors are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	The BSM Chops in between the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-05A-R.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 84 of 115

4.2.20 Procedure SPIRE-FM-WFT-FUNC-BSM-05B-R

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (REDUNDANT) Closed Loop Chop Test
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. BSM Chop/Jiggle sensors are ON.
Final configuration	BSM is in closed loop mode
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • CHOP PARAMETERS and JIGGLE PARAMETERS displays are selected on the CCS
Duration	5 minutes
Pass/Fail criteria	The BSM Chops in between the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute SPIRE-FM-WFT-BSM-INIT-R.tcl	CHOPLOOPMODE JIGGLOOPMODE	3/-/1 3/-/1		
2	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-05B-R.tcl	—	—	—	—
3	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 85 of 115

4.2.21 Procedure SPIRE-FM-WFT-FUNC-BSM-06-R

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (REDUNDANT) Operational Mode Check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. BSM Chop/Jiggle sensors are ON. BSM is in closed loop.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • CHOP PARAMETERS and JIGGLE PARAMETERS displays are selected on the CCS
Duration	5 minutes
Pass/Fail criteria	The BSM Chops in between the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-BSM-06-R.tcl	CHOPLOOPMODE JIGGLOOPMODE	1 1		
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 86 of 115

4.2.22 Procedure SPIRE-FM-WFT-BSM-OFF-R

Version	2.4
Date	16 th Oct. 2007
Purpose	BSM (REDUNDANT) Switch OFF
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. BSM Chop/Jiggle sensors are ON
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. BSM Chop/Jiggle sensors are OFF.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	3 minutes
Pass/Fail criteria	HK Parameters CHOPSENSPWR and JIGGSENSPWR show expected OFF values.

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute SPIRE-FM-WFT-BSM-OFF-R.tcl	—	—	—	—
2	Check that the power to the BSM sensors is switched off	CHOPSENSPWR JIGGSENSPWR	1/-/0 1/-/0		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 87 of 115

4.2.23 Procedure SPIRE-FM-WFT-FUNC-SMEC-01-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (REDUNDANT) Encoder/LVDT Sensor Check.
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. SMEC Encoder and LVDT are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	HK Parameters SMECENCPWR and SMECLVDTPWR show expected ON values.

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-01-R.tcl	—	—	—	—
2	Check that power to the SMEC LED and LVDT sensor is on	SMECENCPWR SMECLVDTPWR	0/-/6 0/1/1		
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 88 of 115

4.2.24 Procedure SPIRE-FM-WFT-FUNC-SMEC-03-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (REDUNDANT) Encoder Integrity Check.
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. SMEC Encoder and LVDT are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	MCUENGSMECENCNSIG1/2 increase as the encoder power is increased

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-03-R.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 89 of 115

4.2.25 Procedure SPIRE-FM-WFT-FUNC-SMEC-02A-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Open the SMEC Launch Latch (Unlatch it)
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and SMEC is latched
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and SMEC is ON and Unlatched
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS • The Herschel Cryostat should be tilted horizontal
Duration	5 minutes
Pass/Fail criteria	TBD

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-02A-R.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 90 of 115

4.2.26 Procedure SPIRE-FM-WFT-FUNC-SMEC-04A-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (REDUNDANT) Open Loop Positioning Test.
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. SMEC Encoder and LVDT are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS • The Herschel Cryostat should be tilted horizontal
Duration	5 minutes
Pass/Fail criteria	SMEC moves to the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-04A-R.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 91 of 115

4.2.27 Procedure SPIRE-FM-WFT-FUNC-SMEC-09-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (REDUNDANT) Open Loop Scan Test.
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. SMEC Encoder and LVDT are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS • The Herschel Cryostat should be tilted horizontal
Duration	5 minutes
Pass/Fail criteria	SMEC performs a scan between the commanded positions

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	<p>A manual reset of the encoder signals 1 and 2 offsets may be required. If this is the case Two MANUAL commands will be required to be sent from the CCS:</p> <p>SPIRE_SEND_DRCU_COMMAND</p> <ul style="list-style-type: none"> • param 1 = 0x9058xxxx • param 2 = 0 <p>SPIRE_SEND_DRCU_COMMAND</p> <ul style="list-style-type: none"> • param 1 = 0x905Axxxx • param 2 = 0 <p>The 16 bit parameters xxxx will be provided by SPIRE staff</p>	SMECECNSIG1OFF SMECENCNSIG2OFF			
2	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-09-R.tcl	—	—	—	—
3	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 92 of 115

4.2.28 Procedure SPIRE-FM-WFT-FUNC-SMEC-07-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (REDUNDANT) Close Loop Scan Test.
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. SMEC Encoder and LVDT are ON.
Final configuration	SMEC is in closed loop
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS • The Herschel Cryostat should be tilted horizontal
Duration	5 minutes
Pass/Fail criteria	SMEC performs a scan between the commanded positions and the loop remains closed

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-SMEC-INIT-R.tcl	SMECLOOPMODE	6/-/1		
2	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-07-R.tcl	—	—	—	—
3	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 93 of 115

4.2.29 Procedure SPIRE-FM-WFT-FUNC-SMEC-02B-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Close the SMEC Launch Latch (Latch it)
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and SMEC is ON and unlatched
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and SMEC is ON and Latched
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	TBD

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-SMEC-02B-R.tcl	—	—	—	—
2	Wait for the I-EGSE staff to confirm the success or failure of this test				

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 94 of 115

4.2.30 Procedure SPIRE-FM-WFT-SMEC-OFF-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SMEC (REDUNDANT) Switch OFF
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. SMEC Encoder and LVDT are ON.
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted. SMEC Encoder and LVDT are OFF.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is booted. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	3 minutes
Pass/Fail criteria	HK Parameters SMECENC PWR and SMECLVDTPWR show expected OFF values.

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute SPIRE-FM-WFT-SMEC-OFF-R.tcl	—	—	—	—
2	Check that the power to the SMEC sensors is switched off	SMECENC PWR SMECLVDTPWR	6/-/0 1/-/0		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 95 of 115

4.2.31 Procedure SPIRE-FM-WFT-FUNC-DCU-01-R

Version	2.4
Date	16 th Oct. 2007
Purpose	DCU science packet generation check for all Photometer and Spectrometer packet types (PF, PSW, PMW, PLW, SF, SSW and SLW)
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Specified DCU HK parameter shows expected increment

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-01-R.tcl	DCUFRAMECNT	n/n+700		
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref:	SPIRE-RAL-PRC-2422
Issue:	2.4
Date:	16 th October 2007
Page:	96 of 115

4.2.32 Procedure SPIRE-FM-WFT-FUNC-DCU-02-R

Version	2.4
Date	16 th Oct. 2007
Purpose	To check the correct functioning of the DCU REDUNDANT High Speed Link
Initial configuration	SPIRE DPU and DRCU REDUNDANT are switched ON, SPIRE HK is being produced and MCU is booted.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • I-EGSE is up and running • DCU PARAMETERS display is selected on the CCS • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	<p>The following DCU telemetry packet types are received at CCS with :</p> <p>Full Photometer: - (type,subtype): (21,1). - APID 0x505</p> <p>PSW - (type,subtype): (21,2). - APID 0x505</p> <p>PMW -(type,subtype): (21,2). - APID 0x505</p> <p>PLW -(type,subtype): (21,2). - APID 0x505</p> <p>Full Spectrometer: - (type,subtype): (21,1). - APID 0x507</p> <p>SSW - (type,subtype): (21,2). - APID 0x507</p> <p>SLW -(type,subtype): (21,2). - APID 0x507</p>

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FM-DCU-02-R.tcl	DCUFRAMECNT	n/n+700		



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref:	SPIRE-RAL-PRC-2422
Issue:	2.4
Date:	16 th October 2007
Page:	97 of 115

2	<p>Verify that the following type of DCU science telemetry packets have been received at the CCS :</p> <p>Full Photometer:</p> <ul style="list-style-type: none"> - (type,subtype): (21,1). - APID 0x505 <p>PSW</p> <ul style="list-style-type: none"> - (type,subtype): (21,2). - APID 0x505 <p>PMW</p> <ul style="list-style-type: none"> -(type,subtype): (21,2). - APID 0x505 <p>PLW</p> <ul style="list-style-type: none"> -(type,subtype): (21,2). - APID 0x505 <p>Full Spectrometer:</p> <ul style="list-style-type: none"> - (type,subtype): (21,1). - APID 0x507 <p>SSW</p> <ul style="list-style-type: none"> - (type,subtype): (21,2). - APID 0x507 <p>SLW</p> <ul style="list-style-type: none"> -(type,subtype): (21,2). - APID 0x507 	—	—	—	
---	--	---	---	---	--

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 98 of 115

4.2.33 Procedure SPIRE-FM-WFT-FUNC-DCU-03-R

Version	2.4
Date	16 th Oct. 2007
Purpose	DCU Test Pattern Check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU (Photometer/Spectrometer) Test Pattern generated agrees with the one generated on a previous execution.

Procedure Steps:

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Success/Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-03-R.tcl	DCUFRAMECNT	n/n+700		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 99 of 115

4.2.34 Procedure SPIRE-FM-WFT-FUNC-DCU-04-PHOT-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer LIAs check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Photometer LIAs are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-04-PHOT-R.tcl	—	—	—	—
2	Check that the Photometer LIAs are switched on	PLIAP5V PLIAP9V PLIAM9V	~0/ ~+5.19 ± 0.1V ~0/ ~+11.54 ± 0.1V ~0/ ~-11.53 ± 0.1V		
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 100 of 115

4.2.35 Procedure SPIRE-FM-WFT-FUNC-DCU-11-PHOT-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer BDAs switch ON check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Photometer BDAs are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-11-PHOT-R.tcl	—	—	—	—
2	Check that the Photometer detectors and LIAs are switched on	PSWJFETSTAT PMLWJFETSTAT PLIABITSTAT	0/-/0x3F 0/-/0x7F 1		
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 101 of 115

4.2.36 Procedure SPIRE-FM-WFT-FUNC-DCU-13-PHOT-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer BDAs integrity check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Photometer BDAs are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	15 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Check that Photometer LIAs and detectors are switched on	PLIABITSTAT PSWJFETSTAT PMLWJFETSTAT	1 0x3F 0x7F		
2	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-13-PHOT-R.tcl	—	—	—	
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 102 of 115

4.2.37 Procedure SPIRE-FM-WFT-FUNC-DCU-14-PHOT-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer BDAs noise level check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Photometer BDAs are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Photometer BDAs signal show no excess noise

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Check that Photometer LIAs and detectors are switched on	PLIABITSTAT PSWJFETSTAT PMLWJFETSTAT	1 0x3F 0x7F		
2	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-14-PHOT-R.tcl	—	—	—	
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 103 of 115

4.2.38 Procedure SPIRE-FM-WFT-PDET-OFF-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Photometer BDAs Switch OFF
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Photometer BDAs are ON
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Photometer BDAs are OFF
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	3 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-PDET-OFF-R.tcl	—	—		
2	Check that the Photometer detectors are switched off	PSWJFETSTAT PMLWJFETSTAT	0x3F/-/0 0x7F/-/0		
3	Check that the Photometer LIAs are switched off	PLIABITSTAT	1/-/0		
4	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 104 of 115

4.2.39 Procedure SPIRE-FM-WFT-FUNC-DCU-04-SPEC-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer LIAs check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Spectrometer LIAs are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-04-SPEC-R.tcl	—	—	—	—
2	Check that the Spectrometer LIAs are switched on	SLIAP5V - V SLIAP9V - V SLIAM9V - V	~0/ ~+5.23 ± 0.1 ~0/ ~+11.57 ± 0.1 ~0/ ~-11.54 ± 0.1		
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 105 of 115

4.2.40 Procedure SPIRE-FM-WFT-FUNC-DCU-11-SPEC-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer BDAs switch ON check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Spectrometer BDAs are ON.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-11-SPEC-R.tcl	—	—	—	—
2	Check that the Spectrometer detectors are switched on	SPECJFETSTAT SLIABITSTAT	0/-/7 1		
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 106 of 115

4.2.41 Procedure SPIRE-FM-WFT-FUNC-DCU-13-SPEC-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer BDAs integrity check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Spectrometer BDAs are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	12 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Check that the Spectrometer detectors and LIAs are switched on	SPECJFETSTAT SLIABITSTAT	7 1		
2	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-13-SPEC-R.tcl	—	—	—	
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref:	SPIRE-RAL-PRC-2422
Issue:	2.4
Date:	16 th October 2007
Page:	107 of 115

4.2.42 Procedure SPIRE-FM-WFT-FUNC-DCU-14-SPEC-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer BDAs noise check
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Spectrometer BDAs are ON.
Final configuration	Unchanged
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Spectrometers BDAs signal show no excess noise

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Check that the Spectrometer detectors and LIAs are switched on	SPECJFETSTAT SLIABITSTAT	7 1		
2	Execute TCL script SPIRE-FM-WFT-FUNC-DCU-13-SPEC-R.tcl	—	—	—	
3	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 108 of 115

4.2.43 Procedure SPIRE-FM-WFT-SDET-OFF-R

Version	2.4
Date	16 th Oct. 2007
Purpose	Spectrometer BDAs Switch OFF
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Spectrometer BDAs are ON
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted and Spectrometer BDAs are OFF
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	DCU HK parameters show expected values

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-SDET-OFF-R.tcl	—	—		
2	Check that the Spectrometer detectors are switched off	SPECJFETSTAT	7/-/0		
3	Check that the Spectrometer LIAs are switched off	SLIABITSTAT	1/-/0		
4	Wait for the I-EGSE staff to confirm the success or failure of this test	—	—	—	—
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 109 of 115

4.2.44 Procedure SPIRE-FM-WFT-MCU-OFF-R

Version	2.4
Date	16 th Oct. 2007
Purpose	MCU REDUNDANT Switch OFF
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is booted.
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON and MCU REDUNDANT is OFF.
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MCU REDUNDANT is ON. • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	2 minutes
Pass/Fail criteria	Specified MCU HK Parameter shows expected value.

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute SPIRE-FM-WFT-MCU-OFF-R.tcl	—	—	—	—
2	Check that the MCU is switched off	MCUBITSTAT	1/-/0		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test
Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 110 of 115

4.2.45 Procedure SPIRE-FM-WFT-SCU-OFF-R

Version	2.4
Date	16 th Oct. 2007
Purpose	SCU REDUNDANT Switch OFF
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON.
Final configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is OFF
Preconditions	<ul style="list-style-type: none"> • SPIRE DRCU REDUNDANT is switched ON • SPIRE MIB REDUNDANT is imported in the CCS database. • CCS is up and running • FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	2 minutes
Pass/Fail criteria	Specified SCU HK Parameters show expected value.

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-SCU-OFF-R.tcl	---	---	---	---
2	A few seconds later record the value of parameter SCUTEMPSTAT	SCUTEMPSTAT	0xFFFF/-/0		
3	A few seconds later record the value of parameter SUBKSTAT	SUBKSTAT	1/-/0		

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test Procedures
A.A.Aramburu & Sunil D.Sidher

Ref:	SPIRE-RAL-PRC-2422
Issue:	2.4
Date:	16 th October 2007
Page:	111 of 115

4.2.46 Procedure SPIRE-FM-WFT-DRCU-OFF-R

Version	2.4
Date	16 th Oct. 2007
Purpose	DRCU REDUNDANT Switch OFF
Initial configuration	SPIRE DPU and DRCU REDUNDANT are ON and SPIRE HK is being produced and AC/DC thermometry is ON.
Final configuration	SPIRE DPU REDUNDANT is ON, SPIRE DRCU REDUNDANT is OFF and SPIRE HK is not being produced.
Preconditions	<ul style="list-style-type: none"> SPIRE-FM-WFT-SCU-OFF has been executed. SPIRE DRCU REDUNDANT is switched ON SPIRE MIB REDUNDANT is imported in the CCS database. CCS is up and running FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	THSK and TM2N stop refreshing/incrementing

Procedure Steps:

Step	Description	Parameter - Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Execute TCL script SPIRE-FM-WFT-DRCU-OFF-R.tcl	—	—	—	
2	Check that THSK parameter is not refreshing anymore	THSK	Not refreshing	—	
3	Check that TM2N parameter is not incrementing anymore	TM2N	Not incrementing	—	
4	Power OFF the SPIRE DRCU REDUNDANT unit.	—	—	—	

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test Procedures
A.A.Aramburu & Sunil D.Sidher

Ref:	SPIRE-RAL-PRC-2422
Issue:	2.4
Date:	16 th October 2007
Page:	112 of 115

4.2.47 Procedure SPIRE-FM-WFT-DPU-OFF-R

Version	2.4
Date	16 th Oct. 2007
Purpose	DPU REDUNDANT Switch OFF
Initial configuration	SPIRE DPU REDUNDANT is ON but not generating HK.
Final configuration	SPIRE DPU REDUNDANT is OFF.
Preconditions	<ul style="list-style-type: none"> SPIRE-FM-WFT-DRCU-OFF has been executed. SPIRE DPU REDUNDANT is switched ON SPIRE MIB REDUNDANT is imported in the CCS database. CCS is up and running FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	5 minutes
Pass/Fail criteria	Power to SPIRE DPU REDUNDANT is OFF

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Power OFF the SPIRE DPU REDUNDANT unit.	—	—	—	

Test Result (Pass/Fail):



Spire Procedure

SPIRE FM Warm Functional Test Procedures
A.A.Aramburu & Sunil D.Sidher

Ref:	SPIRE-RAL-PRC-2422
Issue:	2.4
Date:	16 th October 2007
Page:	113 of 115

4.2.48 Procedure SPIRE-FM-WFT-LPU-01-R

Version	1.0
Date	Tuesday, 28 August 2007
Purpose	DPU PRIME Switch OFF
Initial configuration	Prime and redundant DPU and DRCU are off
Final configuration	Prime and redundant DPU and DRCU are off
Constraints	<ul style="list-style-type: none"> Cryostat is vertical to within $\pm 45^\circ$ Prime and redundant DPU and DRCU are off
Duration	5 minutes
Pass/Fail criteria	The specified current is drawn when the LPU is enabled and is switched off when the LPU is disabled

Procedure Steps:

Step	Description	Parameter – Unit	Expected Values Before/ During/ After	Actual Values Before/ During/ After	Success/ Failure
1	Power on Redundant LPU LCL (LCL #26)	LCL status	OFF/ /ON		State of LCL #26 switches to ON
3	Send HL command #21 (LPU Enable Redundant)	LCL #26 current	0mA/ /130-180mA		Current between 130-180mA
4	Send HL command #22 (LPU Disable Redundant)	LCL #26 current	130-180mA/ /0mA		Current off
5	Un-power Prime LPU LCL (LCL # 25)	LCL status	ON/ / OFF		State of LCL #26 switches to OFF
Test Result (Pass/Fail):					



Spire Procedure

SPIRE FM Warm Functional Test Procedures
A.A.Aramburu & Sunil D.Sidher

Ref: SPIRE-RAL-PRC-2422
Issue: 2.4
Date: 16th October 2007
Page: 114 of 115

5. Safe switch off

The following procedure describes the necessary steps to safely switch off SPIRE if an anomaly should occur.

5.1 SPIRE-SAFE-SWITCH-OFF

Version	2.4
Date	16 th Oct. 2007
Purpose	To switch OFF the SPIRE instrument if an anomaly should occur
Initial configuration	SPIRE can be on ANY configuration as specified on the procedure steps
Final configuration	SPIRE is OFF
Preconditions	<ul style="list-style-type: none">• SPIRE FM DPU is electrically integrated with the Herschel Satellite• SPIRE MIB REDUNDANT is imported in the CCS database.• CCS is up and running• FUNCTIONAL TEST PARAMETERS display is selected on the CCS
Duration	~5-8 minutes
Pass/Fail Criteria	SPIRE is OFF. All instrument subsystems are completely powered OFF.

Notes:

1. All HK parameters relevant to this procedure can be located on the FUNCTIONAL TEST PARAMETERS CCS display
2. The expected values of HK parameters before the execution of a switch-off script are not indicated in the table below because the scripts can be run from any instrument configuration without harming the instrument.



Spire Procedure

SPIRE FM Warm Functional Test Procedures
A.A.Aramburu & Sunil D.Sidher

Ref:	SPIRE-RAL-PRC-2422
Issue:	2.4
Date:	16 th October 2007
Page:	115 of 115

Procedure Steps:

Step	Description	Parameter - Unit	Expected value before/after	Actual value before/after
1.	Execute Procedures: <ul style="list-style-type: none"> ▪ SPIRE-FM-WFT-PDET-OFF-P/R ▪ SPIRE-FM-WFT-BSM-OFF-P/R 	PLIABITSAT PSWJFETSTAT PMLWJFETSTAT CHOPSENSPWR	- / 0 - / 0 - / 0 - / 0	
2.	Execute Procedures: <ul style="list-style-type: none"> ▪ SPIRE-FM-WFT-SDET-OFF-P/R ▪ SPIRE-FM-WFT-SMEC-OFF-P/R 	SLIABITSAT SPECJFETSTAT SMECENCPWR SMECLVDPWR	- / 0 - / 0 - / 0 - / 0	
3.	Execute Procedures: <ul style="list-style-type: none"> ▪ SPIRE-FM-WFT-MCU-OFF-P/R ▪ SPIRE-FM-WFT-SCU-OFF-P/R 	MCUBITSTAT SCUTEMPSTAT SUBKSTAT	- / 0 - / 0 - / 0	
4.	Execute Procedure: <ul style="list-style-type: none"> ▪ SPIRE-FM-WFT-DRCU-OFF-P/R 	TM2N THSK	- / Not updating	
5.	Execute Procedure: <ul style="list-style-type: none"> ▪ SPIRE-FM-WFT-DPU-OFF-P/R 	—	—	