

# Introduction

This document describes the Integrated Module Test (IMT) procedures to be executed on the *cold* SPIRE CQM at EADS Astrium in Ottobrunn in the presence of I-EGSE staff. This document gives step-by-step instructions on how to perform each test.

# **Change Record**

Issue 1.0 – First version.

# **Applicable Documents**

AD1 SPIRE Integrated Module Test (IMT) sequence for EQM testing, SPIRE-RAL-NOT-002284, Issue 2.1, 5/4/2005
AD2 SPIRE COOLER RECYCLING SCOS PROCEDURE - SPIRE-RAL-PRC-002267

# **Reference Documents**

**RD01** SPIRE Functional Test Specification - SPIRE-RAL-DOC-001652 **RD02** SPIRE Short Functional Test (SFT) Procedures for the CCS, SPIRE-RAL-PRC-002494, Issue 1.1, 09/09/2005

# General instructions for executing test procedures

- The procedures listed here are not necessarily in the order in which they are expected to be performed. For the exact order of the IMTs please refer to AD1. Each procedure should only be executed in consultation with the I-EGSE staff.
- Each step in the procedure should only be executed after confirmation with the I-EGSE staff.
- The procedure tables include blank boxes where the actual values of parameters can be noted. Based on the comparison with the expected values the success or failure of a step should be recorded in the final column of the table.
- The last row in a procedure table should be used to record the overall Pass/Fail result of each test.
- Any text in **boldface** in the procedural steps generally indicates an action which may have to be performed manually by the CCS staff. Text in italics gives some background information about the step in progress.

# **Prerequisites for the IMT**

FPU is integrated onto HOB WE integrated with CCE WE integrated with harness and FPU Warm SFTs done in accordance with RD02



Cold SFTs done in accordance with RD02 Cold functional test done at "4K" and "1.7K" as per RD02 FPU is at nominal temperature and left in REDY mode – see transition diagram in AD1 FPU in OFF mode

# **Duration of IMTs**

The total duration for IMTs is estimated to be  $\sim$  **5-6 days**, assuming that the tests proceed without any problems.



# Procedure: SPIRE-IMT-SETUP-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Setup the DCU frame generation for a particular bias and sampling frequencies Duration: ~ 15 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DCU PARAMETERS display is selected on the CCS

# **Initial Configuration:** SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected	Actual	Pass/
			Values	Values Before/After	Fail
			<b>Before</b> /After		
1	Execute TCL script SPIRE-				
	IMT-SETUP-P.tcl				
2	Wait for the I-EGSE staff	—	—	—	
	to confirm the success or				
	failure of this test				
Test	Result (Pass/Fail):				



Procedure: SPIRE-IMT-START-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Start the DCU frame generation Duration: ~ 15 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DCU PARAMETERS display is selected on the CCS

# **Initial Configuration:** SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected	Actual	Pass/
			Values	Values Before/After	Fail
			<b>Before</b> /After		
1	Execute TCL script SPIRE-	DCUFRAMESTAT	OFF	CONTINUOUS	
	IMT-START-P.tcl				
2	Wait for the I-EGSE staff	—	—	—	
	to confirm the success or				
	failure of this test				
Test	Result (Pass/Fail):				

**Final Configuration:** SPIRE is in PHOTSTBY-TEST mode



Procedure: SPIRE-IMT-STOP-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Stop the DCU frame generation Duration: ~ 15 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DCU PARAMETERS display is selected on the CCS

#### **Initial Configuration:** SPIRE is in PHOTSTBY-TEST mode

## **Procedure Steps:**

Step	Description	Parameter	Expected	Actual	Pass/
			Values	Values Before/After	Fail
			<b>Before</b> /After		
1	Execute TCL script SPIRE-	DCUFRAMESTAT	CONTINUOU	OFF	
	IMT-STOP-P.tcl		S		
2	Wait for the I-EGSE staff	—	—	—	
	to confirm the success or				
	failure of this test				
Test	Result (Pass/Fail):				

Final Configuration: SPIRE is in PHOTSTBY mode



Procedure: SPIRE-IMT-NOMINAL-BIAS-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Set the nominal bias on the photometer detectors Duration: ~ 15 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DCU PARAMETERS display is selected on the CCS

#### Initial Configuration: SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values	Actual Values Before/After	Pass/ Fail			
			<b>Before/After</b>					
1	Execute TCL script SPIRE- IMT-NOMINAL-BIAS- P.tcl							
2	Wait for the I-EGSE staff to confirm the success or failure of this test		_					
Test l	Test Result (Pass/Fail):							

Final Configuration: SPIRE is in PHOTSTBY mode



# Procedure: SPIRE-IMT-NOISE-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Check the noise in PLW JFETs with shorted inputs versus Vss (detectors at ~2K) Duration: ~ 30 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are off
- DPU and OBS PARAMETERS display is selected on the CCS

Initial Configuration: SPIRE is in REDY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values	Actual Values Before/After	Pass/ Fail
			Before/After		
1	Execute TCL script SPIRE-				
	IMT-PDET-ON-STEP1.tcl	SCUDCDCSTAT	0/1		
2	Execute TCL script SPIRE-	MODE	REDY/		
	IMT-PDET-ON-STEP2 tcl		PHOTSTBY		
			THOTOTOT		
3	Execute TCL script SPIRE-	—	—	—	
	IMT-NOISE-P.tcl				
4	Execute TCL script SPIRE-	MODE	PHOTSTBY/		
	IMT-PDET-OFF.tcl	_	REDY		
		SCUDCDCSTAT	1/0		
5	Wait for the I-EGSE staff	_		_	
-	to confirm the success or				
	failure of this test				
Test	Result (Pass/Fail):		1	1	1

Final Configuration: SPIRE mode REDY



Procedure: SPIRE-IMT-NOISEVBIAS-S Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Measure noise versus bias using Spectrometer side and STM JFETS Duration: ~ 30 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The STM JFETs are off
- DPU and OBS PARAMETERS display is selected on the CCS

#### **Initial Configuration:**

• SPIRE is in REDY mode

# **Procedure Steps:**

Step	Description	Parameter	Expected Values	Actual	Pass/
			Before/After	Values Before/After	Fall
1	Execute TCL script SPIRE- IMT-PDET-ON-STEP1.tcl NOTE: There is no mistake in the name of the script to be executed!	SCUDCDCSTAT	0/1		
2	Execute TCL script SPIRE- IMT-SDET-ON.tcl	MODE	REDY/ SPECSTBY		
3	Execute TCL script SPIRE- IMT-NOISEVBIAS-S.tcl				
4	Execute TCL script SPIRE- IMT-SDET-OFF.tcl	MODE	SPECSTBY/REDY		
5	Wait for the I-EGSE staff to confirm the success or failure of this test				
Test ]	Result (Pass/Fail):				

# Final Configuration: SPIRE is in REDY mode



Procedure: SPIRE-IMT-PUMP-CHAR Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Cooler sorption pump characterisation test Duration: ~ 1.5 hours

**Preconditions:** 

- SCU DC and AC thermometry is on
- Level 0 Detector Box and Pump are at 2 K and the Level 0 Evaporator is at 1.85 K

# **Initial Configuration:**

- SPIRE DPU is on and generating HK
- SCU PARAMETERS display is selected on the CCS
- SPIRE is in REDY mode

#### **Procedure Steps:**

Step	Description	Parameters	Expected Values	Actual Values	Success/ Failure
1	Execute TCL script SPIRE-IMT- PUMP-CHAR.tcl 40 mW power applied to Pump Heater & Evaporator Heat Switch turned on.	SPHSV SPHTRV	~565 mV ~4 V		
2	Wait for the I-EGSE staff to confirm the success or failure of this test	PUMPHTRTEMP			
Test l	Result (Pass/Fail):				



# **Procedure: SPIRE-IMT-CREC**

Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Cooler Recycle – same procedure to be run for all subsequent recycles. This procedure will be run manually from the CCS to determine the parameters needed to prepare an automated TCL script. This automated script can then be run overnight as necessary.

**Duration:** ~ 2 hours

#### **Preconditions:**

- SCU DC and AC thermometry is on
- Level 0 Detector Box and Pump are at 2 K and the Level 0 Evaporator is at 1.85 K

# **Initial Configuration:**

- SPIRE DPU is on and generating HK
- SCU PARAMETERS display is selected on the CCS

#### **Procedure Steps:**

Step	Description	Parameters	Expected	Actual	Success/
			Values	Values	Failure
1	Execute TCL script SPIRE-IMT-	STEP	1		
	CREC.tcl	Time (UT)	-		
	• Click on OK button to	CDUCN			
	turn off Pump Heat	SPHSV	$\sim 565 \text{ mV}$		
	Switch (whether it is on	PUMPHSIEMP	- 2.0 K		
	or off)	EVAPHSIEMP	~ 3.0 K		
	• Apply 1.4 mA to the				
	Evaporator Heat Switch	~~~~~			
2	Wait for PUMPHSTEMP to go	STEP	2		
	just below 12 K and then click	Time (UT)	-		
	on OK to apply 300 mW power	$\Delta Time (minutes)$			
	to Pump Heater				
		SPHTRV	~ 10.8 V		
3	Wait for PUMPHTRTEMP to	STEP	3		
	increase to 45 K and then click	Time (UT)	-		
	on OK to reduce power to	$\Delta Time (minutes)$			
	Pump Heater to 40mW	~~~~~			
		SPHTRV	$\sim 4 \text{ V}$		
		PUMPHTRTEMP	~ 45 K		
4	Wait for SUBKTEMP to fall	STEP	4		
	below 2 K and then click on OK	Time (UT)	-		
	to switch off power to the	$\Delta Time$ (minutes)			
	Pump Heater and Evaporator				
	Heat Switch.	SPHSV	$\sim 0 \text{ mV}$		



# SPIRE Procedure

SPIRE Integrated Module Test (IMT) Procedures for the CCS S.D.Sidher & A.A Aramburu

**Ref:** SPIRE-RAL-PRC-002512 Issue: 1.0 Date: 15/09/05 Page: 11 of 30

IMPORTANT: This step should be executed even if SUBKTEMP is above 2 K but more than an hour has elapsed since the start of the recycle procedure.SPHTRV PUMPHSTEMP EVAPHSTEMP ATIME (UT)~ 0 V ~ 4.1 K ~ 19.3 K~ 10.3 K5Wait for EVAPHSTEMP to fall below ~ 16 K and then click on OK to switch on power to the Pump Heat SwitchSTEP Time (UT) ATime (minutes)56Monitor SUBKTEMP and PUMPHSTEMP.Time (UT) ATime (minutes)-6Monitor SUBKTEMP and PUMPHSTEMP.Time (UT) ATime (minutes)-	Step	Description	Parameters	Expected	Actual	Success/
IMPORTANT: This step should be executed even if SUBKTEMP is above 2 K but more than an hour has elapsed since the start of the recycle procedure.~ 0 V ~ 4.1 K ~ 19.3 K5Wait for EVAPHSTEMP to fall below ~ 16 K and then click on OK to switch on power to the Pump Heat SwitchSTEP Time (UT) ATime (minutes)56Monitor SUBKTEMP and PUMPHSTEMP.Time (UT) ~ 13 K				Values	Values	Failure
IMPORTANT: This step should be executed even if SUBKTEMP is above 2 K but more than an hour has elapsed since the start of the recycle procedure.PUMPHSTEMP~ 4.1 K ~ 19.3 K5Wait for EVAPHSTEMP to fall below ~ 16 K and then click on OK to switch on power to the Pump Heat SwitchSTEP56Monitor SUBKTEMP and PUMPHSTEMP.ZUBKTEMP PUMPHSTEMP.~1.9 K ~1.3 K			SPHTRV	$\sim 0 \text{ V}$		
be executed even if SUBKTEMP is above 2 K but more than an hour has elapsed since the start of the recycle procedure.EVAPHSTEMP~ 19.3 K5Wait for EVAPHSTEMP to fall below ~ 16 K and then click on OK to switch on power to the Pump Heat SwitchSTEP55EVHSV6Monitor SUBKTEMP and PUMPHSTEMP.Time (UT) ~ 13 K6Monitor SUBKTEMP and PUMPHSTEMP.Time (UT) ~ 13 K		<b>IMPORTANT:</b> This step should	PUMPHSTEMP	~ 4.1 K		
SUBKTEMP is above 2 K but more than an hour has elapsed since the start of the recycle procedure.       -         5       Wait for EVAPHSTEMP to fall below ~ 16 K and then click on OK to switch on power to the Pump Heat Switch       STEP       5         6       Monitor SUBKTEMP and PUMPHSTEMP.       Time (UT) ATime (minutes)       -		be executed even if	EVAPHSTEMP	~ 19.3 K		
more than an hour has elapsed since the start of the recycle procedure.Image: Constraint of the recycle procedure.Image: Constraint of the recycle procedure.5Wait for EVAPHSTEMP to fall below ~ 16 K and then click on OK to switch on power to the Pump Heat SwitchSTEP56Monitor SUBKTEMP and PUMPHSTEMP.Time (UT) ATime (minutes)-		SUBKTEMP is above 2 K but				
since the start of the recycle procedure.Image: Constraint of the recycle procedure.Image: Constraint of the recycle procedure.5Wait for EVAPHSTEMP to fall below ~ 16 K and then click on OK to switch on power to the Pump Heat SwitchSTEP56Monitor SUBKTEMP and PUMPHSTEMP.Time (UT) PUMPHSTEMP6Monitor SUBKTEMP PUMPHSTEMP		more than an hour has elapsed				
procedure.Image: style of all style of all below ~ 16 K and then click on Time (UT)5below ~ 16 K and then click on OK to switch on power to the Dump Heat SwitchTime (minutes)-Pump Heat SwitchEVHSV~565 mVThe TCL script ends afterSUBKTEMP~1.9 Kexecution of this stepPUMPHSTEMP~13 K6Monitor SUBKTEMP and Time (UT)-PUMPHSTEMP.ΔTime (minutes)-		since the start of the recycle				
5Wait for EVAPHSTEMP to fall below ~ 16 K and then click on OK to switch on power to the Pump Heat SwitchSTEP5Pump Heat SwitchΔTime (UT)-Fre TCL script ends after execution of this stepSUBKTEMP~565 mV6Monitor SUBKTEMP and PUMPHSTEMP.Time (UT) ΔTime (minutes)-		procedure.				
below ~ 16 K and then click on OK to switch on power to the Pump Heat SwitchTime (UT) ΔTime (minutes)-Pump Heat SwitchEVHSV~565 mVThe TCL script ends after execution of this stepSUBKTEMP~1.9 K6Monitor SUBKTEMP and PUMPHSTEMP.Time (UT) ΔTime (minutes)-	5	Wait for EVAPHSTEMP to fall	STEP	5		
OK to switch on power to the Pump Heat SwitchΔTime (minutes)Fund FieldEVHSVFieldSUBKTEMPFieldSUBKTEMPexecution of this stepPUMPHSTEMPFine (UT)-PUMPHSTEMP.ΔTime (minutes)		below ~ 16 K and then click on	Time (UT)	-		
Pump Heat SwitchEVHSV~565 mVEVHSV~565 mVThe TCL script ends afterSUBKTEMPexecution of this stepPUMPHSTEMP6Monitor SUBKTEMP andTime (UT)PUMPHSTEMP.ΔTime (minutes)		OK to switch on power to the	$\Delta Time$ (minutes)			
EVHSV~565 mVThe TCL script ends after execution of this stepSUBKTEMPPUMPHSTEMP~1.9 KPUMPHSTEMP~13 KMonitor SUBKTEMP and PUMPHSTEMP.Time (UT)- ΔTime (minutes)-		Pump Heat Switch				
The TCL script ends after       SUBKTEMP       ~1.9 K         execution of this step       PUMPHSTEMP       ~13 K         6       Monitor SUBKTEMP and PUMPHSTEMP.       Time (UT)       -         ΔTime (minutes)       -       -			EVHSV	~565 mV		
execution of this stepPUMPHSTEMP~13 K6Monitor SUBKTEMP and PUMPHSTEMP.Time (UT) ΔTime (minutes)-		The TCL script ends after	SUBKTEMP	~1.9 K		
6Monitor SUBKTEMP and PUMPHSTEMP.Time (UT) ΔTime (minutes)-		execution of this step	PUMPHSTEMP	~13 K		
<b>PUMPHSTEMP.</b> $\Delta Time \ (minutes)$	6	Monitor SUBKTEMP and	Time (UT)	-		
		PUMPHSTEMP.	$\Delta Time$ (minutes)			
Cooler recycle procedure		Cooler recycle procedure				
<i>completes when SUBKTEMP</i> SUBKTEMP ~ 0.285 K		completes when SUBKTEMP	SUBKTEMP	~ 0.285 K		
<i>reaches</i> ~ 0.285 K and PUMPHSTEMP ~16.5 K		reaches $\sim 0.285$ K and	PUMPHSTEMP	~16.5 K		
PUMPHSTEMP reaches ~16.5 K.		PUMPHSTEMP reaches ~16.5 K.				
Test Result (Pass/Fail):	Test ]	Result (Pass/Fail):				
Actual Duration of SPIRE Cooler Recycle Procedure:	Actua	al Duration of SPIRE Cooler Recvo	cle Procedure:			

Final Configuration: Cooler recycled



Procedure: SPIRE-IMT-PHOTSTBY Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Switch on the Photometer detectors and reset offsets. Duration: ~ 10 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are off
- DPU and OBS PARAMETERS display is selected on the CCS

**Initial Configuration:** SPIRE is in REDY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected	Actual	Pass/
			Values	Values Before/After	Fail
			<b>Before</b> /After		
1	Execute TCL script SPIRE-				
	IMT-PDET-ON-STEP1.tcl	SCUDCDCSTAT	0/1		
2	Execute TCL script SPIRE-	MODE	REDY/		
	IMT-PDET-ON-STEP2.tcl		PHOTSTBY		
	Wait for I-EGSE staff to				
	execute manual procedure				
	to set equivalent power in				
	BSM coils				
3	Wait for the I-EGSE staff	—	—	—	
	to confirm the success or				
	failure of step 2				
4	If step 2 is a success,				
	execute TCL script				
	SPIRE-IMT-NOMINAL-				
	BIAS-P.tcl				
	Contingency:				
	If step 2 is a failure then				
_	execute steps 5 and then 6				
5	Execute TCL script				
	SPIRE-IMT-JFET-OFF-				
	P.tcl. (Consult with IEGSE				
6	staff)				
6	Execute TCL script SPIRE-	—	—	—	
	IMT-PDET-ON-STEP2.tcl				
	This requires the I-EGSE				
	to switch on the JFET				
	heater by updating CUS				
	script input parameter.				
Test l	Result (Pass/Fail):				



**Ref:** SPIRE-RAL-PRC-002512 Issue: 1.0 Date: 15/09/05 Page: 13 of 30

# Final Configuration: SPIRE mode PHOTSTBY



# Procedure: SPIRE-IMT-DNA-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: To determine Photometer noise versus bias level and frequency Duration: ~4 hours maximum

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

# Initial Configuration: SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected	Actual	Pass/
			Values	Values Before/After	Fail
			<b>Before</b> /After		
1	If required, execute TCL				
	script SPIRE-IMT-BIAS-				
	FREQ-P.tcl				
	Consult with IEGSE staff				
2	Execute TCL script SPIRE-				
	IMT-BIAS-AMPL-P.tcl				
3	Execute TCL script SPIRE-				
	IMT-PHASEUP-P.tcl				
4	Execute TCL script SPIRE-			_	
	IMT-GET-P.tcl				
5	Note 1: Repeat steps 2-4 for				
	as many bias amplitudes as				
	required.				
	Note 2: Repeat steps 1-4 for				
	as many bias frequencies as				
	required				
6	Wait for the I-EGSE staff	_		—	
	to confirm the success or				
	failure of this test				
Test ]	Result (Pass/Fail):				



Procedure: SPIRE-IMT-BIAS-FREQ-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Set up for clean bias level frequency and nominal bias level for Photometer Duration: ~ 10 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

Initial Configuration: SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail
1	Execute TCL script SPIRE- IMT-BIAS-FREQ.tcl				
2	Wait for the I-EGSE staff to confirm the success or failure of this test				
Test l	Result (Pass/Fail):				



Procedure: SPIRE-IMT-PHASEUP-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Phase up to maximise signal. Note that this test will probably have to be repeated 2-3 times in succession to optimise the phase. Duration: ~ 30 minutes

#### **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

#### Initial Configuration: SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail
1	Execute TCL script SPIRE- IMT-PHASEUP-P.tcl				
2	Wait for the I-EGSE staff to confirm the success or failure of this test				
Test	Result (Pass/Fail):				



Procedure: SPIRE-IMT-LC-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Load curve at fixed frequency and phase Duration: ~ 15 minutes (TBC)

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

**Initial Configuration:** SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail			
1	Execute TCL script SPIRE- IMT-LC-P.tcl							
2	Wait for the I-EGSE staff to confirm the success or failure of this test							
Test l	Test Result (Pass/Fail):							



Procedure: SPIRE-IMT-LC-PLUS90-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Load curve at fixed frequency and phase + 90° Duration: ~ 15 minutes (TBC)

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

**Initial Configuration:** SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail		
1	Execute TCL script SPIRE- IMT-LC-P.tcl						
2	Wait for the I-EGSE staff to confirm the success or failure of this test						
Test l	Test Result (Pass/Fail):						



Procedure: SPIRE-IMT-LC-MINUS90-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Load curve at fixed frequency and phase - 90° Duration: ~ 15 minutes (TBC)

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

**Initial Configuration:** SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail			
1	Execute TCL script SPIRE- IMT-LC-P.tcl							
2	Wait for the I-EGSE staff to confirm the success or failure of this test							
Test l	Test Result (Pass/Fail):							



Procedure: SPIRE-IMT-SET-BIAS-AMPL-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Set optimum bias for Photometer detectors and reset offsets Duration: ~ 5 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

Initial Configuration: SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail
1	Execute TCL script SPIRE-IMT-SET-BIAS- AMPL-P.tcl	PLWBIAS	-/~16.5 mV		
2	Wait for the I-EGSE staff to confirm the success or failure of this test				
Test	Result (Pass/Fail):				



Procedure: SPIRE-IMT-PHASEUP-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Phase up to maximum signal for optimum bias settings. Note that it may be necessary to repeat this test. Duration: ~ 10 minutes

#### **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

#### Initial Configuration: SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail
1	Execute TCL script SPIRE- IMT-PHASEUP-P.tcl		_		
2	Wait for the I-EGSE staff to confirm the success or failure of this test				
Test l	Result (Pass/Fail):				



Procedure: SPIRE-IMT-PCAL-LEVEL Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Run PCAL static test to check calibration Duration: ~ 15 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

**Initial Configuration:** SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail
1	Execute TCL script SPIRE- IMT-PCAL-LEVEL.tcl CUS observing mode : Mode_ILT_PERF_CPC_P TestControl script: ILT_PERF_CPC_P.tcl				
2	Wait for the I-EGSE staff to confirm the success or failure of this test				
Test	Kesult (Pass/Fail):				



Procedure: SPIRE-IMT-PCAL-FLASH Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Run PCAL Flash Duration: ~ 15 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

**Initial Configuration:** SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail			
1	Execute TCL script SPIRE- IMT-PCAL-FLASH.tcl							
2	Wait for the I-EGSE staff to confirm the success or failure of this test							
Test l	Test Result (Pass/Fail):							



Procedure: SPIRE-IMT-SCAN-MODE-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Thermal test case to switch to Photometer scan mode Duration: ~ 60 minutes?

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

**Initial Configuration:** SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail
1	No script necessary. Wait for the I-EGSE staff to signal start of this test.				
2	Wait for the I-EGSE staff to confirm the success or failure of this test				
Test ]	Result (Pass/Fail):				



Procedure: SPIRE-IMT-CHOP-MODE-P Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Thermal test case to switch to Photometer chop mode Duration: ~ 60 minutes?

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

**Initial Configuration:** SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected	Actual	Pass/
			Values	Values Before/After	Fail
			<b>Before</b> /After		
1	No script necessary.				
	Wait for the I-EGSE staff				
	to manually apply power				
	to BSM using external				
	(GSE) supply.				
2	Wait for the I-EGSE staff	—	—	—	
	to confirm the success or				
	failure of this test				
Test	Result (Pass/Fail):				



# Procedure: SPIRE-IMT-PHOT2SPEC Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Thermal test case to switch from PHOTSTBY to SPECSTBY mode Duration: ~ 10 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

**Initial Configuration:** SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected	Actual	Pass/
			Values	Values Before/After	Fail
			<b>Before</b> /After		
1	Execute script SPIRE-IMT-	MODE	PHOTSTBY/		
	PDET-OFF.tcl		REDY		
2	Execute script SPIRE-IMT-	MODE	REDY/		
	SDET-ON.tcl		SPECSTBY		
3	Wait for the I-EGSE staff		—	—	
	to confirm the success or				
	failure of this test				
Test ]	Result (Pass/Fail):				

Final Configuration: SPIRE is in SPECSTBY mode.



Procedure: SPIRE-IMT-SPEC-MODE Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Thermal test case for Spectrometer mode Duration: ~ 60 minutes?

# **Preconditions:**

- SCU AC and DC thermometry is on
- The Photometer detectors are on
- DPU and OBS PARAMETERS display is selected on the CCS

Initial Configuration: SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail
1	No script necessary				
2	Wait for the I-EGSE staff to manually apply power to SMEC using external (GSE) supply.	_	_		
3	Wait for the I-EGSE staff to confirm the success or failure of this test				
Test ]	Result (Pass/Fail):				

Final Configuration: SPIRE is in SPECSTBY mode.



Procedure: SPIRE-IMT-CREC-PARALLEL Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: Recycle SPIRE cooler for SPIRE/PACS parallel mode test Duration: ~ 2.5 hours

# **Preconditions:**

- SCU AC and DC thermometry is on
- DPU and OBS PARAMETERS display is selected on the CCS
- SCU PARAMETERS display is selected on the CCS
- Wait for SPIRE Cooler exhaustion (~ 30-32 hours after last recycle)
- Start this test ~ 25 minutes after PACS recycle

Initial Configuration: SPIRE is in SPECSTBY mode and the cooler is discharged.

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail	
1	Execute script SPIRE-IMT- SDET-OFF.tcl	MODE	SPECSTBY/ REDY			
2	Follow Procedure SPIRE- IMT-CREC					
3	Follow Procedure SPIRE- IMT-PHOTSTBY to switch SPIRE into PHOTSTBY mode	MODE	REDY/ PHOTSTBY			
4	Wait for the I-EGSE staff to confirm the success or failure of this test					
Test Result (Pass/Fail):						

Final Configuration: SPIRE cooler is recycled in parallel with the PACS cooler



Procedure: SPIRE-IMT-PARALLEL-SCAN Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: To switch to SPIRE parallel mode for scan observations Duration: ~ 2 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- DPU and OBS PARAMETERS display is selected on the CCS
- Procedure SPIRE-IMT-CREC-PARALLEL has been completed successfully
- Photometer detectors are switched on

#### Initial Configuration: SPIRE is in PHOTSTBY mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Pass/ Fail	
1	Execute script SPIRE-IMT- PARALLEL-SCAN.tcl	MODE	PHOTSTBY/ PARALLEL			
2	Wait for the I-EGSE staff to confirm the success or failure of this test					
Test Result (Pass/Fail):						

Final Configuration: SPIRE is in PARALLEL mode



Procedure: SPIRE-IMT-PARALLEL-CHOP Version: 1.0 Date: 23<sup>rd</sup> Aug 2005 Purpose: To switch to SPIRE parallel mode for chop observations Duration: ~ 2 minutes

# **Preconditions:**

- SCU AC and DC thermometry is on
- DPU and OBS PARAMETERS display is selected on the CCS
- Procedure SPIRE-IMT-CREC-PARALLEL has been completed successfully
- Photometer detectors are switched on
- Wait until temperatures have stabilised

#### Initial Configuration: SPIRE is in PARALLEL mode

#### **Procedure Steps:**

Step	Description	Parameter	Expected	Actual Values Defense/After	Pass/	
			Before/After	values before/After	гап	
1	Execute script SPIRE-IMT- PARALLEL-CHOP.tcl		_			
2	Wait for I-EGSE staff to execute manual procedure to set equivalent power in BSM coils					
3	Wait for the I-EGSE staff to confirm the success or failure of this test		_			
Test Result (Pass/Fail):						