








Test Report

Herschel

Title: Test Report For Integrated FM SPIRE Warm Units UFT

CI-No: 125200

Prepared by:	S. Hamer/TERMA AS 	Date:	4th May 2007
Checked by:	S. Idler 		05-05-2007
Product Assurance:	R. Stritter 		04.05.07
Configuration Control:	W. Wietbrock 		15.05.07
Project Management:	W. Fricke 		15/05/07

Distribution: See Distribution List (last page)

Copying of this document, and giving it to others and the use or communication of the contents thereof, are forbidden without express authority. Offenders are liable to the payment of damages. All rights are reserved in the event of the grant of a patent or the registration of a utility model or design.

Issue	Date	Sheet	Description of Change	Release
1	04.05.07	All	Formal Issue	

Table of Content

0	Test Summary	6
0.1	Unit tested	6
0.2	Applied Procedures:	6
0.3	Procedure Execution Summary:	6
0.4	Summary Conclusion	7
0.5	Open Issues:	7
1	Scope	8
1.1	Objective	8
1.2	Test Flow	8
2	Documents/Drawings	10
2.1	Applicable Documents	10
2.2	Reference Documents	10
2.3	Other Documents	10
2.4	Acronyms & Abbreviations	10
3	Main Observations and Problems Identified	11
3.1	DPU Prime EEPROM Failure (NCRs: 3204)	11
3.2	No Communication on DPU Redundant MilBus Interface (NCR-3205)	11
3.3	HPCCS Session Start Anomalies (NCR-3275)	11
3.4	HPCCS Appears to Receive TM Packets in Bursts (NCR-3276)	11
3.5	Switch On Sequence for DRCU (FCU) (NCR-3211)	12
3.6	MCU Voltages Out-Of-Limits (NCR-3277)	12
3.7	DCU High Speed Checks only Working for Full Photometer Mode (NCR-3210)	12
3.8	Procedure Changes	13
3.9	Re-Run Of SPIRE Prime UFT with DRCU Simulator	13
4	Conclusion	14
5	Appendix 1: FM SPIRE UFT As-Run Procedure	15



Table of Figures

None



List of Tables

Table 1: FM SPIRE Warm Units UFT Summary7

0 Test Summary

0.1 Unit tested

FM SPIRE Warm Units

PFM DPU, PN: 20-SPIRE-00.00, S/N: 01

DRCU: PFM DCU, PFM FCU

0.2 Applied Procedures:

FM SPIRE Warm Units UFT HP-2-ASED-TP-0148, Issue 1 Redlined

ACS: SPIRE PRIME FM UFT with DRCU Simulator

HP-2-ASED-SD-0164 Issue 1

0.3 Procedure Execution Summary:

FM SPIRE WU TRR: 05.04.2007 HP-ASP-MN-9005

FM SPIRE WU UFT: 11-12.04.2007 see Appendix 1 for "as-run"

FM SPIRE WU PTR: 13.04.2007 HP-ASP-MN-9006

Location: Astrium-EADS, Friedrichshafen

Test Session Name 1: 2007_04_11_04_44_hercdmu_hpws23_REALTIME

Environment: H_ASTRUM_ENV

Any procedure variations are recorded in the Procedure Variation Summary in § 7.1 for the corresponding "as-run" procedure.

All non-compliances are recorded in the Observation/NCR Summary below and detailed further in Section 3.

The following main observations were made during the test or in the post-test results analysis:

Section/ Step No.	Description	Item Affected	NCR Raised	Affects Test Objective
Pre-Test	DPU Prime EEPROM failure (primary partition, secondary partition OK)	FM DPU	3204	No
Pre-Test	MilBus Interface not working on DPU Redundant during Integration (Procedure error – redline correction to UFT procedure)	Procedure	3205	No
Pre-Test	HP CCS session start problems	HPCCS	3275	No
§6.2.2 – 6.2.23	TM packets received in bursts on HPCCS.	HPCCS	3276	No
§6.2.3 & §6.2.14	Switch on Sequence for DRCU (FCU) Prime & Redundant incorrect	Procedure	3211	No
§6.2.6 Step 6.2 & §6.2.17 Step 17.2	Voltages out of limits for MCU Prime parameter MCUP15C & MCU Prime & Redundant parameter MCUM15V	Spec. (EIDP)	3277	No
§6.2.9 Step 9.3 & §6.2.20. Step 20.3	DCU Prime & Redundant High Speed check only works for Full Photometer packets	Test Script	3210	Yes

Table 1: FM SPIRE Warm Units UFT Summary

0.4 Summary Conclusion

The FM SPIRE Unit Functional Test (UFT) has been performed using version 2.2.G of the DPU OBSW with both FM DRCU and DRCU simulator.

There are a couple of open issues arising from the integration and UFT activities, which are listed in the following section.

A number of Non-Conformance Reports (as listed above) were raised, prior to, or during the test and only one affected the test objectives (NCR-3210). However, subsequently a new test script has been provided by SPIRE and the re-test demonstrated that all Spectrometer and Photometer packets were produced correctly.

0.5 Open Issues:

- SPIRE PRIME DPU EEPROM Partition 1 Failure (NCR-3204);
- SPIRE DCU High Speed Checks on both Main & Redundant units (NCR-3210), however it is believed that this is related to a SPIRE test script problem rather than an onboard;

1 Scope

This document reports on the UFT performed on the FM SPIRE Instrument warm units to check correct operation, after they have been electrically integrated with the FM SVM, using the Herschel CCS.

It also addresses the repeat UFT on SPIRE PRIME DPU using the DRCU Simulator.

1.1 Objective

The objectives of the UFT and software upload were:

1. To check as much as possible the correct functional operation of the integrated FM SPIRE warm units;
2. To re-check the correct functional operation of the FM SPIRE DPU PRIME with the DRCU Simulator for use in the development of the IST Reference Mission Scenario where the FM FPU will not be available;
3. To act as baseline procedure on which the SPIRE specific aspects of the satellite level SFT and IST procedures can be developed;

The UFT verified the following for SPIRE warm units:

- Power on/off of FM SPIRE Prime & Redundant (CDMS/PCDU Interface) warm units (DPU + DRCU);
- Health Status HKTM Acquisition from SPIRE Prime (CDMS Interface);
- DRCU SCU/MCU/DCU High/Low Speed Link Checks;

1.2 Test Flow

The UFT test flow was structured to reflect nominal operations of SPIRE as much as possible to enable re-use for PFM and higher-level Satellite tests (SFT and IST).

The flow is as follows:

1. Power on and configure EGSE for test
2. Power on and configure SVM for test
3. Power on NOMINAL SPIRE warm units and enable Mil1553B-bus interface
4. Simulated SCU Prime Low Speed Link Check
5. Simulated SCU Prime High Speed Link Check
6. Simulated MCU Prime Low Speed Link Check
7. Simulated MCU Prime High Speed Link Check

8. Simulated DCU Prime Low Speed Link Check
9. Simulated DCU Prime High Speed Link Check
10. Disable Mil1553B-bus interface and Power off NOMINAL SPIRE warm units
11. Repeat Steps 3-10 for SPIRE Redundant Units
12. Repeat Prime UFT (steps 3-10) using FM DPU & DRCU Simulator
13. Power off SVM
14. Switch off all EGSE

2 Documents/Drawings

2.1 Applicable Documents

AD 1 Unit Functional Test of Integrated FM SPIRE Warm Units HP-2-ASED-TP-0148

2.2 Reference Documents

None

2.3 Other Documents

None

2.4 Acronyms & Abbreviations

See "as-run" procedure.

3 Main Observations and Problems Identified

3.1 DPU Prime EEPROM Failure (NCRs: 3204)

Observed: Pre-Test: Instrument Warm Unit Electrical Integration

EEPROM Failure in Primary Partition of DPU Prime detected during Warm Unit Integration. NRB agreed to use secondary partition for formal UFT. New test script provided by SPIRE to force boot from the secondary partition. Procedure redlined to reference this new test script.

3.2 No Communication on DPU Redundant MilBus Interface (NCR-3205)

Observed: Pre-Test: Instrument Warm Unit Electrical Integration

No communication was observed on DPU Redundant Interface during electrical integration. Identified as a CDMU commanding error (wrong bit set in ConfigureSDBFDIR – DC005161 - command). Procedures redlined accordingly – no impact on UFT execution.

3.3 HPCCS Session Start Anomalies (NCR-3275)

Observed: Pre-Test: HPCCS Session Start

Start of test was delayed due to a number of HPCCS session start up problems. Initial attempt to start a Real—Time session failed with errors. Following attempt no communication could be established with the Power SCOE. Third attempt HPCCS reported errors in generating TM cache.

3.4 HPCCS Appears to Receive TM Packets in Bursts (NCR-3276)

Observed: Full Test Duration

TM Packets from satellite appear to be arriving in bursts even though they are generated at regular intervals. Default switch on configuration of SVM enables all 3 TM Packets (DLCM, Monitoring Mode 1 & Monitoring Mode 2) for downlink from CCU A & B. However, only one of the above should be downlinked at any one time. Moreover, none should be downlinked when CCU switched off (as was the case for the UFT). These packets were disabled as per Procedure Variation Sheet 1, which appeared to have some effect but regular bursts were still observed afterwards. Alenia on-site support suggests it is possibly related to the TM DFE but needs further investigation.

3.5 Switch On Sequence for DRCU (FCU) (NCR-3211)

Observed: Sections 6.2.3 & 6.2.14

Switch on sequence for DRCU(FCU) incorrect for both main and redundant units. HK TM packets need to be stopped before closing the FCU LCL and then restarted afterwards. The test did not fail with the incorrect sequence used on DRCU Prime. However, the correct sequence was attempted on DRCU Redundant but failed. This was identified as a timing problem between disabling HKTM packets generation and restarting, resulting in the CDMS declaring SickTM on the MilBus interface, as it considered the DPU to have failed as no TM packets had arrived within its timeout period.

After the formal UFT test run the required switch on sequence was repeated in a more timely fashion and this was successful.

It needs to be clarified what timeout period the CDMS uses to detect a problem on the MilBus TM interface.

3.6 MCU Voltages Out-Of-Limits (NCR-3277)

Observed: Sections 6.2.6 Step 6.2 (MCU Prime) & 6.2.17 Step 17.2 (MCU Redundant)

A number of MCU voltages were slightly outside their nominal limits.

MCU Prime:

MCUP15V 15.54V (High Limit = 15.50V)

MCUM15V -15.63V (Low Limit = -15.50V)

MCU Redundant:

MCUM15V -15.61V (Low Limit = -15.50V)

3.7 DCU High Speed Checks only Working for Full Photometer Mode (NCR-3210)

Observed: Sections 6.2.9 Step 9.3 (DCU Prime) & 6.2.20 Step 20.3 (DCU Redundant)

Execution of test script SPIRE-WU-INT-MCU-02-P(R).tcl results in Science Packets only being generated for Full Photometer (TM Pkt 21,1 APID 1284(P) or 1285 (R).

Believed to be a test script timing problem. New test script provided, to be tested under cover of ACS HP-2-ASED-SD-0166 as part of the NCR investigation.

3.8 Procedure Changes

Several updates and clarifications in the UFT procedure were required. The procedure was redlined accordingly for inclusion, where relevant, in the FM UFT procedure. Main updates covered:

- DPU Redundant MilBus Configuration parameter to be set to 1 indicating Redundant Unit
- Reference to new test script (SPIRE-WU-INT-DPU-START-P-SP.tcl) to boot from DPU Prime secondary EEPROM Partition.
- DRCU Switch On Sequence corrected and warning added.

3.9 Re-Run Of SPIRE Prime UFT with DRCU Simulator

The Reference Mission Scenario cannot be run on the FM SPIRE Warm Units alone. Therefore a repeat test was performed with the DRCU Simulator in place of the FM DRCU under cover of ACS: HP-2-ASED-SD- 0164. All test steps were executed successfully with the known exceptions in the number of science packets generated by the DRCU Simulator (ref. NCR-3274) identified during the AVM SPIRE WU UFT.

4 Conclusion

The FM SPIRE Warm Units UFT was successfully performed apart from two open issues; DCU High Speed Checks failure to produce expected frames (ref. NC-3210). Secondly, the SPIRE PRIME UFT had to be performed booting from the secondary partition of DPU EEPROM (ref. NC-3204).

Post test investigations into the DCU High Speed Checks failure (NC-3210) have shown that the problem was related to a test script. A new test script has been provided by SPIRE and a re-test demonstrated that all Spectrometer and Photometer packets were produced correctly.

The repeat of the FM PRIME UFT using the DRCU Simulator was successful.

All other problems observed during the UFT, and NCRs raised, were primarily related to the EGSE configuration, procedural or documentation issues.

All procedures have been redlined for update in readiness for any repeat of the FM SPIRE UFT.


5 **Appendix 1: FM SPIRE UFT As-Run Procedure**


AS RUN.
REDLINED
MASTER


Title: Unit Functional Test of Integrated FM SPIRE Warm Units


CI-No: 125200

Prepared by: S. Hamer/TERMA AS  Date: 31st March 2007

Checked by: S. Idler  2.4.2007

Product Assurance: for R. Stritter  4.4.2007

Configuration Control: W. Wietbrock  4.4.2007

Project Management: for W. Fricke  4.4.2007

Distribution: See Distribution List (last page)

Copying of this document, and giving it to others and the use or communication of the contents thereof, are forbidden without express authority. Offenders are liable to the payment of damages. All rights are reserved in the event of the grant of a patent or the registration of a utility model or design.

Issue	Date	Sheet	Description of Change	Release
1.0	31.03.07	All	First Formal Issue	

Table of Content

1	Scope	7
1.1	Objective	7
1.2	Test Flow	7
2	Documents/Drawings	9
2.1	Applicable Documents	9
2.2	Reference Documents	9
2.3	Other Documents	10
2.4	Acronyms & Abbreviations	10
3	Configuration	14
3.1	Satellite Configuration	14
3.2	EGSE Configuration	14
3.3	Set-up	14
4	Conditions	16
4.1	Personnel	16
4.2	Environmental	16
4.3	General Precautions and Safety	17
4.3.1	General Safety Requirements, Precautions	17
4.3.2	ESD constraints	17
4.3.3	Special QA Requirements	17
4.4	GSE	17
4.4.1	MGSE	17
4.4.2	CVSE	17
4.4.3	EGSE	17
4.4.4	OGSE	17
4.4.5	Special Equipment	18
5	Verification Requirements and Test Criteria	19
6	Test Procedure	20
6.1	Initial EGSE and Satellite Configuration for the Test	20
6.2	Step by Step Procedure	20

6.2.1	EGSE & Satellite Switch On	20
6.2.2	Switch On SPIRE PRIME DPU	21
6.2.3	Switch On DRCU Prime	27
6.2.4	Check correct functioning of the SCU PRIME Low Speed Link	29
6.2.5	Check correct functioning of the SCU PRIME High Speed Link	30
6.2.6	Check correct functioning of the MCU PRIME Low Speed Link	30
6.2.7	Check correct functioning of the MCU PRIME High Speed Link	31
6.2.8	Check correct functioning of the DCU PRIME Low Speed Link	33
6.2.9	Check correct functioning of the DCU PRIME High Speed Link	34
6.2.10	Switch Off MCU Prime	35
6.2.11	Switch Off DRCU PRIME	35
6.2.12	Switch Off SPIRE DPU Prime Unit	36
6.2.13	Switch On Redundant SPIRE Units	39
6.2.14	Switch On DRCU REDUNDANT	45
6.2.15	Check correct functioning of the SCU REDUNDANT Low Speed Link	46
6.2.16	Check correct functioning of the SCU REDUNDANT High Speed Link	47
6.2.17	Check correct functioning of the MCU REDUNDANT Low Speed Link	47
6.2.18	Check correct functioning of the MCU REDUNDANT High Speed Link	48
6.2.19	Check correct functioning of the DCU REDUNDANT Low Speed Link	49
6.2.20	Check correct functioning of the DCU REDUNDANT High Speed Link	49
6.2.21	Switch Off MCU REDUNDANT	50
6.2.22	Switch Off DRCU REDUNDANT	51
6.2.23	Switch Off Redundant SPIRE Units	52
6.2.24	Satellite & EGSE Switch Off	55
7	Summary Sheets	56
7.1	Procedure Variation Summary	57
7.2	Non Conformance Report (NCR) Summary	58
7.3	Sign-off Sheet	59

Table of Figures

Figure 4-1: FM SPIRE UFT Configuration14

List of Tables

Table 8.1-1: Procedure Variation Sheet57
Table 8.2-1: Non-Conformance Record Sheet.....58

1 Scope

This document describes the set of functional tests to be performed on the FM SPIRE Instrument to check correct operation using the Herschel CCS after it has been electrically integrated with the FM SVM.

Specifically the functional test will verify the following for both prime and redundant SPIRE warm units:

- **Power on/off of FM SPIRE (CDMS/PCDU Interface) warm unit and DRCU (FCU)**
- **Health Status HKTM Acquisition from SPIRE (CDMS Interface)**
- **Check of SCU Prime Low & High Speed Links**
- **Check of MCU Prime Low & High Speed Links**
- **Check of DCU Prime Low & High Speed Links**

Constraint

This test shall only be executed upon successful completion of the FM SPIRE integration activities as defined in ref. AD1.

1.1 Objective

The objective of the test is twofold:

1. To check as much as possible the correct functional operation of the integrated FM SPIRE warm units.
2. To act as baseline procedure on which the SPIRE specific aspects of the satellite level SFT and IST procedures can be developed.

1.2 Test Flow

This test flow is structured to reflect nominal operations of the FM SPIRE as much as possible to enable re-use for higher-level Satellite tests (SFT and IST).

The flow is as follows:

1. Power on and configure EGSE for test
2. Power on and configure SVM for test
3. Power on NOMINAL SPIRE Prime DPU and enable Mil1553B-bus interface
4. Power on DRCU(FCU) Prime

5. Check of SCU Prime Low & High Speed Links
6. Check of MCU Prime Low & High Speed Links
7. Check of DCU Prime Low & High Speed Links
8. Power off MCU Prime
9. Power off DRCU(FCU) Prime
10. Disable Mil1553B-bus interface and Power off SPIRE Prime DPU
11. Repeat Steps 3 – 10 for Spire Redundant including bus
12. Power off SVM
13. Switch off all EGSE

2 Documents/Drawings

2.1 Applicable Documents

AD 1	FM SPIRE Integration to Herschel SVM Procedure	HP-2-ASED-TP-125
AD 2	Herschel PCDU & CDMS Nominal Switch On/Off Procedure	HP-2-ASED-PR-070 in preparation
AD 3	Herschel SAT Emergency Switch Off Procedure	HP-2-ASED-PR-071
AD 4	PA Plan	HP-2-ASED-PL-0007
AD 5	I-EGSE Switch ON/OFF Procedure	TBI
AD 6	Test Specification for Herschel Instrument AVM & FM Tests Performed at Satellite Level	H-P-2-ASP-TS-1083
AD 7	H-P GDIR	H-P-1-ASPI-SP-0027
AD 8	SPIRE I-EGSE Set-Up, Issue 1.2	SPIRE-RAL-DOC-002841

2.2 Reference Documents

RD 1	Herschel Planck Central Checkout System System User Manual	H-P-4-TE-MA-0010
RD 2	N/A	N/A
RD 3	Herschel CDMU ASW S/W Interface Control Document	H-P-4-SSF-IC-0001
RD 4	Herschel CDMU BSW S/W Interface Control Document	H-P-4-SES-NT-0076
RD 5	SPIRE IID-B	SCI-PT-IIDB/SPIRE-02124
RD 6	SPIRE Warm Units Integration Test Procedures Iss. 1.3	SPIRE-RAL-PRC-2680
RD 7	SPIRE Functional Test Specification Iss. 1.4	SPIRE-RAL-DOC-001652
RD 8	SPIRE ILT Warm Unit Functional Test Procedure Iss. 1.2	SPIRE-RAL-PRC-002322
RD 9	SPIRE Instrument User Manual Iss. 1.0	SPIRE-RAL-PRJ-002395

RD 10	H/P OBT-UTC Time Synchronisation Technical Note Iss. 1.3	PT-CMOC-OPS-TN-6604- OPS- OGH
RD 11	Operating Manual DRCU Simulator, Iss 1	SPIRE-STK-PRC-001744

2.3 Other Documents

None

2.4 Acronyms & Abbreviations

1553	MIL-STD-1553B conform communication interface
AAD	Attitude Anomaly Detector
ACC	ACMS Control Computer
ACMS	Attitude Control and Measurement Subsystem
AD	Applicable Document
AIR	ACC In Reconfiguration
AIT	Assembly, Integration and Test
AIV	Assembly, Integration and Verification
APID	Application Process ID
ASW	Application Software
AVM	Avionics Model
BOLC	BOLometer Control unit (PACS)
BSW	Basic Software
CBH	Catalyst Bed Heater
CCS	Central Check-out System
CCSDS	Consultative Committee for Space Data Systems
CDMU	Control and Data Management Unit
CDMS	Control and Data Management Sub-system
CIR	CDMU In Reconfiguration
CLCW	Command Link Control Word
CLTU	Command Link Transmission Unit
CPDU	Command Pulse Distribution Unit
CRS	Coarse Rate Sensor
CTR	Central on board Reference Time

DCU	Detector Control Unit (SPIRE)
DEC	Detectors Electronics Control unit (PACS)
DMC	Detector and Mechanism Control unit (PACS)
DPU	Digital Processing Unit
DRCU	Detector Readout & Control Unit (SPIRE)
EEPROM	Electrically Erasable PROM
EGSE	Electrical Ground Support Equipment
FCL	Fold-back Current Limiter
FCU	FPU Control Unit (Spire)
FCV	Flow Control Valves
FDIR	Failure Detection, Isolation, and Recovery
FPU	Focal Plane Unit
GDIR	General Design and Interface Requirement
GRP	Group Heaters Switch
HBR	High Bit Rate
HL/HLC	High Level command
HP/HPC	High Priority commands
HPLM	Herschel PayLoad Module
HPADB	Herschel Planck System Data Base
HW	Hardware
i.a.w.	In accordance with
I/F	InterFace
I/O	Input/Output
ICD	Interface Control Document
IST	Integrated System Test
LCL	Latching Current Limiter
LV	Latching Valves
LBR	Low Bit Rate
MAP	Multiplexed Access Point
MBR	Medium Bit Rate
MCU	Mechanisms Control Unit (SPIRE)
MEC	Mechanisms Electronics Control unit (PACS)

ML 16	Memory Load command (ML 16)
MM	Memory Module
MOIS	Mission Operations Information System
MTL	Mission Timeline
NRZ-L	Non Return to Zero – Litton
OBCP	On-Board Control Procedure
OBDH	On-Board Data Handling
OBMF	On-Board Monitoring Function
OBRT/OBT	On-Board Reference Time
OIRD	Operation Interface Requirement Document
PACS	Photodetector Array Camera & Spectrometer
P/L	Payload
PCDU/PCS	Power Control Distribution Unit/Power Control Subsystem
PM	Processor Module
PROM	Programmable Read Only Memory
PSK	Phase Shift Keying
RA	Rate Anomaly
RAM	Random Access Memory
RCS	Reaction Control Subsystem
RD	Reference Document
RF	Radio Frequency
RM	Reconfiguration Module
RT	1553 Remote Terminal
RTU	RT Unit
RTA	RTU
RWL	Reaction Wheel Assembly
SA	1553 Remote Terminal Sub Address
SAS	Sun Acquisition Sensor
SCOE	Special Check-out Equipment
SCU	Subsystems Control Unit (SPIRE)
SIR	S/C In Reconfiguration
SIT	Subsystem Integrated Test

SP	Sun Pointing
SPIRE	Spectral & Photometric Imaging Receiver
SPU	Signal Processing Unit (PACS)
SSMM	Solid State Mass Memory
STR	Star Tracker
SVM	Service Module
SW	Software
TAI	International Atomic Time
TC	TeleCommand
TFG	Transfer Frame Generator
TM	TeleMetry
TTC	Telemetry Tracking & Command subsystem
TTR	Telemetry Telecommand and Reconfiguration
UFT	Unit Functional Test
VC	Virtual Channel
WD	Watchdog

3 Configuration

The figure below shows the overall EGSE/Satellite configuration for the test.




Figure 3-1: FM SPIRE UFT Configuration

3.1 Satellite Configuration

The test requires use of the FM SVM powered on in its basic test mode (i.e. quick switch on (PCDU & CDMS) in accordance with AD 2.

3.2 EGSE Configuration

This test requires the EGSE to be configured and elements powered on in accordance with AD 2.

I-EGSE shall be configured and connected to the HPCCS in accordance with AD 5 & AD 9.

3.3 Set-up

SPIRE Test Scripts for the test must be loaded on to the HPCCS and checked in to the **H_FM_ASTRUM_ENV** Environment and compiled prior to start of test.

The following test scripts are required for execution on the HPCCS:

No.	Tcl Script Name	Comment	Confirmed
1	SPIRE-WU-INT-DPU-ON-P	DPU Prime power on sequence	
2	SPIRE-WU-INT-DRCU-START-P-STEP1	DRCU PRIME Power up step 1	
3	SPIRE-WU-INT-DRCU-START-P-STEP2	DRCU PRIME Power up step 1	
4	SPIRE-WU-INT-SCU-01-P	SCU Low Speed Link check	
5	SPIRE-WU-INT-SCU-02-P	SCU High Speed Link check	
6	SPIRE-WU-INT-MCU-01-P	MCU Low Speed Link check	
7	SPIRE-WU-INT-MCU-02-P	MCU High Speed Link check	
8	SPIRE-WU-INT-DCU-01-P	DCU Low Speed Link check	
9	SPIRE-WU-INT-DCU-02-P	DCU High Speed Link check	
10	SPIRE-WU-INT-MCU-OFF-P	MCU power off	
11	SPIRE-WU-INT-DRCU-OFF-P	DRCU PRIME power off	
12	SPIRE-WU-INT-DPU-ON-R	DPU Prime power on sequence	
13	SPIRE-WU-INT-DRCU-START-R-STEP1	DRCU PRIME Power up step 1	
14	SPIRE-WU-INT-DRCU-START-R-STEP2	DRCU PRIME Power up step 1	
15	SPIRE-WU-INT-SCU-01-R	SCU Low Speed Link check	
16	SPIRE-WU-INT-SCU-02-R	SCU High Speed Link check	
17	SPIRE-WU-INT-MCU-01-R	MCU Low Speed Link check	
18	SPIRE-WU-INT-MCU-02-R	MCU High Speed Link check	
19	SPIRE-WU-INT-DCU-01-R	DCU Low Speed Link check	
20	SPIRE-WU-INT-DCU-02-R	DCU High Speed Link check	
21	SPIRE-WU-INT-MCU-OFF-R	MCU power off	
22	SPIRE-WU-INT-DRCU-OFF-R	DRCU PRIME power off	
23	SubscribeParams	Subscribe Parameters sequence	

24 SPIRE-WU-INT-DPU-ON-P-SP *DPU Prime power on sequence boot from Secondary partition*

The HPCSS must also have the following MIB files for SPIRE loaded:

HPCCS Software	Version	Comment	Confirmed Installed
SPIRE MIB version	2.2.G2	Valid for both versions of DPU software.	

The SPIRE I-EGSE will be running the following software for the test:

I-EGSE Software	Version	Comment
SPIRE MIB version	2.2.G2	Valid for both versions of DPU software.
SCOS version	2.3e patch 5	

4 Conditions

4.1 Personnel

Responsibility	Name / Organisation
Test Director	A. KOPPE / ASED
Test Conductor	A. Koppe / ASED
EGSE Operator	S. HAMER / TERMA
Electrical Engineer	N/A
Specialist Engineer	N/A
Element Cognizant	S. IDLER / ASED
PA Responsible	B. BARLAGE / ASED
Instrument Representative	S. SIDAER / RAZ
Customer Representative	N/P.
ESA Representative	C. SCHARMBERG

4.2 Environmental

The actual clean room environmental conditions for the test shall be recorded below.

Environmental	Nominal	Actual	P	N
Clean Room Class	class 100000 or better	96	✓	
Temperature	22°C ± 3°C	21.3°C	✓	
Rel. Humidity	40 % - 60 %	48%	✓	
Pressure	Ambient	973.7 hpa	✓	

4.3 General Precautions and Safety

Non-test specific precautions and safety considerations are detailed in section 5.3 of AD 2. Specific safety issues and general precautions for the tests to performed are detailed in the following sections.

4.3.1 General Safety Requirements, Precautions

In the event of unrecoverable anomaly requiring emergency switch off of the satellite, the switch off shall be performed in accordance with AD 3.

4.3.2 ESD constraints

Normal ESD constraints are to be observed when handling SPIRE units.

4.3.3 Special QA Requirements

None.

4.4 GSE

Non-test specific GSE details are provided in section 5.4 of AD 2. Specific GSE needs for the tests to performed are detailed in the following sections.

4.4.1 MGSE

None.

4.4.2 CVSE

None.

4.4.3 EGSE

The I-EGSE is required for this test and will be connected to the HPCCS in accordance with AD 5.

4.4.4 OGSE

None.

4.4.5 Special Equipment

None.

5 Verification Requirements and Test Criteria

This is purely a functional health check of the FM SPIRE warm units and interfaces. No specific requirements are to be verified.

Functional performance and status parameter actual values recorded will be checked during the test and must be the same as the nominal status value indicated.

The test will only be deemed successful once all offline analysis of the results has been performed. Typically, the PTR will be held before completion of this activity and therefore only a preliminary assessment of the test success can be provided to allow disconnection of any specific GSE required for the test and which needs to be removed before further activities can be performed.

6 Test Procedure

6.1 Initial EGSE and Satellite Configuration for the Test

Spire FM Warm Units Integration to Herschel SVM Test Procedure ref. AD 1 SHALL be successfully completed before execution of this procedure.

The EGSE and Satellite SHALL be configured according to AD 2 prior to start of test.

In the event of emergency the Satellite SHALL be switched down according to AD 3.

6.2 Step by Step Procedure

6.2.1 EGSE & Satellite Switch On

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	Install Test Box and Satellite & EGSE Switch On						
1.1	Confirm I-EGSE physically connected to HPCCS	OK		OK			
1.2	If not already on, switch on HPCCS, SCOEs and Satellite/SVM and configure into Basic Test Mode i.a.w. AD 2 Section 7.1 to 7.5						
1.3	Record Test Session Name:	2007_04_11_04_44_hercdmu_hpus23_REALTIME					
1.4	Confirm that EGSE and Satellite are in the correct configuration as per AD 2	OK		OK			
1.5	If not already selected, from HPCCS command CDMU to use SPIRE Bus Profile (Profile 3): <div style="text-align: right;">DC819160</div> SelectActiveSCBP DH049160 =3	OK		OK	AND: ZAD07999 SPIRE Bus Profile		
1.6	Verify correct bus profile selected: <div style="text-align: right;">DEF5F160</div> 3	3		3			

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
1.7	Switch on & configure SPIRE I-EGSE i.a.w. AD5 & AD 9						
1.8	Confirm SPIRE I-EGSE is in the correct configuration as per AD5 & AD 9	OK		OK		SM	
1.9	From HPCCS Test Conductor console issue command to connect to SPIRE I-EGSE connect HIEGSE						
1.10	Confirm from HPCCS and SPIRE I-EGSE that the connection has been established	OK		OK		SM	
START OF SPIRE UFT							
1.11	Load Synoptics INSTRUMENTS on HPCCS to display SPIRE status overview						

6.2.2 Switch On SPIRE PRIME DPU

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
SWITCH ON DPU PRIME							
DPU-A Power On							
Initial Conditions: DPU-A OFF							
2.1	Verify the following PCDU telemetry to verify DPU-A Off: LCL11 Status SpireHsdN_L11 LCL11 current SpireHsN_L11	WM32C565 OFF WM308565 =0.0A		OFF 0.0	AND: ZAD03999 MIM: LCL_HERSCHEL	SM	

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
2.2	Disable CDMU FDIR while DPU switched ON and forced boot (RTA SPIRE used but not relevant) by issuing the following CMDS telecommand and verify on-board execution (x = don't care, either 0 or 1) :						
	ConfigureSDBFDIR	DC005161	OK	OK			
	RTA	DH011161	=21		SPIRE-A		
	F0	DH018161	=x		RTA ON		
	F1	DH019161	=x		RTA Alive		
	F2	DH020161	=x		RTA Well_TC		
	F3	DH021161	=x		RTA Well_TM		
	F4	DH022161	=x		RTA Valid		
	F5	DH023161	=x		RTA Vital/Non-vital		
	F6	DH024161	=x		RT Nominal Unit		
	F7	DH025161	=x		RT TM Retry On/Off		
	F8	DH026161	=x		Bus A Active		
	F9	DH027161	=x		Bus A Healthy/Unhealthy		
	F10	DH028161	=x		Bus B Healthy/Unhealthy		
	F11	DH029161	=0		SDBFDIR Disable		
	M0	DH030161	=0		Mask F0		
	M1	DH031161	=0		Mask F1		
	M2	DH032161	=0		Mask F2		
	M3	DH033161	=0		Mask F3		
	M4	DH034161	=0		Mask F4		
	M5	DH035161	=0		Mask F5		
	M6	DH036161	=0		Mask F6		

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	M7 DH037161 =0				Mask F7		
	M8 DH038161 =0				Mask F8		
	M9 DH039161 =0				Mask F9		
	M10 DH040161 =0				Mask F10		
	M11 DH041161 =1				Mask F11		
	CNT DH042161 =1				Vital RT Loop (1)		
	M_C DH043161 =0				Mask for CNT		
2.3	Verify FDIR disabled DEFJ4160	DISABLED		DISABLED	AND: ZAD07999		
2.4	Switch on RTA and enable Bus A on SPIRE DPU-A (RTA=21) by issuing the following CMDS telecommand and verify on-board execution (x = don't care, either 0 or 1) : ConfigureSDBFDIR	DC005161	OK	OK			
	RTA DH011161 =21				SPIRE-A		
	F0 DH018161 =1				RTA ON		
	F1 DH019161 =1				RTA Alive		
	F2 DH020161 =1				RTA Well_TC		
	F3 DH021161 =1				RTA Well_TM		
	F4 DH022161 =1				RTA Valid		
	F5 DH023161 =x				RTA Vital/Non-vital		
	F6 DH024161 =0				RT Nominal Unit		
	F7 DH025161 =x				RT TM Retry On/Off		
	F8 DH026161 =0				Bus A Active		
	F9 DH027161 =x				Bus A Healthy/Unhealthy		
	F10 DH028161 =x				Bus B Healthy/Unhealthy		

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	F11 DH029161 =x				SDBFDIR Enable/Disable		
	M0 DH030161 =1				Mask F0		
	M1 DH031161 =1				Mask F1		
	M2 DH032161 =1				Mask F2		
	M3 DH033161 =1				Mask F3		
	M4 DH034161 =1				Mask F4		
	M5 DH035161 =0				Mask F5		
	M6 DH036161 =1				Mask F6		
	M7 DH037161 =0				Mask F7		
	M8 DH038161 =1				Mask F8		
	M9 DH039161 =0				Mask F9		
	M10 DH040161 =0				Mask F10		
	M11 DH041161 =0				Mask F11		
	CNT DH042161 =1				Vital RT Loop (1)		
	M_C DH043161 =0				Mask for CNT		
2.5	After 10secs verify SPIRE-A RTA ON: SPIREA_OnOff DED1G161 ON SPIREA_DeadAliv DED1H161 Alive SPIREA_WellStiTM DED1J161 Well SPIREA_ValidInval DED1K161 Valid SPIREA_WellStiTC DED1Z161 Well			ON Alive Well Valid Well	AND: ZAD12999		
2.6	Power on DPU-A by issuing the following SwOn_SpireHSPDU_N_L11 telecommand (CDMS-TC(8,4,112,5)) and verify on-board execution: DC11D170 OK			OK			
2.7	Verify the following PCDU telemetry to verify DPU-A ON:						

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	LCL11 (DPU-A) Status STS_LCL11 LCL11 (DPU-A) current ITLM_LCL11	WM32C565 ON WM308565 0.46 A		ON 0.44A			
2.8	HPCCS Operator to inform SPIRE Responsible that SPIRE DPU Nominal powered	OK		OK			
2.9	On HPCCS start test script SubscribeParams.tcl to handle command parameter packets sent from the I-EGSE	OK		OK			
2.10	On HPCCS start SPIRE-WU-INT-DPU-START-P-SP.tcl test script to configure DPU	OK		OK	Boot from secondary partition		
2.11	Enable CDMU FDIR (RTA SPIRE used but not relevant) by issuing the following CMDS telecommand and verify on-board execution (x = don't care, either 0 or 1) :						
	ConfigureSDBFDIR	DC005161	OK	OK			
	RTA DH011161 =21				SPIRE-A		
	F0 DH018161 =x				RTA ON		
	F1 DH019161 =x				RTA Alive		
	F2 DH020161 =x				RTA Well TC		
	F3 DH021161 =x				RTA Well TM		
	F4 DH022161 =x				RTA Valid		
	F5 DH023161 =x				RTA Vital/Non-vital		
	F6 DH024161 =x				RT Nominal Unit		
	F7 DH025161 =x				RT TM Retry On/Off		
	F8 DH026161 =x				Bus A Active		
	F9 DH027161 =x				Bus A Healthy/Unhealthy		

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	F10 DH028161 =x				Bus B Healthy/Unhealthy		
	F11 DH029161 =1				SDBFDIR Enable		
	M0 DH030161 =0				Mask F0		
	M1 DH031161 =0				Mask F1		
	M2 DH032161 =0				Mask F2		
	M3 DH033161 =0				Mask F3		
	M4 DH034161 =0				Mask F4		
	M5 DH035161 =0				Mask F5		
	M6 DH036161 =0				Mask F6		
	M7 DH037161 =0				Mask F7		
	M8 DH038161 =0				Mask F8		
	M9 DH039161 =0				Mask F9		
	M10 DH040161 =0				Mask F10		
	M11 DH041161 =1				Mask F11		
	CNT DH042161 =1				Vital RT Loop (1)		
	M_C DH043161 =0				Mask for CNT		
2.12	Verify FDIR (re-)enabled DEFJ4160	ENABLED		ENABLED	AND: ZAD07999		
2.13	Check that Nominal and Critical HK packets are arriving at the CCS: SPIRE Nominal HK: <ul style="list-style-type: none"> (type ,subtype) : (3,25) APID : 0x502 (1282) SPIRE Critical HK: <ul style="list-style-type: none"> (type ,subtype) : (3,25) APID: 0x500 (1280) 	OK			OK		

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
2.14	On I-EGSE check that THSK parameter is refreshing every second	OK		OK		SVA	
2.15	On I-EGSE check that TM2N parameter is incrementing by 1 every second	OK		OK		SVA	
2.16	On I-EGSE check that TM1N parameter is incrementing by 1 every 2 second	OK		OK		SVA	
2.17	On CCS check the consistency of the SPIRE on board time to the HCDMU time and the CCS.	OK		OK	<i>[Handwritten scribbles]</i>	SVA	
2.18	On IEGSE check the consistency between SCOS time and THSK and QLA time.	OK		OK		SVA	
SPIRE PRIME DPU POWER ON COMPLETE							

6.2.3 Switch On DRCU Prime

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
SWITCH ON DRCU PRIME							
DRCU-A Power On							
Initial Conditions: DRCU-A OFF							
3.1	Verify the following PCDU telemetry to verify FCU-A Off: LCL51 Status SpireHsfN_L51 LCL51 current SpireHsfN_L51	WM42C565 OFF WM408565 =0.0A		OFF 0.0	AND: ZAD03999 MIM: LCL_HERSHEL		

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
3.2	Power on FCU-A by issuing the following SwOn_SpireHSPDU_N_L51 telecommand (CDMS-TC(8,4,112,5)) and verify on-board execution: DC51D170	OK		OK		Sign	
3.3	Verify the following PCDU telemetry to verify FCU-A ON: LCL51 (FCU-A) Status STS_LCL51 LCL51 (FCU-A) current ITLM_LCL51 WM42C565 WM408565	ON 2.8A0.44		0.42A	Rises to around 2.8A when MCU powered	Sign	
3.4	HPCCS Operator to inform SPIRE Responsible that SPIRE DRCU Nominal powered	OK		OK		Sign	
3.5	On HPCCS start SPIRE-WU-INT-DRCU-START-P-STEP1.tcl test script to configure DRCU	OK		OK		Sign	
3.6	On I-EGSE check that THSK parameter is not refreshing anymore	OK		OK		Sign	
3.7	On I-EGSE check that TM2N parameter is not incrementing anymore	OK		OK		Sign	
3.8	On HPCCS Execute TCL script SPIRE-WU-INT-DRCU-START-P-STEP2.tcl			OK		Sign	
3.9	On I-EGSE check that THSK parameter is refreshing every second	OK		OK		Sign	
3.10	On I-EGSE check that TM2N parameter is incrementing by 1 every second	OK					
3.11	Check that the SCU/DCU voltages show nominal values: SCUP5V SCUP9V	~ 5.2 ± 0.5V ~ 9.0 ± 0.2V		5.24V 9.49V		Sign	

3.2
3.3
3.4
3.5
3.6
3.7
3.8
3.9
3.10
3.11

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	SCUM9V	~-9.0 ± 0.2V		-9.08V			
	BIASP5V	~5.1 ± 0.5V		5.18V			
	BIASP9V	~9.0 ± 0.2V		8.99V			
	BIASM9V	~-9.0 ± 0.2V		-9.05V			
SPIRE PRIME DRCU POWER ON COMPLETE							

6.2.4 Check correct functioning of the SCU PRIME Low Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/ Fail
4.1	On HPCCS Execute TCL script SPIRE-WU-INT-SCU-01-P.tcl		OK	OK		Pass
4.2	On I-EGSE verify:	SCUTEMPSTAT SUBKSTAT	0/0xFFFF 0/1	0/0xFFFF 0/1		Pass

6.2.5 Check correct functioning of the SCU PRIME High Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
5.1	On HPCCS Execute TCL script SPIRE-WU-INT-SCU-02-P.tcl		OK	OK		
5.2	On I-EGSE verify:	SCUFRAMECNT TM5N	0/31 0x3FFF/1	0/31 03FFE/1		Pass
5.3	Verify that two telemetry packets with : <ul style="list-style-type: none"> (type,subtype): (21,1). APID : 0x508 (1288) have been received at CCS		OK	OK		Pass

6.2.6 Check correct functioning of the MCU PRIME Low Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
6.1	On HPCCS Execute TCL script SPIRE-WU-INT-MCU-01-P.tcl		OK	OK		
6.2	On I-EGSE check that the MCU is booted up successfully	MCUBITSTAT MCUP5V MCUP14V MCUM14V	0/-1 ~ 5.0 ± 0.2V ~ 14.0 ± 0.5V ~ -14.0 ± 0.5V	0/1 5.06 14.15 -14.46		OK

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
		MCUP15V	~ 15.0 ± 0.5V	15.54 V	Full current = 0.92 A.	NOK.
		MCUM15V	~ -15.0 ± 0.5V	-15.63 V		

6.2.7 Check correct functioning of the MCU PRIME High Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
7.1	On HPCCS Execute TCL script SPIRE-WU-INT-MCU-02-P.tcl		OK			
7.2	On I-EGSE Record the values of MCUFRAMECNT at the start and end of the test	MCUFRAMECNT	FM: 0/297	0/297		Pass
7.3	Verify that the following type of MCU telemetry packets have been received at the CCS : ENG: - (type,subtype): (21,3). - APID 0x508 (1288) BSM - (type,subtype): (21,1). - APID 0x508 (1288) SMEC -(type,subtype): (21,1).		OK	OK		Pass

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/ Fail
	- APID 0x508 (1288)					

6.2.8 Check correct functioning of the DCU PRIME Low Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
8.1	On HPCCS Execute TCL script SPIRE-WU-INT-DCU-01-P.tcl		OK	OK		
8.2	On I-EGSE check that:	PSWBIAS PMWBIAS PLWBIAS	0/0xff/0 0/0xff/0 0/0xff/0	0/0xff/0 0/0xff/0 0/0xff/0		Pass

6.2.9 Check correct functioning of the DCU PRIME High Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
9.1	On HPCCS Execute TCL script SPIRE-WU-INT-DCU-02-P.tcl		OK	OK		
9.2	On I-EGSE check that:	DCUFRAMECNT	FM: 0/700	0/100		
9.3	Verify that the following type of DCU science telemetry packets have been received at the CCS : Full Photometer: - (type,subtype): (21,1). - APID 0x504 (1284) PSW - (type,subtype): (21,2). - APID 0x504 (1284) PMW -(type,subtype): (21,2). - APID 0x504 (1284) PLW -(type,subtype): (21,2). - APID 0x504 (1284) Full Spectrometer: - (type,subtype): (21,1). - APID 0x506 (1286) SSW - (type,subtype): (21,2). - APID 0x506 (1286) SLW -(type,subtype): (21,2). - APID 0x506 (1286)		OK OK (100) NOK (0) NOK (0) NOK (0) NOK (0) NOK (0) NOK (0)			NCR-ASED-3210

6.2.10 Switch Off MCU Prime

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
10.1	On HPCCS Execute TCL script SPIRE-WU-INT-MCU-OFF-P.tcl		OK	OK.		Pass
10.2	On I-EGSE check that the MCU is switched off:	MCUBITSTAT	1/-/0	1/0		Pass

6.2.11 Switch Off DRCU PRIME

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	SWITCH OFF DRCU PRIME						
	DRCU-A Power Off						
	Initial Conditions: DRCU-A ON						
11.1	Verify the following PCDU telemetry to verify FCU-A On: LCL51 Status SpireHsfN_L51 LCL51 current SpireHsfN_L51	WM42C565 ON WM408565 =2-80.44A		ON 0.50A	AND: ZAD03999 MIM: LCL_HERSHEL		
11.2	On HPCCS start SPIRE-WU-INT-DRCU-OFF-P.tcl test script to configure DRCU for switch off	OK		OK			
11.3	On I-EGSE check that THSK parameter is not refreshing anymore	OK		OK			

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
11.4	On I-EGSE check that TM2N parameter is not incrementing anymore	OK		OK		Swk	
11.5	Power off FCU-A by issuing the following SwOff_SpireHSPDU_N_L51 telecommand (CDMS-TC(8,4,112,5)) and verify on-board execution: DC51B170	OK		OK		Swk	
11.6	Verify the following PCDU telemetry to verify FCU-A OFF: LCL51 (FCU-A) Status STS_LCL51 WM42C565 LCL51 (FCU-A) current ITLM_LCL51 WM408565	OFF 0.0 A		OFF 0.0 A		Swk	
11.7	HPPCS Operator to inform SPIRE Responsible that SPIRE DRCU/FCU Prime powered off	OK	+/- 0.28-06 A	OK		Swk	
SPIRE PRIME DRCU POWER OFF COMPLETE							

6.2.12 Switch Off SPIRE DPU Prime Unit

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
SWITCH OFF DPU PRIME							
DPU-A Power Off							
	Initial Conditions: DPU-A ON						
12.1	Verify the following PCDU telemetry to verify DPU-A On: LCL11 Status SpireHsdN_L11				AND: ZAD03999 MIM: LCL_HERSHEL		

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	LCL11 current SpireHsN_L11	WM32C565 ON		ON			
		WM308565 0.46 A	+/- 0.046 A	0.44A			
12.2	Disable and Switch off RTA SPIRE DPU-A (RTA=21) by issuing the following CMDS telecommand and verify on-board execution (x = don't care) :						
	ConfigureSDBFDIR	DC005161	OK	OK			
	RTA DH011161 =21				SPIRE-A		
	F0 DH018161 =0				RTA OFF		
	F1 DH019161 =x				RTA Alive		
	F2 DH020161 =x				RTA Well_TC		
	F3 DH021161 =x				RTA Well_TM		
	F4 DH022161 =0				RTA Invalid		
	F5 DH023161 =x				RTA Vital/Non-vital		
	F6 DH024161 =x				RT Nominal Unit		
	F7 DH025161 =x				RT TM Retry On/Off		
	F8 DH026161 =x				Bus A Active		
	F9 DH027161 =x				Bus A Healthy/Unhealthy		
	F10 DH028161 =x				Bus B Healthy/Unhealthy		
	F11 DH029161 =x				SDBFDIR Enable/Disable		
	M0 DH030161 =1				Mask F0		
	M1 DH031161 =0				Mask F1		
	M2 DH032161 =0				Mask F2		
	M3 DH033161 =0				Mask F3		

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	M4 DH034161 =1				Mask F4		
	M5 DH035161 =0				Mask F5		
	M6 DH036161 =0				Mask F6		
	M7 DH037161 =0				Mask F7		
	M8 DH038161 =0				Mask F8		
	M9 DH039161 =0				Mask F9		
	M10 DH040161 =0				Mask F10		
	M11 DH041161 =0				Mask F11		
	CNT DH042161 =1				Vital RT Loop (1)		
	M_C DH043161 =0				Mask for CNT		
12.3	After 10secs verify SPIRE-A RTA OFF: SPIREA_OnOff DED1G161 OFF SPIREA_ValidInval DED1K161 Invalid			OFF Invalid	AND: ZAD12999		
12.4	Power off DPU-A by issuing the following SwOff_SpireHSPDU_N_L11 telecommand (CDMS- TC(8,4,112,5)) and verify on-board execution: DC11B170 OK			OK			
12.5	Verify the following PCDU telemetry to verify DPU-A OFF: LCL11 (DPU-A) Status STS_LCL11 WM32C565 OFF LCL11 (DPU-A) current ITLM_LCL11 WM308565 0.0 A		+/- 0.046A	OFF 0.0A	AND: ZAD03999 MIM: LCL_HERSCHEL		
12.6	HPCSS Operator to inform SPIRE Responsible that SPIRE DPU Prime powered off			OK			
12.7	On HPCSS terminate SubscribeParams test script.			OK			
SPIRE DPU PRIME POWER OFF COMPLETE							

6.2.13 Switch On Redundant SPIRE Units

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
SWITCH ON DPU REDUNDANT							
DPU-B Power On							
Initial Conditions: DPU-A OFF							
13.1	Verify the following PCDU telemetry to verify DPU-B Off: LCL12 Status SpireHsdN_L12 LCL12 current SpireHsN_L12	WM82C565 OFF WM808565 =0.0A		OFF 0.0A	AND: ZAD03999 MIM: LCL_HERSHEL		
13.2	Disable CDMU FDIR while DPU switched ON and forced boot (RTA SPIRE used but not relevant) by issuing the following CMDS telecommand and verify on-board execution (x = don't care, either 0 or 1) :	DC005161	OK	OK			
	ConfigureSDBFDIR	RTA	DH011161	=22			
		F0	DH018161	=x		SPIRE-B	
		F1	DH019161	=x		RTA ON	
		F2	DH020161	=x		RTA Alive	
		F3	DH021161	=x		RTA Well_TC	
		F4	DH022161	=x		RTA Well_TM	
		F5	DH023161	=x		RTA Valid	
		F6	DH024161	=x		RTA Vital/Non-vital	
		F7	DH025161	=x		RT Nominal Unit	
						RT TM Retry On/Off	

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	F8 DH026161 =x				Bus A Active		
	F9 DH027161 =x				Bus A Healthy/Unhealthy		
	F10 DH028161 =x				Bus B Healthy/Unhealthy		
	F11 DH029161 =0				SDBFDIR Disable		
	M0 DH030161 =0				Mask F0		
	M1 DH031161 =0				Mask F1		
	M2 DH032161 =0				Mask F2		
	M3 DH033161 =0				Mask F3		
	M4 DH034161 =0				Mask F4		
	M5 DH035161 =0				Mask F5		
	M6 DH036161 =0				Mask F6		
	M7 DH037161 =0				Mask F7		
	M8 DH038161 =0				Mask F8		
	M9 DH039161 =0				Mask F9		
	M10 DH040161 =0				Mask F10		
	M11 DH041161 =1				Mask F11		
	CNT DH042161 =1				Vital RT Loop (1)		
	M_C DH043161 =0				Mask for CNT		
13.3	Verify FDIR disabled DEFJ4160	DISABLED		DISABLED	AND: ZAD07999		
13.4	Switch on RTA and enable Bus A on SPIRE DPU-A (RTA=22) by issuing the following CMDS telecommand and verify on-board execution (x = don't care, either 0 or 1): ConfigureSDBFDIR RTA DH011161 =22	DC005161	OK	OK	SPIRE-B		

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	F0 DH018161 =1				RTA ON		
	F1 DH019161 =1				RTA Alive		
	F2 DH020161 =1				RTA Well_TC		
	F3 DH021161 =1				RTA Well_TM		
	F4 DH022161 =1				RTA Valid		
	F5 DH023161 =x				RTA Vital/Non-vital		
	F6 DH024161 =0 ₁				RT Nominal Redundant Unit		
	F7 DH025161 =x				RT TM Retry On/Off		
	F8 DH026161 =0				Bus A Active		
	F9 DH027161 =x				Bus A Healthy/Unhealthy		
	F10 DH028161 =x				Bus B Healthy/Unhealthy		
	F11 DH029161 =x				SDBFDIR Enable/Disable		
	M0 DH030161 =1				Mask F0		
	M1 DH031161 =1				Mask F1		
	M2 DH032161 =1				Mask F2		
	M3 DH033161 =1				Mask F3		
	M4 DH034161 =1				Mask F4		
	M5 DH035161 =0				Mask F5		
	M6 DH036161 =1				Mask F6		
	M7 DH037161 =0				Mask F7		
	M8 DH038161 =1				Mask F8		
	M9 DH039161 =0				Mask F9		
	M10 DH040161 =0				Mask F10		

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	M11 DH041161 =0				Mask F11		
	CNT DH042161 =1				Vital RT Loop (1)		
	M_C DH043161 =0				Mask for CNT		
13.5	After 10secs verify SPIRE-B RTA ON: SPIREB_OnOff DED21161 ON SPIREB_Dealiv DED22161 Alive SPIREB_WellStiTC DED23161 Well SPIREB_WellStiTM DED24161 Well SPIREB_ValidInval DED25161 Valid			ON Alive Well Well Valid	AND: ZAD12999		
13.6	Power on DPU-B by issuing the following SwOn_SpireHSPDU_N_L12 telecommand (CDMS-TC(8,4,112,5)) and verify on-board execution: DC12D170	OK		OK			
13.7	Verify the following PCDU telemetry to verify DPU-B Off: LCL12 Status SpireHsdN_L12 WM82C565 LCL12 current SpireHsN_L12 WM808565	ON 0.46 A		ON 0.45			
13.9	On HPCCS start test script SubscribeParams.tcl to handle command parameter packets sent from the I-EGSE	OK		OK			
13.10	On HPCCS start SPIRE-WU-INT-DPU-START-R.tcl test script to configure DPU	OK		OK			
13.11	Enable CDMU FDIR (RTA SPIRE used but not relevant) by issuing the following CMDS telecommand and verify on-board execution (x = don't care, either 0 or 1): ConfigureSDBFDIR RTA DH011161 =22	DC005161	OK	OK			
					SPIRE-B		

Step- No.	Test-Step-Description			Nominal Value	Tolerance	Actual Value	Remarks	P	N
	F0	DH018161	=x				RTA ON		
	F1	DH019161	=x				RTA Alive		
	F2	DH020161	=x				RTA Well_TC		
	F3	DH021161	=x				RTA Well_TM		
	F4	DH022161	=x				RTA Valid		
	F5	DH023161	=x				RTA Vital/Non-vital		
	F6	DH024161	=x				RT Nominal Unit		
	F7	DH025161	=x				RT TM Retry On/Off		
	F8	DH026161	=x				Bus A Active		
	F9	DH027161	=x				Bus A Healthy/Unhealthy		
	F10	DH028161	=x				Bus B Healthy/Unhealthy		
	F11	DH029161	=1				SDBFDIR Enable		
	M0	DH030161	=0				Mask F0		
	M1	DH031161	=0				Mask F1		
	M2	DH032161	=0				Mask F2		
	M3	DH033161	=0				Mask F3		
	M4	DH034161	=0				Mask F4		
	M5	DH035161	=0				Mask F5		
	M6	DH036161	=0				Mask F6		
	M7	DH037161	=0				Mask F7		
	M8	DH038161	=0				Mask F8		
	M9	DH039161	=0				Mask F9		
	M10	DH040161	=0				Mask F10		
	M11	DH041161	=1				Mask F11		
	CNT	DH042161	=1				Vital RT Loop (1)		

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	M_C DH043161 =0				Mask for CNT		
13.12	Verify FDIR (re-)enabled DEFJ4160 ENABLED			ENABLED	AND: ZAD07999	<i>SW</i>	
13.13	HPCCS Operator to inform SPIRE Responsible that SPIRE DPU Redundant powered	OK		<i>OK</i>		<i>SW</i>	
13.14	Check that Nominal and Critical HK packets are arriving at the CCS: SPIRE Nominal HK: <ul style="list-style-type: none"> • (type ,subtype) : (3,25) • APID : 0x503 (1283) SPIRE Critical HK: <ul style="list-style-type: none"> • (type ,subtype) : (3,25) • APID: 0x501 (1281) 	OK		<i>OK</i>		<i>SW</i>	
13.15	On I-EGSE check that THSK parameter is refreshing every second	OK		<i>OK</i>		<i>SW</i>	
13.16	On I-EGSE check that TM2N parameter is incrementing by 1 every second	OK		<i>OK</i>		<i>SW</i>	
13.17	On I-EGSE check that TM1N parameter is incrementing by 1 every 2 second	OK		<i>OK</i>		<i>SW</i>	
13.18	On CCS check the consistency of the SPIRE on board time to the HCDMU time and the CCS.	OK		<i>OK</i>		<i>SW</i>	
13.19	On IEGSE check the consistency between SCOS time and THSK and QLA time.	OK		<i>OK</i>		<i>SW</i>	
SPIRE REDUNDANT DPU POWER ON COMPLETE							

6.2.14 Switch On DRCU REDUNDANT

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
SWITCH ON DRCU REDUNDANT							
DRCU-B Power On							
Initial Conditions: DRCU-B OFF							
14.1	Verify the following PCDU telemetry to verify FCU-B Off: LCL52 Status SpireHsfN_L52 LCL52 current SpireHsfN_L52	WM72C565 OFF WM708565 =0.0A		OFF 0.0A	AND: ZAD03999 MIM: LCL_HERSHEL		
14.2	Power on FCU-B by issuing the following SwOn_SpireHSPDU_N_L52 telecommand (CDMS-TC(8,4,112,5)) and verify on-board execution: DC52D170 OK	OK		OK			
14.3	Verify the following PCDU telemetry to verify FCU-B ON: LCL52 (FCU-B) Status STS_LCL52 LCL52 (FCU-B) current ITLM_LCL52	WM72C565 ON WM708565 2.80.44A		ON 0.47A	Rises to around 2.8A when MCU powered		
14.4	HPCCS Operator to inform SPIRE Responsible that SPIRE DRCU Redundant powered	OK		OK			
14.5	On HPCCS start SPIRE-WU-INT-DRCU-START-R-STEP1.tcl test script to configure DRCU	OK		OK			
14.6	On I-EGSE check that THSK parameter is not refreshing anymore	OK		OK			

RVS1
 after
 14.7
 end

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
14.7	On I-EGSE check that TM2N parameter is not incrementing anymore	OK		OK		Sub	
14.8	On HPCCS Execute TCL script SPIRE-WU-INT-DRCU-START-R-STEP2.tcl			OK		Sub	
14.9	On I-EGSE check that THSK parameter is refreshing every second	OK					
14.10	On I-EGSE check that TM2N parameter is incrementing by 1 every second	OK					
14.11	Check that the SCU/DCU voltages show nominal values: SCUP5V ~ 5.2 ± 0.5V SCUP9V ~ 9.0 ± 0.2V SCUM9V ~ -9.0 ± 0.2V BIASP5V ~ 5.1 ± 0.5V BIASP9V ~ 9.0 ± 0.2V BIASM9V ~ -9.0 ± 0.2V			5.25 9.09 -9.10 5.17 9.01 -9.07		Sub	
SPIRE REDUNDANT DRCU POWER ON COMPLETE							

6.2.15 Check correct functioning of the SCU REDUNDANT Low Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
15.1	On HPCCS Execute TCL script SPIRE-WU-INT-SCU-01-R.tcl		OK	OK		Sub
15.2	On I-EGSE verify:	SCUTEMPSTAT SUBKSTAT	0/0xFFFF 0/1	0 / 0xFFFF 0 / 1		Sub

DS: 65535 ID: ZAD129 Title: CDMS HK-0x1000 EssLow 2 of 12

Sample Time: 2007.101.19.40.30.142

Workstation: hpws24

NAME	DESCRIPTION	VALUE	UNIT	NAME	DESCRIPTION	VALUE	UNIT
DEF75160	ACCBValid Inval	Invalid		DED30161	SdbRtaCfgPACS_B	14	
DEDZF161	SdbRtaCfgHIFI_A	14		DED31161	PACSB_OnOff	OFF	
DEDZG161	HIFIA_OnOff	OFF		DED32161	PACSB_DeadAliv	Alive	
DEDZH161	HIFIA_DeadAlive	Alive		DED33161	PACSB_WellSiTC	Well	
DEDZZ161	HIFIA_WellSiTC	Well		DED34161	PACSB_WellSiTM	Well	
DEDZJ161	HIFIA_WellSiTM	Well		DED35161	PACSB_ValidInv	Invalid	
DEDZK161	HIFIA_ValidInv	Invalid		DEFAF160	BSW_SDBRTAPCDUA	31	
DED10161	SdbRtaCfgHIFI_B	14		DEFAG160	PCDUA_On_Off	ON	
DED11161	HIFIB_OnOff	OFF		DEFAH160	PCDUADeal Alive	Alive	
DED12161	HIFIB_DeadAlive	Alive		DEFAZ160	PCDUAWellSickTC	Well	
DED13161	HIFIB_WellSiTC	Well		DEFAJ160	PCDUAWellSickTM	Well	
DED14161	HIFIB_WellSiTM	Well		DEFAK160	PCDUA_Val_Inval	Valid	
DED15161	HIFIB_ValidInv	Invalid		DEFB0160	BSW_SDBRTAPCDUB	31	
DED1F161	SdbRtaCfgSpireA	14		DEFB1160	PCDUB_On_Off	ON	
DED1G161	SPIREA_OnOff	OFF		DEFB2160	PCDUBDead Alive	Alive	
DED1H161	SPIREA_DeadAliv	Alive		DEFB3160	PCDUBWellSickTC	Well	
DED1Z161	SPIREA_WellSiTC	Well		DEFB4160	PCDUBWellSickTM	Well	
DED1J161	SPIREA_WellSiTM	Well		DEFB5160	PCDUB_Val_Inval	Valid	
DED1K161	SPIREA_ValidInv	Invalid		DED3F161	SdbRtaCfgCCU_A	14	
DED20161	SdbRtaCfgSpireB	29		DED3G161	CCUA_OnOff	OFF	
DED21161	SPIREB_OnOff	ON		DED3H161	CCUA_DeadAlive	Alive	
DED22161	SPIREB_DeadAliv	Alive		DED3Z161	CCUA_WellSickTC	Well	
DED23161	SPIREB_WellSiTC	Well		DED3J161	CCUA_WellSickTM	Well	
DED24161	SPIREB_WellSiTM	Sick		DED3K161	CCUA_ValidInval	Invalid	
DED25161	SPIREB_ValidInv	Valid		DED40161	SdbRtaCfgCCU_B	14	
DED2F161	SdbRtaCfgPACS_A	14		DED41161	CCUB_OnOff	OFF	
DED2G161	PACSA_OnOff	OFF		DED42161	CCUB_DeadAlive	Alive	
DED2H161	PACSA_DeadAliv	Alive		DED43161	CCUB_WellSickTC	Well	
DED2Z161	PACSA_WellSiTC	Well		DED44161	CCUB_WellSickTM	Well	
DED2J161	PACSA_WellSiTM	Well		DED45161	CCUB_ValidInval	Invalid	
DED2K161	PACSA_ValidInv	Invalid		DEFCE160	BSW_SDBRTAXPND1	14	
				DEFCE160	XPND1On_Off	OFF	

Step 14.2 (first attempt)
- 14.8. Sick TM




Apr 12, 07 19:42

CHIS_PRNT_2007.102.19.42.44.464

Command history display printout from time: 2007.101.19.33.26.822 to time: 2007.101.19.41.05.236
Current printout time: 2007.102.19.42.44.465 Display view mode: BRIEF Sort order: RELEASE Filter status: INACTIVE
Number of commands printed: 50

Table with columns: Name, Description, Sequence, Release Time, Execution Time, S D C G B IL ST Source, Update Time, R GTO A S 012345 C. Contains command history entries for SEND_DRCU_COMMAND, SET_OBS_MODE, SET_BBID, DEFINE_NEW_HK_REPORT, Observation_will_start, Req_Obs_TC_Params_Chunks, Report_Test_Start, SwOn_SpireHSFCU_R_L52, CLEAR_HK_REPORT, UPDATE_TABLE, and SET_TABLE.

Steps 14.2-14.8 (first attempt)



6.2.16 Check correct functioning of the SCU REDUNDANT High Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
16.1	On HPCCS Execute TCL script SPIRE-WU-INT-SCU-02-R.tcl		OK	OK		Pass
16.2	On I-EGSE verify:	SCUFRAMECNT TM5N	0/31 0x3FFF/1	0/31 0x3FFF/1		Pass
16.3	Verify that two telemetry packets with : <ul style="list-style-type: none"> (type,subtype): (21,1). APID : 0x509 (1289) have been received at CCS		OK	OK		Pass

6.2.17 Check correct functioning of the MCU REDUNDANT Low Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
17.1	On HPCCS Execute TCL script SPIRE-WU-INT-MCU-01-R.tcl		OK	OK		Pass
17.2	On I-EGSE check that the MCU is booted up successfully	MCUBITSTAT MCUP5V MCUP14V MCUM14V MCUP15V	0/-1 ~ 5.0 ± 0.2V ~ 14.0 ± 0.5V ~ -14.0 ± 0.5V ~ 15.0 ± 0.5V	0/1 5.00 14.13 -14.49 15.80		Pass

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
		MCUM15V	~-15.0 ± 0.5V	-15.61		NOIC

6.2.18 Check correct functioning of the MCU REDUNDANT High Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
18.1	On HPCCS Execute TCL script SPIRE-WU-INT-MCU-02-R.tcl		OK	OK		Sub
18.2	On I-EGSE Record the values of MCUFRAMECNT at the start and end of the test	MCUFRAMECNT	FM: 0/297	0/297		Sub
18.3	Verify that the following type of MCU telemetry packets have been received at the CCS : ENG: - (type,subtype): (21,3). - APID 0x509 (1289) BSM - (type,subtype): (21,1). - APID 0x509 (1289) SMEC -(type,subtype): (21,1). - APID 0x509 (1289)		OK	OK OK OK		Sub

6.2.19 Check correct functioning of the DCU REDUNDANT Low Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
19.1	On HPCCS Execute TCL script SPIRE-WU-INT-DCU-01-R.tcl		OK	OK		Success
19.2	On I-EGSE check that:	PSWBIAS PMWBIAS PLWBIAS	0/0xff/0 0/0xff/0 0/0xff/0	0/ff/0 0/ff/0 0/ff/0		Fail

6.2.20 Check correct functioning of the DCU REDUNDANT High Speed Link

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
20.1	On HPCCS Execute TCL script SPIRE-WU-INT-DCU-02-R.tcl		OK	OK		
20.2	On I-EGSE check that:	DCUFRAMECNT	FM: 0/700	0/100		
20.3	Verify that the following type of DCU science telemetry packets have been received at the CCS : Full Photometer: - (type,subtype): (21,1). - APID 0x505 PSW - (type,subtype): (21,2). - APID 0x505 PMW -(type,subtype): (21,2). - APID 0x505		OK OK	OK (100) NOK (0) NOK (0)		NOK-ASED-3210

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
	PLW -(type,subtype): (21,2). - APID 0x505 (1285) Full Spectrometer: - (type,subtype): (21,1). - APID 0x507 (1287) SSW - (type,subtype): (21,2). - APID 0x507 (1287) SLW -(type,subtype): (21,2). - APID 0x507 (1287)			NOK(0) NOK(0) NOK(0) NOK(0)		

6.2.21 Switch Off MCU REDUNDANT

Step	Description	Parameter	Expected Values Before/After	Actual Values Before/After	Remark	Pass/Fail
21.1	On HPCCS Execute TCL script SPIRE-WU-INT-MCU-OFF-R.tcl		OK	OK		Pass
21.2	On I-EGSE check that the MCU is switched off:	MCUBITSTAT	1/-/0	1/0		Fail

6.2.22 Switch Off DRCU REDUNDANT

Step-No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
SWITCH OFF DRCU REDUNDANT							
DRCU-B Power Off							
Initial Conditions: DRCU-B ON							
22.1	Verify the following PCDU telemetry to verify FCU-B On: LCL52 Status SpireHsfN_L52 LCL52 current SpireHsfN_L52	WM72C565 ON		ON	AND: ZAD03999 MIM: LCL_HERSHEL		
		WM708565 =2.80.44A	+/-0.28A06A	0.50			
22.2	On HPCCS start SPIRE-WU-INT-DRCU-OFF-R.tcl test script to configure DRCU for switch off	OK		OK			
22.3	On I-EGSE check that THSK parameter is not refreshing anymore	OK		OK			
22.4	On I-EGSE check that TM2N parameter is not incrementing anymore	OK		OK			
22.5	Power off FCU-B by issuing the following SwOff_SpireHSPDU_N_L52 telecommand (CDMS-TC(8,4,112,5)) and verify on-board execution:	DC51D170 OK		OK			
22.6	Verify the following PCDU telemetry to verify FCU-B OFF: LCL52 (FCU-B) Status STS_LCL52 LCL52 (FCU-B) current ITLM_LCL52	WM72C565 OFF		OFF			
		WM708565 0.0 A	+/- 0.28-06 A	0.0 A			
22.7	HPCCS Operator to inform SPIRE Responsible that SPIRE DRCU/FCU Redundant powered off	OK		OK			

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	SPIRE REDUNDANT DRCU POWER OFF COMPLETE						

6.2.23 Switch Off Redundant SPIRE Units

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	SWITCH OFF DPU REDUNDANT						
	DPU-B Power Off						
	Initial Conditions: DPU-B ON						
23.1	Verify the following PCDU telemetry to verify DPU-B On: LCL12 Status SpireHsdN_L12 LCL12 current SpireHsN_L12	WM82C565 ON WM808565 0.46 A		0.2 0.44A	AND: ZAD03999 MIM: LCL_HERSCHEL		
23.2	Disable and Switch off RTA SPIRE DPU-B (RTA=22) by issuing the following CMDS telecommand and verify on-board execution (x = don't care) :						
	ConfigureSDBFDIR	DC005161	OK	OK			
	RTA DH011161 =22				SPIRE-B		
	F0 DH018161 =0				RTA OFF		
	F1 DH019161 =x				RTA Alive		
	F2 DH020161 =x				RTA Well_TC		
	F3 DH021161 =x				RTA Well_TM		
	F4 DH022161 =0				RTA Invalid		

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
	F5 DH023161 =x				RTA Vital/Non-vital		
	F6 DH024161 =x				RT Nominal Unit		
	F7 DH025161 =x				RT TM Retry On/Off		
	F8 DH026161 =x				Bus A Active		
	F9 DH027161 =x				Bus A Healthy/Unhealthy		
	F10 DH028161 =x				Bus B Healthy/Unhealthy		
	F11 DH029161 =x				SDBFDIR Enable/Disable		
	M0 DH030161 =1				Mask F0		
	M1 DH031161 =0				Mask F1		
	M2 DH032161 =0				Mask F2		
	M3 DH033161 =0				Mask F3		
	M4 DH034161 =1				Mask F4		
	M5 DH035161 =0				Mask F5		
	M6 DH036161 =0				Mask F6		
	M7 DH037161 =0				Mask F7		
	M8 DH038161 =0				Mask F8		
	M9 DH039161 =0				Mask F9		
	M10 DH040161 =0				Mask F10		
	M11 DH041161 =0				Mask F11		
	CNT DH042161 =1				Vital RT Loop (1)		
	M_C DH043161 =0				Mask for CNT		
23.3	After 10secs verify SPIRE-B RTA OFF: SPIREB_OnOff DED21161 OFF SPIREB_ValidInval DED25161 Invalid				AND: ZAD12999 OFF Invalid		

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
23.4	Power off DPU-B by issuing the following SwOff_SpireHSPDU_N_L12 telecommand (CDMS- TC(8,4,112,5)) and verify on-board execution: DC12B170	OK		OK			
23.5	Verify the following PCDU telemetry to verify DPU-B OFF: LCL12 (DPU-B) Status STS_LCL12 WM82C565 LCL12 (DPU-B) current ITLM_LCL12 WM808565	OFF 0.0 A	 +/- 0.046A	OFF 0-0A	AND: ZAD03999 MIM: LCL_HERSCHEL		
23.6	HPCSS Operator to inform SPIRE Responsible that SPIRE DPU Redundant powered off	OK		OK			
23.7	On HPCSS terminate SubscribeParams test script.	OK		OK			
SPIRE DPU REDUNDANT POWER OFF COMPLETE							

6.2.24 Satellite & EGSE Switch Off

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value		P	N
	Satellite & EGSE Switch Off						
	Initial Conditions: Nominal & Redundant SPIRE warm units OFF						
24.1	From HPCCS Test Conductor console issue command to disconnect from SPIRE I-EGSE disconnect HIEGSE	OK		OK			
24.2	Confirm from HPCSS and SPIRE I-EGSE that the disconnection was successful	OK		OK			
24.3	Switch OFF I-EGSE i.a.w. AD 5						
24.4	Switch OFF Satellite/SVM, HPCCS and SCOE's i.a.w. procedure AD 2 Sections 7.7 to 7.11	OK		OK			
24.5	Confirm both Satellite and EGSE powered down	OK		OK			
	End Conditions: Satellite and EGSE OFF			OK			
	END OF TEST						

7 Summary Sheets

7.1 Procedure Variation Summary


		Test Change		Curr. No.: 1	
				Date 17/04/07	
				Page 1 of 1	
Test designation SPIRE FM UFT		Test Procedure TP-0148		Issue 1	
				Rev. -	
Test step changed 14.2 - 14.4		Reason for Change Test Step Order Incorrect			
<p>RAL (SPIRE) Identified during test that test steps 14.2 - 14.4 were to be executed in the wrong place during DRCH power on.</p> <p>It was agreed to move these steps to be performed after 14.7.</p> <p>NB. Post execution of PVS. Move of these test steps resulted in loss of TM link with DPU, COMS reporting Sick TM (NCR-3211 refers)</p> <p>It was therefore agreed to revert to original test step order which was successful.</p>					
Prepared by: 		Resp. Test Leader		Project Engineer	
PA/QA		Prime		Customer	

Table 7.1-1: Procedure Variation Sheet

7.2 Non Conformance Report (NCR) Summary

NCR - No.	NCR - Title	Date	Open Closed	PA sig.
	See test report			

Table 7.2-1: Non-Conformance Record Sheet

7.3 Sign-off Sheet

	Date	Signature
Test Manager		
Operator		
PA Responsible		
ESA Representative		

END OF DOCUMENT

	Name	Dep./Comp.		Name	Dep./Comp.
X	Alberti von Mathias Dr.	ASG22		Schweickert Gunn	ASG22
	Baldock Richard	FAE12	X	Sonn Nico	ASG51
	Barlage Bernhard	AED13		Steininger Eric	AED32
	Bayer Thomas	ASA42	X	Stritter Rene	AED11
	Brune Holger	ASA45		Suess Rudi	OTN/ASA44
	Edelhoff Dirk	AED2		Wagner Klaus	ASG22
	Fehringer Alexander	ASG13	X	Wietbrock Walter	AET12
X	Fricke Wolfgang Dr.	AED 65		Wöhler Hans	ASG22
	Geiger Hermann	ASA42		Wössner Ulrich	ASE252
	Grasl Andreas	OTN/ASA44	X	Theunissen Martijn/Dutch Space	ASA43
	Grasshoff Brigitte	AET12	X	Martin Olivier	ASA43
X	Hamer Simon	Terma			
X	Hendry David	Terma			
	Hengstler Reinhold	ASA42			
	Hinger Jürgen	ASG22			
X	Hohn Rüdiger	AED65			
	Hölzle Edgar Dr.	AED32			
	Huber Johann	ASA42			
	Hund Walter	ASE252			
	Idler Siegmund	AED312			
	Ivány von András	FAE12			
	Jahn Gerd Dr.	ASG22			
	Kalde Clemens	ASM2			
	Kameter Rudolf	OTN/ASA42			
	Kettner Bernhard	AET42			
	Knoblauch August	AET32	X	Alcatel Alenia Space Cannes	AAS-F
X	Koelle Markus	ASA43		Alcatel Alenia Space Torino	AAS-I
X	Koppe Axel	AED312	X	ESA/ESTEC	ESA
X	Kroeker Jürgen	AED65			
X	La Gioia Valentina	Terma		Instruments:	
	Lang Jürgen	ASE252		MPE (PACS)	MPE
	Langenstein Rolf	AED15	X	RAL (SPIRE)	RAL
	Langfermann Michael	ASA41		SRON (HIFI)	SRON
X	Maukisch Jan	ASA43			
X	Much Christoph	ASA43			
	Müller Jörg	ASA42		Subcontractors:	
X	Müller Martin	ASA43		Alcatel Alenia Space Antwerp	ABSP
	Peltz Heinz-Willi	ASG13		Austrian Aerospace	AAE
	Pietroboni Karin	AED65		Austrian Aerospace	AAEM
	Platzer Wilhelm	AED2		BOC Edwards	BOCE
	Reichle Konrad	ASA42		Dutch Space Solar Arrays	DSSA
	Runge Axel	OTN/ASA44		EADS Astrium Sub-Subsyst. & Equipment	ASSE
	Schink Dietmar	AED32		EADS CASA Espacio	CASA
	Schlosser Christian	OTN/ASA44		EADS CASA Espacio	ECAS
	Schmidt Rudolf	FAE12		European Test Services	ETS
	Schmidt Thomas	ASA42		Patria New Technologies Oy	PANT
	Schuler Günter	ASA42		SENER Ingenieria SA	SEN

END OF DOCUMENT

	Name	Dep./Comp.		Name	Dep./Comp.
X	Alberti von Mathias Dr.	ASG22		Schweickert Gunn	ASG22
	Baldock Richard	FAE12	X	Sonn Nico	ASG51
	Barlage Bernhard	AED13		Steininger Eric	AED32
	Bayer Thomas	ASA42	X	Stritter Rene	AED11
	Brune Holger	ASA45		Suess Rudi	OTN/ASA44
	Edelhoff Dirk	AED2		Wagner Klaus	ASG22
	Fehringer Alexander	ASG13	X	Wietbrock Walter	AET12
X	Fricke Wolfgang Dr.	AED 65		Wöhler Hans	ASG22
	Geiger Hermann	ASA42		Wössner Ulrich	ASE252
	Grasl Andreas	OTN/ASA44	X	Martin Olivier	ASA43
	Grasshoff Brigitte	AET12	X	Theunissen Martijn	DutchSpace
X	Hamer Simon	Terma			
X	Hendry David	Terma			
	Hengstler Reinhold	ASA42			
	Hinger Jürgen	ASG22			
X	Hohn Rüdiger	AED65			
	Hölzle Edgar Dr.	AED32			
	Huber Johann	ASA42			
	Hund Walter	ASE252			
	Idler Siegmund	AED312			
	Ivány von András	FAE12			
	Jahn Gerd Dr.	ASG22			
	Kalde Clemens	ASM2			
	Kameter Rudolf	OTN/ASA42			
	Kettner Bernhard	AET42			
	Knoblauch August	AET32	X	Alcatel Alenia Space Cannes	AAS-F
X	Koelle Markus	ASA43		Alcatel Alenia Space Torino	AAS-I
X	Koppe Axel	AED312	X	ESA/ESTEC	ESA
X	Kroeker Jürgen	AED65			
X	La Gioia Valentina	Terma		Instruments:	
	Lang Jürgen	ASE252		MPE (PACS)	MPE
	Langenstein Rolf	AED15	X	RAL (SPIRE)	RAL
	Langfermann Michael	ASA41		SRON (HIFI)	SRON
X	Maukisch Jan	ASA43			
X	Much Christoph	ASA43			
	Müller Jörg	ASA42		Subcontractors:	
X	Müller Martin	ASA43		Alcatel Alenia Space Antwerp	ABSP
	Peltz Heinz-Willi	ASG13		Austrian Aerospace	AAE
	Pietroboni Karin	AED65		Austrian Aerospace	AAEM
	Platzer Wilhelm	AED2		BOC Edwards	BOCE
	Reichle Konrad	ASA42		Dutch Space Solar Arrays	DSSA
	Runge Axel	OTN/ASA44		EADS Astrium Sub-Subsyst. & Equipment	ASSE
	Schink Dietmar	AED32		EADS CASA Espacio	CASA
	Schlosser Christian	OTN/ASA44		EADS CASA Espacio	ECAS
	Schmidt Rudolf	FAE12		European Test Services	ETS
	Schmidt Thomas	ASA42		Patria New Technologies Oy	PANT
	Schuler Günter	ASA42		SENER Ingenieria SA	SEN