



Procedure

Herschel

Title: **Herschel Instrument Power ON-OFF and Mode Switching Procedure for Functional Testing**

CI-No: *100000*

| | | | |
|------------------------|----------------------------|-------|-------------------|
| Prepared by: | <u>S. Hamer TERMA A/S</u> | Date: | <u>07.01.2008</u> |
| Checked by: | <i>for</i> <u>S. Idler</u> | | <u>10.01.08</u> |
| Product Assurance: | <u>R. Stritter</u> | | <u>11/1/08</u> |
| Configuration Control: | <u>W. Wietbrock</u> | | <u>18/01/08</u> |
| Project Management: | <u>Dr. Fricke</u> | | <u>11/01/08</u> |

Distribution: See Distribution List (last page)

Copying of this document, and giving it to others and the use or communication of the contents thereof, are forbidden without express authority. Offenders are liable to the payment of damages. All rights are reserved in the event of the grant of a patent or the registration of a utility model or design.

| Issue | Date | Sheet | Description of Change | Release |
|-------|------------|-------|-----------------------|---------|
| 1.0 | 07.01.2008 | | Initial version | |

Table of Content

| | |
|--|-----------|
| Table of Content | 3 |
| 1 Scope | 6 |
| 1.1 Objective | 6 |
| 1.2 Operational Flow | 6 |
| 2 Documents/Drawings | 8 |
| 2.1 Applicable Documents | 8 |
| 2.2 Reference Documents | 8 |
| 2.3 Other Documents | 9 |
| 2.4 Acronyms | 9 |
| 3 Requirements to be verified | 10 |
| 4 Configuration | 11 |
| 4.1 Herschel S/C Configuration | 11 |
| 4.1.1 Hardware Configuration | 11 |
| 4.1.2 Software Configuration | 11 |
| 4.1.3 Test Configuration | 11 |
| 4.1.3.1 SVM | 11 |
| 4.1.3.2 HIFI | 11 |
| 4.1.3.3 PACS | 11 |
| 4.1.3.4 SPIRE | 11 |
| 4.1.4 Simulated Equipments | 11 |
| 5 Conditions | 12 |
| 5.1 Personnel | 12 |
| 5.2 Environmental | 12 |
| 5.3 General Precautions and Safety | 12 |
| 5.3.1 General Safety Requirements, Precautions | 12 |
| 5.3.2 Special condition and hazards | 12 |
| 5.3.2.1 HIFI | 12 |
| 5.3.2.2 PACS | 13 |

| | | |
|----------|--|-----------|
| 5.3.2.3 | SPIRE | 13 |
| 5.3.3 | ESD constraints | 13 |
| 5.3.4 | Special QA Requirements | 14 |
| 5.4 | GSE | 15 |
| 5.4.1 | MGSE | 15 |
| 5.4.2 | CVSE | 15 |
| 5.4.3 | EGSE | 15 |
| 5.4.3.1 | EGSE Hardware Configuration | 15 |
| 5.4.3.2 | EGSE User Software | 15 |
| 5.4.3.3 | Grounding Configuration | 15 |
| 5.4.3.4 | Test Equipment | 15 |
| 5.4.3.5 | Data Acquisition System | 15 |
| 5.4.4 | OGSE | 15 |
| 5.4.5 | Special Equipment | 15 |
| 6 | Verification Requirements and Test Criteria | 16 |
| 7 | Step-by-Step Procedures | 17 |
| 7.1 | PACS Instrument Procedures | 17 |
| 7.1.1 | PACS I-EGSE Configuration/Connection | 17 |
| 7.1.2 | PACS Prime OFF to Standby (SAFE) | 19 |
| 7.1.3 | PACS Prime Standby (SAFE) to OFF | 23 |
| 7.1.4 | PACS Redundant OFF to Standby (SAFE) | 26 |
| 7.1.5 | PACS Redundant Standby (SAFE) to OFF | 30 |
| 7.1.6 | PACS Standby (SAFE) to Nominal Spectroscopy (to Standby) | 33 |
| 7.1.7 | PACS Standby (SAFE) to Burst Mode (to Standby) | 34 |
| 7.1.8 | PACS I-EGSE Disconnection | 35 |
| 7.2 | SPIRE Instrument Procedures | 36 |
| 7.2.1 | SPIRE I-EGSE Configuration/Connection | 36 |
| 7.2.2 | SPIRE Prime OFF to Standby (REDY) | 38 |
| 7.2.3 | SPIRE Prime Standby (REDY) to OFF | 42 |
| 7.2.4 | SPIRE Redundant OFF to Standby (REDY) | 45 |
| 7.2.5 | SPIRE Redundant Standby (REDY) to OFF | 49 |
| 7.2.6 | SPIRE I-EGSE Disconnection | 52 |
| 7.3 | HIFI Instrument Procedures | 53 |
| 7.3.1 | HIFI I-EGSE Configuration/Connection | 53 |
| 7.3.2 | HIFI Prime OFF to Standby | 56 |
| 7.3.3 | HIFI Prime Standby to OFF | 61 |
| 7.3.4 | HIFI Redundant OFF to Standby | 64 |
| 7.3.5 | HIFI Redundant Standby to OFF | 68 |
| 7.3.6 | HIFI I-EGSE Disconnection | 71 |

| | | |
|----------|--------------------------------------|-----------|
| 8 | ANNEX | 72 |
| 8.1 | Script hierarchy | 72 |
| 8.1.1 | General | 72 |
| 8.1.2 | PACS | 72 |
| 8.1.3 | SPIRE | 72 |
| 8.1.4 | HIFI | 73 |
| 8.2 | Procedure Variation Summary | 75 |
| 8.3 | Non Conformance Report (NCR) Summary | 76 |
| 8.4 | Sign-off Sheet | 77 |

1 Scope

1.1 Objective

This document details the Instrument (PACS, SPIRE & HIFI) procedures provided to support primarily SVM oriented IST activities. The procedures can be used where appropriate to support other non-specific instrument tests (e.g. EMC, shipping health check). The procedures cover the following basic activities:

- Instrument (Prime & Redundant) Switch ON/OFF to/from Standby* mode
- Configuration of, and connection to, the Instrument EGSEs (I-EGSEs)
- Transition from “Standby” to dummy** Science producing mode

* “Standby” is an artificial mode which cannot be characterised by one particular parameter for any instrument. Each instrument also uses an alternative name to indicate “Standby” mode; for PACS this is SAFE and for SPIRE it is REDY, HIFI does not use a specific name.

** Dummy Science is sufficient for the needs of non-specific instrument IST activities and is representative in terms of APID allocation and bandwidth but not data content.

This document will, where necessary, evolve during the system level AIT activities in order to reflect the configuration of the instruments (completion of integration activities) and the Herschel satellite (the latter in order to handle operation of the instruments in warm, Hel and Hell conditions)

1.2 Operational Flow

Chapter 7 provides the detailed step-by-step procedures for each instrument, which are summarised below:

PACS

- EGSE Configuration & Connection
- PACS Prime OFF to Standby (SAFE)
- PACS Prime Standby (SAFE) to OFF
- PACS Redundant OFF to Standby (SAFE)
- PACS Redundant Standby (SAFE) to OFF
- PACS Standby (SAFE) to Nominal Spectroscopy (to Standby)
- PACS Standby (SAFE) to Burst Mode (to Standby)

- EGSE Disconnection

SPIRE

- EGSE Configuration & Connection
- SPIRE Prime OFF to Standby (REDY)
- SPIRE Prime Standby (REDY) to OFF
- SPIRE Redundant OFF to Standby (REDY)
- SPIRE Redundant Standby (REDY) to OFF
- EGSE Disconnection

HIFI

- EGSE Configuration & Connection
- HIFI Prime OFF to Standby
- HIFI Prime Standby to OFF
- HIFI Redundant OFF to Standby
- HIFI Redundant Standby to OFF
- EGSE Disconnection

2 Documents/Drawings

This document incorporates, by dated or undated references, provisions from other publications. These normative references are cited at appropriate places in the text and publications are listed hereafter. For dated references, subsequent amendments to or revisions of any of these apply to this document only when incorporated into it by amendment or revision. For undated references, the latest edition of the publication referred to apply.

2.1 Applicable Documents

| | | |
|------|---|-------------------|
| AD-1 | Herschel SAT Emergency Switch Off Procedure | H-P-2-ASED-PR-071 |
|------|---|-------------------|

2.2 Reference Documents

| | | |
|-------|---|-------------------------|
| RD-1 | Herschel PCDU & CDMS nominal switch on / off procedure | HP-2-ASED-PR-0070 |
| RD-2 | HIFI Switch On Procedure, Issue 1.5.3 | SRON-G/HIFI/PR/200707 |
| RD-3 | PACS Switch On/Off, ref. email Helmut Feuchtgruber | 17. April 2007 11:58 |
| RD-4 | SPIRE Integration System Test Debugging Procedures, Issue 1.3 | SPIRE-RAL-PRC-002880 |
| RD-5 | PACS I-EGSE User Manual, Issue 1, 19-Jul-2007 | PICC-ME-MN-010 |
| RD-6 | HIFI IEGSE setup procedure | SRON-U/HIFI/PR/2007-005 |
| RD-7 | SPIRE I-EGSE Set-Up, Issue 2.2 | SPIRE-RAL-DOC-002841 |
| RD-8 | FIRST/PLANCK Instrument Interface Document part A | PT-IID-A-04624 |
| RD-9 | FIRST/PLANCK Instrument Interface Document part B (HIFI) | PT-IIDB/HIFI-02125 |
| RD-10 | FIRST/PLANCK Instrument Interface Document part B (PACS) | PT-IIDB/PACS-02126 |
| RD-11 | FIRST/PLANCK Instrument Interface Document part B (SPIRE) | PT-IIDB/SPIRE-02124 |
| RD-12 | LO SFT Procedure using LO Dummy, Issue 1.01 | MPIfR/HIFI/PR/2006-565 |

2.3 Other Documents

N/A

2.4 Acronyms

See calling procedure.

3 Requirements to be verified

N/A

4 Configuration

4.1 Herschel S/C Configuration

4.1.1 *Hardware Configuration*

See relevant TRR MoM

4.1.2 *Software Configuration*

See relevant TRR MoM

4.1.3 *Test Configuration*

4.1.3.1 SVM

See relevant TRR MoM

4.1.3.2 HIFI

All warm units & FPU integrated, LOU dummy fitted, waveguides suitably terminated. Warm conditions only.

4.1.3.3 PACS

All warm units and FPU is integrated and connected to the warm units. Warm or Cold Hel/Hel conditions.

4.1.3.4 SPIRE

All warm units integrated. Warm conditions only.

4.1.4 *Simulated Equipments*

N/A

5 Conditions

5.1 Personnel

See relevant TRR MoM

5.2 Environmental

See relevant TRR MoM

5.3 General Precautions and Safety

5.3.1 General Safety Requirements, Precautions

- For HIFI, Handling precautions according to RD-8 and RD-9 are applicable.
- For PACS, Handling precautions according to RD-8 and RD-10 are applicable.
- For SPIRE, Handling precautions according to RD-8 and RD-11 are applicable.

5.3.2 Special condition and hazards

The following Operational restrictions shall be carefully taken into account:

- In case of any failure, the activities shall be stopped until troubleshooting plan is generated and approved.

5.3.2.1 HIFI

| Activity | Confirmed Completed | PA Sign Off | Date |
|--|---------------------|-------------|------|
| Waveguide outputs must be covered with kapton tape (to prevent from dust contamination) | | | |
| For ultimate personnel safety 1 could stay 1 m away from the waveguides once the LSU output power is on. | N/A | | |

5.3.2.2 PACS

None

5.3.2.3 SPIRE

None

5.3.3 ESD constraints

See the Lead Procedure for the test concerned and the following:

- For HIFI, ESD precautions according to RD-8 and RD-9 are applicable.
- For SPIRE according to nominal ESD protection
- For PACS according to nominal ESD protection

5.3.4 Special QA Requirements

N/A

5.4 GSE

5.4.1 MGSE

N/A

5.4.2 CVSE

N/A

5.4.3 EGSE

5.4.3.1 EGSE Hardware Configuration

See TRR MoM for test concerned.

5.4.3.2 EGSE User Software

See TRR MoM for test concerned.

5.4.3.3 Grounding Configuration

N/A

5.4.3.4 Test Equipment

N/A

5.4.3.5 Data Acquisition System

N/A

5.4.4 OGSE

N/A

5.4.5 Special Equipment

N/A

6 Verification Requirements and Test Criteria

No specific requirements are verified by this procedure, it is purely acts as a supporting procedure to the main lead test procedure where the overall test criteria and verification requirements are defined.

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7 Step-by-Step Procedures

7.1 PACS Instrument Procedures

7.1.1 PACS I-EGSE Configuration/Connection

The following procedure is used when it is required to use the PACS IEGSE to support the test being performed, either for monitoring of PACS specific TM on the IEGSE or for commanding the instrument above SAFE mode using a handshaking protocol between the HPCCS and the I-EGSE (i.e. Instrument specific testing such as SFTs). It is NOT normally required for switching PACS ON or OFF. This procedure is independent of PACS redundancy configuration.

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|--|-------------------------|--------------|----------------------|---|---|
| 1. | If not already on, Switch on & configure PACS I-EGSE i.a.w. RD-5 | | | | | |
| 2. | From HPCCS Test Conductor console issue command to connect to PACS I-EGSE connect HPACSEGSE | YES28940== CONNECTED | | AND: SYS_PARS | | |
| | <i>Perform the following two steps if command parameter exchange is required between the IEGSE and HPCCS for the test concerned.</i> | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|---------------------------|--|--|-----------------------|
| Enter Date Time: | | | Test Location: |
|---------------------------|--|--|-----------------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 3. | If not already running from the HPCCS test conductor console execute the test script: <p style="text-align: center;">ALL_SubscribeParams</p> | | | | | |
| 4. | Verify HPCCS-IEGSE connection by sending the following test command from manual command stack (repeater value 0) and verify received OK on IEGSE: <p style="text-align: center;">YC00X964</p> | OK | | | | |
| 5. | Return to calling Procedure | | | | | |

| | | | | | |
|---------------------------|--|--|-----------------|------------|------------|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|---------------------------|--|--|-----------------|------------|------------|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.1.2 PACS Prime OFF to Standby (SAFE)

The following will switch ON and configure PACS Prime instrument in SAFE mode in any satellite configuration (i.e. warm, or Cold He1/He11). HKTM packets will be generated on APIDs 1152 dec and 1154 decimal (these can be observed using TMPH with corresponding filter – note however a limited number of TMPHs should be running at any one time).

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script to power PACS Prime to SAFE: Z102999SCVT010_ASDGEN_PACSPWRON_P | | | | | |
| 2. | On HPCCS when prompted: "FM PACS Switch ON in Warm or Cold conditions, FPU connected - Select NO to abort TS if not correct" | YES | | | | |
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 4. | If YES is selected the test script will go on to automatically power on all PACS warm units, force boot the DPU ASW and configure the instrument to SAFE (Standby mode) as per PACS test script: PACS_Switch_On_CCS_Nominal.tcl | | | | | |
| 5. | On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT010_ASDGEN_PACSPWRON_P it will prompt: <i>"Set Bus Profile Back to Original Setting?"</i> | NO | | | | |
| 6. | Select YES if it is likely that other non-PACS instrument related activities are to be performed. <i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i> <i>"Bus Profile left unchanged, as original setting 0 (Launch)"</i> | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|--|---------------|--------------|--|---|---|
| 7. | If NO selected then at the prompt: "Bus Profile left unchanged" Select OK to continue | OK | | | | |
| 8. | Verify HK TM packets are being received on APIDs 1152 & 1154 | | | | | |
| 9. | Either using the ANDs indicated verify the correct status of the following PACS specific TM parameters or if the IEGSE is connected request IEGSE Operator to confirm that PACS is in SAFE mode: DP_SPS_LINK = "ON" DP_SPL_LINK = "ON" DP_DMC_LINK = "ON" DP_SPUS_CMD = "SS ENABLED" DP_SPUL_CMD = "SS ENABLED" DP_DMC_CMD = "SS ENABLED" DP_SPUS_HK = "NEW HK" DP_SPUL_HK = "NEW HK" DP_DMC_HK = "NEW HK" SPL_DMC_LINK = "LINK ON" SPS_DMC_LINK = "LINK ON" DM_BOL_REC_PAC = incrementing | OK | | AND: PA000380 PA003390 PA206400 PA019420 PA001380 | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| | - Counters for TM(1,2), TM(1,8) and NACKs shall be 0 DP_1_8_REJECTED = 0 DP_1_2_REJECTED = 0 DP_COM_DMC_NACK = 0 DP_COM_SPL_NACK = 0 DP_COM_SPS_NACK = 0 - HK parameter DP_UNIT indicates "NOMINAL DPU" | | | | | |
| 10. | PACS in SAFE mode. Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.1.3 PACS Prime Standby (SAFE) to OFF

The following procedure will switch PACS Prime from SAFE to OFF.

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script to power OFF PACS Prime from SAFE: Z102999SCVT011_ASDGEN_PACSPWROFF_P | | | | | |
| 2. | On HPCCS when prompted: "FM PACS Switch OFF in Warm or Cold conditions, FPU connected - Select NO to abort TS if not correct" | YES | | | | |
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |
| 4. | If YES is selected the test script will go on to automatically power off all PACS warm units as per PACS test script: PACS_Switch_Off_CCS_Nominal.tcl | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|---------|---|---|
| 5. | Note: During switch off of PACS (5,2) TM event packets are expected | | | | | |
| 6. | On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT011_ASDGEN_PACSPWROFF_P it will prompt: <i>"Set Bus Profile Back to Original Setting?"</i> | NO | | | | |
| 7. | Select YES if it is likely that other non-PACS instrument related activities are to be performed. <i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i> <i>"Bus Profile left unchanged, as original setting 0 (Launch)"</i> | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|



| | | | | |
|--------------------|--|--|----------------|--|
| Enter Date Time: | | | Test Location: | |
|--------------------|--|--|----------------|--|

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------------------|--|--------------------------|---------------------|----------------|----------|----------|
| 8. | If NO selected then at the prompt: "Bus Profile left unchanged" Select OK to continue | OK | | | | |
| 9. | PACS OFF. Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.1.4 PACS Redundant OFF to Standby (SAFE)

The following will switch ON and configure PACS Redundant instrument in SAFE mode in any satellite configuration (i.e. warm, or Cold: He1/He11). HKTM packets will be generated on APIDs 1153 dec and 1155 decimal (these can be observed using TMPH with corresponding filter – note however a limited number of TMPHs should be running at any one time).

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script to power PACS Redundant to SAFE: Z102999SCVT012_ASDGEN_PACSPWRON_R | | | | | |
| 2. | On HPCCS when prompted: "FM PACS Switch ON in Warm or Cold conditions, FPU connected - Select NO to abort TS if not correct" | YES | | | | |
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 4. | If YES is selected the test script will go on to automatically power on all PACS redundant warm units, force boot the DPU ASW and configure the instrument to SAFE (Standby mode) as per PACS test script: PACS_Switch_On_CCS_Redundant.tcl | | | | | |
| 5. | On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT012_ASDGEN_PACSPWRON_R it will prompt: <i>“Set Bus Profile Back to Original Setting?”</i> | NO | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|--|---|---|
| 6. | <p>Select YES if it is likely that other non-PACS instrument related activities are to be performed.</p> <p><i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i></p> <p>“Bus Profile left unchanged, as original setting 0 (Launch)”</p> | OK | | | | |
| 7. | <p>If NO selected then at the prompt:</p> <p>“Bus Profile left unchanged”</p> <p>Select OK to continue</p> | OK | | | | |
| 8. | Verify HK TM packets are being received on APIDs 1153 & 1155 | | | | | |
| 9. | <p>Either using the ANDs indicated verify the correct status of the following PACS specific TM parameters or if the IEGSE is connected request IEGSE Operator to confirm that PACS is in SAFE mode:</p> <p>DP_SPS_LINK = "ON"</p> | OK | | AND: PA000380 PA003390 PA206400 PA019420 PA001380 | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|---------|---|---|
| | DP_SPL_LINK = "ON" DP_DMC_LINK = "ON" DP_SPUS_CMD = "SS ENABLED" DP_SPUL_CMD = "SS ENABLED" DP_DMC_CMD = "SS ENABLED" DP_SPUS_HK = "NEW HK" DP_SPUL_HK = "NEW HK" DP_DMC_HK = "NEW HK" SPL_DMC_LINK = "LINK ON" SPS_DMC_LINK = "LINK ON" DM_BOL_REC_PAC = incrementing - Counters for TM(1,2), TM(1,8) and NACKs shall be 0 DP_1_8_REJECTED = 0 DP_1_2_REJECTED = 0 DP_COM_DMC_NACK = 0 DP_COM_SPL_NACK = 0 DP_COM_SPS_NACK = 0 - HK parameter DP_UNIT indicates "NOMINAL DPU" | | | | | |
| 10. | PACS in SAFE mode. Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.1.5 PACS Redundant Standby (SAFE) to OFF

The following procedure will switch PACS Redundant from SAFE to OFF.

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script to power OFF PACS Prime from SAFE: Z102999SCVT013_ASDGEN_PACSPWROFF_R | | | | | |
| 2. | On HPCCS when prompted: "FM PACS Switch OFF in Warm or Cold conditions, FPU connected - Select NO to abort TS if not correct" | YES | | | | |
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |
| 4. | If YES is selected the test script will go on to automatically power off all PACS Redundant warm units as per PACS test script: PACS_Switch_Off_CCS_Redundant.tcl | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 5. | Note: During switch off of PACS (5,2) TM event packets are expected | | | | | |
| 6. | On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT013_ASDGEN_PACSPWROFF_R it will prompt: <i>“Set Bus Profile Back to Original Setting?”</i> | NO | | | | |
| 7. | Select YES if it is likely that other non-PACS instrument related activities are to be performed. <i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i> <i>“Bus Profile left unchanged, as original setting 0 (Launch)”</i> | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|



| | | | | |
|--------------------|--|--|----------------|--|
| Enter Date Time: | | | Test Location: | |
|--------------------|--|--|----------------|--|

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|--|------------------|--------------|---------|---|---|
| 8. | If NO selected then at the prompt: "Bus Profile left unchanged" Select OK to continue | OK | | | | |
| 9. | PACS OFF. Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|---------------------------|--|--|-----------------------|
| Enter Date Time: | | | Test Location: |
|---------------------------|--|--|-----------------------|

7.1.6 PACS Standby (SAFE) to Nominal Spectroscopy (to Standby)

Running the following procedure will configure PACS from SAFE to Simulated Nominal Spectroscopy for a period of 60mins. **TBC which APIDs are generated and duration!!** The test script will autonomously return PACS to SAFE after the allotted time.

Note HPCCS does not acquire the science packets in SCOS but archives them into TMDUMP files instead. However, it will route the packets to the IEGSE if the link is enabled.

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script to put PACS in simulated Nominal Spectroscopy from SAFE: P102999SCVT904_ASDGENPACS_NomSpect | | | | | |
| 2. | PACS in Simulated Nominal Spectroscopy for 60 mins. | | | | | |
| 3. | Return to or synchronise with calling Procedure | | | | | |

| | | | | | |
|---------------------------|--|--|-----------------|------------|------------|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|---------------------------|--|--|-----------------|------------|------------|

| | | | |
|---------------------------|--|--|-----------------------|
| Enter Date Time: | | | Test Location: |
|---------------------------|--|--|-----------------------|

7.1.7 PACS Standby (SAFE) to Burst Mode (to Standby)

Running the following procedure will configure PACS from SAFE to Simulated Burst mode for a period of 60mins. **TBC which APIDs are generated!!** The test script will autonomously return PACS to SAFE after the allotted time.

Note HPCCS does not acquire the science packets in SCOS but archives them into TMDUMP files instead. However, it will route the packets to the IEGSE if the link is enabled.

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|--|------------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script to put PACS in simulated Nominal Spectroscopy from SAFE: P102999SCVT913_ASDGENPACS_BurstMode | | | | | |
| 2. | PACS in Simulated Burst mode for 60 mins. | | | | | |
| 3. | Return to or synchronise with calling Procedure | | | | | |

| | | | | | |
|---------------------------|--|--|-----------------|------------|------------|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|---------------------------|--|--|-----------------|------------|------------|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.1.8 PACS I-EGSE Disconnection

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|----------------------|---|---|
| 1. | From HPCCS Test Conductor console issue command to disconnect PACS I-EGSE disconnect HPACSEGSE | DISCONNECTED | | AND: SYS_PARS | | |
| 2. | If no longer required for other instrument activities, from the HPCCS test conductor console terminate the test script: ALL_SubscribeParams | | | | | |
| 3. | Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.2 SPIRE Instrument Procedures

7.2.1 SPIRE I-EGSE Configuration/Connection

The following procedure is used when it is required to use the SPIRE IEGSE to support the test being performed, either for monitoring of SPIRE specific TM on the IEGSE or for commanding the instrument above REDY mode using a handshaking protocol between the HPCCS and the I-EGSE (i.e. Instrument specific testing such as SFTs). It is NOT normally required for switching SPIRE ON or OFF. This procedure is independent of SPIRE redundancy configuration.

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|--|------------------------|--------------|---------------------|---|---|
| 1. | If not already on, Switch on & configure SPIRE I-EGSE i.a.w. RD-7 | | | | | |
| 2. | From HPCCS Test Conductor console issue command to connect to SPIRE I-EGSE connect HSPIREEGSE | YES29940= CONNECTED | | AND SYS_PARS | | |
| | <i>Perform the following two steps if command parameter exchange is required between the IEGSE and HPCCS for the test concerned.</i> | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 3. | If not already running from the HPCCS test conductor console execute the test script: <p style="text-align: center;">ALL_SubscribeParams</p> | | | | | |
| 4. | Verify HPCCS-IEGSE connection by sending the following test command from manual command stack (repeater value 0) and verify received OK on IEGSE: <p style="text-align: center;">YC00X966</p> | OK | | | | |
| 5. | Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.2.2 SPIRE Prime OFF to Standby (REDY)

The following will switch ON and configure SPIRE Prime instrument in REDY (Standby) mode. HKTM packets will be generated on APIDs 1280 dec and 1282 decimal (these can be observed using TMPH with corresponding filter – note however a limited number of TMPHs should be running at one time).

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script to power SPIRE Prime to REDY: Z102999SCVT004_ASDGEN_SPIREPWRON_P | | | | | |
| 2. | On HPCCS when prompted: "SPIRE Switch ON for IST Debug only in warm conditions - Select NO to abort TS if not correct" | YES | | | | |
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|--|------------------|--------------|---------|---|---|
| 4. | If YES is selected the test script will go on to automatically power on all SPIRE warm units, force boot the DPU ASW and configure the instrument to REDY (Standby mode). | | | | | |
| 5. | On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT004_ASDGEN_SPIREPWRON_P it will prompt: <i>“Set Bus Profile Back to Original Setting?”</i> | NO | | | | |
| 6. | Select YES if it is likely that other non-SPIRE instrument related activities are to be performed. <i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i> <i>“Bus Profile left unchanged, as original setting 0 (Launch)”</i> | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|



| | | | | |
|--------------------|--|--|----------------|--|
| Enter Date Time: | | | Test Location: | |
|--------------------|--|--|----------------|--|

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------------------|---|--------------------------|---------------------|----------------|----------|----------|
| 10 | SPIRE powered and in REDY mode Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.2.3 SPIRE Prime Standby (REDY) to OFF

The following procedure will switch SPIRE Prime from REDY to OFF.

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script to power OFF SPIRE Prime from REDY: Z102999SCVT005_ASDGEN_SPIREPWROFF_P | OK | | | | |
| 2. | On HPCCS when prompted: "SPIRE Switch OFF for IST Debug only in warm conditions - Select NO to abort TS if not correct" | YES | | | | |
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |
| 4. | If YES is selected the test script will go on to automatically power off all SPIRE warm units. | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 5. | <p>During Switch OFF of SPIRE the following (5,1) and (5,4) event messages on APID 1280 are expected and do not indicate a problem:</p> <p style="margin-left: 40px;">a) EVID 1313 No_MCU_Response_Error b) EVID 21773 ALARM_LSMCU_DEAD</p> | | | | | |
| 6. | <p>On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT005_ASDGEN_SPIREPWROFF_P it will prompt:</p> <p><i>“Set Bus Profile Back to Original Setting?”</i></p> | NO | | | | |
| 7. | <p>Select YES if it is likely that other non-SPIRE instrument related activities are to be performed.</p> <p><i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i></p> <p><i>“Bus Profile left unchanged, as original setting 0 (Launch)”</i></p> | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|--|---------------|--------------|---------|---|---|
| 8. | If NO selected then at the prompt: "Bus Profile left unchanged" Select OK to continue | OK | | | | |
| 9. | On HPCCS when prompted: "Set Bus Profile Back to Original Setting?" Select NO | NO | | | | |
| 10. | At prompt: "Bus Profile left unchanged" Select OK to continue | OK | | | | |
| 11. | SPIRE OFF. Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.2.4 SPIRE Redundant OFF to Standby (REDY)

The following will switch ON and configure SPIRE Redundant instrument in REDY (Standby) mode. HKTM packets will be generated on APIDs 1281 dec and 1283 decimal (these can be observed using TMPH with corresponding filter – note however a limited number of TMPHs should be running at one time).

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script to power SPIRE Prime to REDY: Z102999SCVT006_ASDGEN_SPIREPWRON_R | | | | | |
| 2. | On HPCCS when prompted: "SPIRE Switch ON for IST Debug only in warm conditions - Select NO to abort TS if not correct" | YES | | | | |
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|--|---------------|--------------|---------|---|---|
| 4. | If YES is selected the test script will go on to automatically power on all SPIRE warm units, force boot the DPU ASW and configure the instrument to REDY (Standby mode). | | | | | |
| 5. | On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT006_ASDGEN_SPIREPWRON_R it will prompt: <i>"Set Bus Profile Back to Original Setting?"</i> | NO | | | | |
| 6. | Select YES if it is likely that other non-SPIRE instrument related activities are to be performed. <i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i> <i>"Bus Profile left unchanged, as original setting 0 (Launch)"</i> | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|



| | | | | |
|--------------------|--|--|----------------|--|
| Enter Date Time: | | | Test Location: | |
|--------------------|--|--|----------------|--|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|-----------------|---|----------------------|---------------------|----------------|----------|----------|
| 10. | SPIRE powered and in REDY mode Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.2.5 SPIRE Redundant Standby (REDY) to OFF

The following procedure will switch SPIRE Redundant from REDY to OFF.

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script to power OFF PACS Redundant from SAFE: Z102999SCVT007_ASDGEN_SPIREPWROFF_R | OK | | | | |
| 2. | On HPCCS when prompted: "SPIRE Switch OFF for IST Debug only in warm conditions - Select NO to abort TS if not correct" | YES | | | | |
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |
| 4. | If YES is selected the test script will go on to automatically power off all SPIRE warm units. | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 5. | <p>During Switch OFF of SPIRE the following (5,1) and (5,4) event messages on APID 1281 are expected and do not indicate a problem:</p> <p style="margin-left: 40px;">c) EVID 1313 No_MCU_Response_Error d) EVID 21773 ALARM_LSMCU_DEAD</p> | | | | | |
| 6. | <p>On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT007_ASDGEN_SPIREPWROFF_R it will prompt:</p> <p style="margin-left: 40px;"><i>“Set Bus Profile Back to Original Setting?”</i></p> | NO | | | | |
| 7. | <p>Select YES if it is likely that other non-SPIRE instrument related activities are to be performed.</p> <p style="margin-left: 40px;"><i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i></p> <p style="margin-left: 40px;"><i>“Bus Profile left unchanged, as original setting 0 (Launch)”</i></p> | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|--|---------------|--------------|---------|---|---|
| 8. | If NO selected then at the prompt: "Bus Profile left unchanged" Select OK to continue | OK | | | | |
| 9. | SPIRE OFF. Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.2.6 SPIRE I-EGSE Disconnection

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|--------------------------|---|---|
| 1. | From HPCCS Test Conductor console issue command to disconnect PACS I-EGSE disconnect HSPIREEGSE | DISCONNECTED | | AND: SYS_PARS | | |
| 2. | If no longer required for other instrument activities, from the HPCCS test conductor console terminate the test script: ALL_SubscribeParams | | | | | |
| 3. | Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.3 HIFI Instrument Procedures

7.3.1 HIFI I-EGSE Configuration/Connection

The following procedure is used when it is required to use the HIFI IEGSE to support the test being performed, either for monitoring of HIFI specific TM on the IEGSE or for commanding the instrument above Standby mode using a handshaking protocol between the HPPCCS and the I-EGSE (i.e. Instrument specific testing such as SFTs). It is NOT normally required for switching HIFI ON or OFF. This procedure is independent of HIFI redundancy configuration.

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|--|---------------|--------------|---------|---|---|
| 1. | Confirm LOU dummy connected to flight harness connector and configured for band 1a, and that drain resistances D1 & D2 on LOA dummy have been set correctly plus that LSU waveguide 1a is terminated with matched load as per section 4.1.3.2. Confirm that safety precautions have been applied as per section 5.3.2.1 | Confirmed | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | | |
|--------------------|--|--|----------------|--|
| Enter Date Time: | | | Test Location: | |
|--------------------|--|--|----------------|--|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|-------------------------|--------------|---------------------|---|---|
| 2. | If not already on, Switch on & configure HIFI I-EGSE i.a.w. RD-6 Ensure HIFI I-EGSE up and running and configured according to RD-6. As part of the configuration in section 4.1, step 3 the configuration to be selected is "Prime" and "FM FPU and dummy LOU" | OK | | | | |
| 3. | If not already on, Switch on & configure HIFI I-EGSE i.a.w. RD-6 | | | | | |
| 4. | From HPCCS Test Conductor console issue command to connect to HIFI I-EGSE connect HHIFIEEGSE | YES27940== CONNECTED | | AND SYS_PARS | | |
| | <i>Perform the following two steps if command parameter exchange is required between the IEGSE and HPCCS for the test concerned.</i> | | | | | |
| 5. | If not already running from the HPCCS test conductor console execute the test script: ALL_SubscribeParams | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|--|---------------|--------------|---------|---|---|
| 6. | Verify HPCCS-IEGSE connection by sending the following test command from manual command stack (repeater value 0) and verify received OK on IEGSE: <div style="text-align: right;">YC00X962</div> | OK | | | | |
| 7. | Patch HIFI synthetic parameters for warm conditions by executing the following scripts: <div style="text-align: center;"> HIFIST_ASED_PatchPtvChecksum HIFIST_ASED_PatchTempLimits </div> <i>Note these scripts replace HIFIST_CCS_conf_ptv_checksum due to NCR-3652</i> | OK | | | | |
| 8. | Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.3.2 HIFI Prime OFF to Standby

The following will switch ON and configure HIFI Prime instrument in Standby mode. HKTM packets will be generated on APIDs 1024 dec and 1026 decimal (these can be observed using TMPH with corresponding filter – note however a limited number of TMPHs should be running at one time).

NB: The WBS laser temperature (HM023193 HWH_Laser_T and HWV_Laser_T) may rise above a red limit in the MIB. If this occurs the test can continue. Logging is not required since the lasers will not be switched on in the CE test

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|--|------------------|--------------|------------------------------|---|---|
| 1. | From the HPCCS test conductor console start the test script: Z102999SCVT014_ASDGEN_HIFIPWRON_P | OK | | ANDs HA000289 HA004289 | | |
| 2. | On HPCCS when prompted: "FM HIFI Switch ON for Functional Tests only in warm conditions with LOU or dummy - Select NO to abort TS if not correct" | YES | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |
| 4. | If YES is selected the test script will go on to automatically power on all HIFI warm units, force boot the DPU ASW and configure the instrument to Standby. | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|--|---------------|--------------|--|---|---|
| 5. | <p>See Remarks !! On HPCCS when prompted:</p> <p>"Press OK when IEGSE confirms LCU status OK"</p> <p>Request I_EGSE operator to run the command 'LCUtable/verifyreadback' using the OBSID retrieved in the previous step. If the word PASS does not appear on the screen at the end, this is a nogo on this test procedure.</p> <p>If OK respond to prompt accordingly, otherwise contact SRON to investigate and resolve before continuing</p> <p>At prompt to record OBS_ID_per_hk during execution of following script HIFIST_Startup_LCU_table_read record value if HM003190 = 900002A5 hex (Note: at start & end value is 90000000 hex)</p> | OK | | <p>The HIFI instrument support responsible shall be connected remotely to observe the status of the HIFI. So he should be contacted before this test step</p> | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|--|---------------|--------------|---------|---|---|
| 6. | <p>On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT014_ASDGEN_HIFIPWRON_P it will prompt:</p> <p><i>“Set Bus Profile Back to Original Setting?”</i></p> | NO | | | | |
| 7. | <p>Select YES if it is likely that other non-HIFI instrument related activities are to be performed.</p> <p><i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i></p> <p><i>“Bus Profile left unchanged, as original setting 0 (Launch)”</i></p> | OK | | | | |
| 8. | <p>If NO selected then at the prompt:</p> <p><i>“Bus Profile left unchanged”</i></p> <p>Select OK to continue</p> | OK | | | | |
| 9. | Verify HK TM packets are being received on | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|



| | | | | |
|--------------------|--|--|----------------|--|
| Enter Date Time: | | | Test Location: | |
|--------------------|--|--|----------------|--|

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------------------|---|--------------------------|---------------------|----------------|----------|----------|
| | APIDs 1024 & 1026 | | | | | |
| 10. | HIFI powered and in Standby mode Return to calling Procedure | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.3.3 HIFI Prime Standby to OFF

The following procedure will switch HIFI Prime from Standby to OFF.

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script: Z102999SCVT015_ASDGEN_HIFIPWROFF_P | OK | | | | |
| 2. | On HPCCS when prompted: "FM HIFI Prime Switch OFF for Functional Tests only in warm conditions - Select NO to abort TS if not correct" | YES | | | | |
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |
| 4. | If YES is selected the test script will go on to automatically power off all HIFI warm units. | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 5. | On HPCCS when prompted: "Press OK when IEGSE confirms LCU status OK" respond accordingly | OK | | | | |
| 6. | On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT015_ASDGEN_HIFIPWROFF_P it will prompt: <i>"Set Bus Profile Back to Original Setting?"</i> | NO | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 7. | <p>Select YES if it is likely that other non-HIFI instrument related activities are to be performed.</p> <p><i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i></p> <p>“Bus Profile left unchanged, as original setting 0 (Launch)”</p> | OK | | | | |
| 8. | <p>If NO selected then at the prompt:</p> <p>“Bus Profile left unchanged”</p> <p>Select OK to continue</p> | OK | | | | |
| 9. | <p>HIFI OFF</p> <p>Return to calling Procedure</p> | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.3.4 HIFI Redundant OFF to Standby

The following will switch ON and configure HIFI Redundant instrument in Standby mode. HKTM packets will be generated on APIDs 1025 dec and 1027 decimal (these can be observed using TMPH with corresponding filter – note however a limited number of TMPHs should be running at one time).

NB: The WBS laser temperature (HM023193 HWH_Laser_T and HWV_Laser_T) may rise above a red limit in the MIB. If this occurs the test can continue. Logging is not required since the lasers will not be switched on in the CE test

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|--|------------------|--------------|------------------------------|---|---|
| 1. | From the HPCCS test conductor console start the test script: Z102999SCVT016_ASDGEN_HIFIPWRON_R | OK | | ANDs HA000289 HA004289 | | |
| 2. | On HPCCS when prompted: “FM HIFI Switch ON for Functional Tests only in warm conditions with LOU or dummy - Select NO to abort TS if not correct” | YES | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---|---|---|
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |
| 4. | If YES is selected the test script will go on to automatically power on all HIFI warm units, force boot the DPU ASW and configure the instrument to Standby. | | | | | |
| 5. | <p>See Remarks !! On HPCCS when prompted:</p> <p>"Press OK when IEGSE confirms LCU status OK"</p> <p>Request I_EGSE operator to run the command 'LCUtable/verifyreadback' using the OBSID retrieved in the previous step. If the word PASS does not appear on the screen at the end, this is a nogo on this test procedure.</p> <p>If OK respond to prompt accordingly, otherwise contact SRON to investigate and resolve before continuing</p> | OK | | The HIFI instrument support responsible shall be connected remotely to observe the status of the HIFI. So he should be contacted before this test step | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| | At prompt to record OBS_ID_per_hk during execution of following script HIFIST_Startup_LCU_table_read record value if HM003190 = 900002A5 hex (Note: at start & end value is 90000000 hex) | | | | | |
| 6. | On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT016_ASDGEN_HIFIPWRON_R it will prompt: <i>“Set Bus Profile Back to Original Setting?”</i> | NO | | | | |
| 7. | Select YES if it is likely that other non-HIFI instrument related activities are to be performed. <i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i> <i>“Bus Profile left unchanged, as original setting 0 (Launch)”</i> | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|



| | | | | |
|--------------------|--|--|----------------|--|
| Enter Date Time: | | | Test Location: | |
|--------------------|--|--|----------------|--|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|--|---------------|--------------|---------|---|---|
| 8. | If NO selected then at the prompt: "Bus Profile left unchanged" Select OK to continue | OK | | | | |
| 9. | Verify HK TM packets are being received on APIDs 1025 & 1027 | | | | | |
| 10. | HIFI powered and in Standby mode Return to calling Procedure | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.3.5 HIFI Redundant Standby to OFF

The following procedure will switch HIFI Redundant from Standby to OFF.

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|---------|---|---|
| 1. | From the HPCCS test conductor console start the test script: Z102999SCVT017_ASDGEN_HIFIPWROFF_R | OK | | | | |
| 2. | On HPCCS when prompted: "FM HIFI Redundant Switch OFF for Functional Tests only in warm conditions - Select NO to abort TS if not correct" | YES | | | | |
| 3. | If in any doubt about the script being executed NO should be selected to abort the script. Before restarting consult the relevant instrument support engineer to confirm the correct script to be used for the test in question. | | | | | |
| 4. | If YES is selected the test script will go on to automatically power off all HIFI warm units. | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|--|---------------|--------------|---------|---|---|
| 5. | On HPCCS when prompted: "Press OK when IEGSE confirms LCU status OK" respond accordingly | OK | | | | |
| 6. | On HPCCS when all autonomous actions have been completed by the power on script Z102999SCVT017_ASDGEN_HIFIPWROFF_R it will prompt: "Set Bus Profile Back to Original Setting?" | NO | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

| Step-No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|----------|---|---------------|--------------|---------|---|---|
| 7. | <p>Select YES if it is likely that other non-HIFI instrument related activities are to be performed.</p> <p><i>However note that if the original Bus Profile was 0 (launch) the script will automatically leave the Bus Profile unchanged as this profile is not compatible with instruments being powered in Standby:</i></p> <p>“Bus Profile left unchanged, as original setting 0 (Launch)”</p> | OK | | | | |
| 8. | <p>If NO selected then at the prompt:</p> <p>“Bus Profile left unchanged”</p> <p>Select OK to continue</p> | OK | | | | |
| 9. | <p>HIFI OFF</p> <p>Return to calling Procedure</p> | OK | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

| | | | |
|--------------------|--|--|----------------|
| Enter Date Time: | | | Test Location: |
|--------------------|--|--|----------------|

7.3.6 HIFI I-EGSE Disconnection

| Step- No. | Test-Step-Description | Nominal Value | Actual Value | Remarks | P | N |
|--------------|---|------------------|--------------|--------------------------|---|---|
| 1. | From HPCCS Test Conductor console issue command to disconnect PACS I-EGSE disconnect HHIFIEGSE | DISCONNECTED | | AND: SYS_PARS | | |
| 2. | If no longer required for other instrument activities, from the HPCCS test conductor console terminate the test script: ALL_SubscribeParams | | | | | |
| 3. | Return to calling Procedure | | | | | |

| | | | | | |
|--------------------|--|--|----------|-----|-----|
| Enter Date Time: | | | Sign Off | TD: | PA: |
|--------------------|--|--|----------|-----|-----|

8 ANNEX

8.1 Script hierarchy

Detailed in the following sub-sections:

8.1.1 General

ALL_SubscribeParams

8.1.2 PACS

Z102999SCVT010_ASDGEN_PACSPWRON_P

- > P102999SCVT905_ASDISTPACS_PWR_ON_N
- > -> Z010999MMXX002UNITS_CHECK

Z102999SCVT011_ASDGEN_PACSPWROFF_P

- > P102999SCVT906_ASDISTPACS_PWR_OFF_N
- > -> Z010999MMXX002UNITS_CHECK

Z102999SCVT012_ASDGEN_PACSPWRON_R

- P102999SCVT907_ASDISTPACS_PWR_ON_R
- > -> Z010999MMXX002UNITS_CHECK

Z102999SCVT013_ASDGEN_PACSPWROFF_R

- > P102999SCVT908_ASDISTPACS_PWR_OFF_R
- > -> Z010999MMXX002UNITS_CHECK

P102999SCVT904_ASDGENPACS_NomSpect

P102999SCVT913_ASDGENPACS_BurstMode

8.1.3 SPIRE

Z102999SCVT004_ASDGEN_SPIREPWRON_P

- > S102999SCVT017_ASDGENSPIR_PWR_ON_P
- > -> SPIRE-IST-DBG-OFF2DPUON-SP
- > -> SPIRE-IST-DBG-DPUON2STBY
- > -> SPIRE-IST-DBG-LOAD-VM-TABLES
- > -> Z010999MMXX002UNITS_CHECK

Z102999SCVT005_ASDGEN_SPIREPWROFF_P

- > S102999SCVT019_ASDGENSPIR_PWR_OFF_P
- > -> SPIRE-IST-DBG-STBY2OFF
- > -> Z010999MMXX002UNITS_CHECK

Z102999SCVT006_ASDGEN_SPIREPWRON_R

-> S102999SCVT018_ASDGENSPIR_PWR_ON_R
-> -> SPIRE-IST-DBG-OFF2DPUON
-> -> SPIRE-IST-DBG-DPUON2STBY
-> -> SPIRE-IST-DBG-LOAD-VM-TABLES
-> -> Z010999MMXX002UNITS_CHECK

Z102999SCVT007_ASDGEN_SPIREPWROFF_R

-> S102999SCVT020_ASDGENSPIR_PWR_OFF_R
-> -> SPIRE-IST-DBG-STBY2OFF
-> -> Z010999MMXX002UNITS_CHECK

8.1.4 HIFI**HIFIST_ASED_PatchPtvChecksum****HIFIST_ASED_PatchTempLimits****Z102999SCVT014_ASDGEN_HIFIPWRON_P**

-> H102999SCVT005_ASDGENHIFI_PWR_ON_P
-> -> HIFIST_Startup_force_boot
-> -> HIFIST_Startup_OBS_SFT
-> -> HIFIST_Startup_FCU_on
-> -> HIFIST_Startup_WBS_lasertemp40
-> -> HIFIST_Startup_WBSH_on
-> -> HIFIST_Startup_WBSV_on
-> -> HIFIST_Startup_HRS_on
-> -> HIFIST_Startup_LCU_on
-> -> HIFIST_Startup_LCU_table_load
-> -> HIFIST_Startup_LCU_table_read
-> -> HIFIST_Startup_LO_Nominal
-> -> Z010999MMXX002UNITS_CHECK

Z102999SCVT015_ASDGEN_HIFIPWROFF_P

-> H102999SCVT006_ASDGENHIFI_PWR_OFF_P
-> -> HIFIST_Startup_FPU_standby
-> -> HIFIST_Startup_WBS_standby
-> -> HIFIST_Startup_HRS_standby
-> -> HIFIST_Startup_LCU_standby
-> -> HIFIST_Startup_all_off
-> -> Z010999MMXX002UNITS_CHECK

Z102999SCVT016_ASDGEN_HIFIPWRON_R

-> H102999SCVT007_ASDGENHIFI_PWR_ON_R
-> -> HIFIST_Startup_force_boot
-> -> HIFIST_Startup_OBS_SFT
-> -> HIFIST_Startup_FCU_on

- > -> HIFIST_Startup_WBS_lasertemp40
- > -> HIFIST_Startup_WBSH_on
- > -> HIFIST_Startup_WBSV_on
- > -> HIFIST_Startup_HRS_on
- > -> HIFIST_Startup_LCU_on
- > -> HIFIST_Startup_LCU_table_load
- > -> HIFIST_Startup_LCU_table_read
- > -> HIFIST_Startup_LO_Nominal
- > -> Z010999MMXX002UNITS_CHECK

Z102999SCVT017_ASDGEN_HIFIPWROFF_R

- > -> HIFIST_Startup_FPU_standby
- > -> HIFIST_Startup_WBS_standby
- > -> HIFIST_Startup_HRS_standby
- > -> HIFIST_Startup_LCU_standby
- > -> HIFIST_Startup_all_off
- > -> Z010999MMXX002UNITS_CHECK

8.2 Procedure Variation Summary

| | | | |
|-------------------|-------------------|------------------|------|
| | Test Change | Curr. No.: | |
| | | Date | |
| | | Page | of |
| Test designation | Test Procedure | Issue | Rev. |
| Test step changed | Reason for Change | | |
| | | | |
| Prepared by: | Resp. Test Leader | Project Engineer | |
| PA/QA | Prime | Customer | |

Table 8.2-1: Procedure Variation Sheet

8.3 Non Conformance Report (NCR) Summary

| NCR - No. | NCR - Title | Date | Open Closed | PA sig. |
|-----------|-------------|------|----------------|------------|
| | | | | |

Table 8.3-1: Non-Conformance Record Sheet

8.4 Sign-off Sheet

| | Date | Signature |
|---------------------------|-------------|------------------|
| Test Director | | |
| Test Conductor | | |
| PA Responsible | | |
| ESA Representative | | |

END OF DOCUMENT

| | Name | Dep./Comp. | | Name | Dep./Comp. |
|---|-------------------------|------------|---|---------------------------------------|-----------------|
| | Alberti von Mathias Dr. | ASG22 | | Schweickert Gunn | ASG22 |
| | Baldock Richard | FAE12 | X | Sonn Nico | ASG51 |
| | Barlage Bernhard | AED13 | | Steininger Eric | AED32 |
| | Bayer Thomas | ASA42 | X | Stritter Rene | AED11 |
| | Brune Holger | ASA45 | | Suess Rudi | OTN/ASA44 |
| | Edelhoff Dirk | AED2 | | Theunissen Martijn | Dutch Space |
| | Fehring Alexander | ASG13 | | Wagner Klaus | ASG22 |
| X | Fricke Wolfgang Dr. | AED 65 | X | Wietbrock Walter | AET12 |
| | Geiger Hermann | ASA42 | | Wöhler Hans | ASG22 |
| | Grasl Andreas | OTN/ASA44 | | Wössner Ulrich | ASE252 |
| | Grasshoff Brigitte | AET12 | X | <i>Vascolto Riccardo</i> | <i>HT Space</i> |
| X | Hamer Simon | Terma | | | |
| | Hendry David | Terma | | | |
| | Hengstler Reinhold | ASA42 | | | |
| | Hinger Jürgen | ASG22 | | | |
| X | Hohn Rüdiger | AED65 | | | |
| | Hölzle Edgar Dr. | AED32 | | | |
| | Huber Johann | ASA42 | | | |
| | Hund Walter | ASE252 | | | |
| X | Idler Siegmund | AED312 | | | |
| | Ivány von András | FAE12 | | | |
| | Jahn Gerd Dr. | ASG22 | | | |
| | Kalde Clemens | ASM2 | | | |
| | Kameter Rudolf | OTN/ASA42 | | | |
| | Kettner Bernhard | AET42 | | | |
| | Knoblauch August | AET32 | X | Alcatel Alenia Space Cannes | AAS-F |
| X | Koelle Markus | ASA43 | X | Alcatel Alenia Space Torino | AAS-I |
| X | Koppe Axel | AED312 | X | ESA/ESTEC | ESA |
| X | Kroeker Jürgen | AED65 | | | |
| X | La Gioia Valentina | Terma | | Instruments: | |
| | Lang Jürgen | ASE252 | X | MPE (PACS) | MPE |
| | Langenstein Rolf | AED15 | X | RAL (SPIRE) | RAL |
| | Langfermann Michael | ASA41 | X | SRON (HIFI) | SRON |
| X | Maukisch Jan | ASA43 | | | |
| X | Much Christoph | ASA43 | | | |
| | Müller Jörg | ASA42 | | Subcontractors: | |
| | Müller Martin | ASA43 | | Alcatel Alenia Space Antwerp | ABSP |
| | Peltz Heinz-Willi | ASG13 | | Austrian Aerospace | AAE |
| | Pietroboni Karin | AED65 | | Austrian Aerospace | AAEM |
| | Platzer Wilhelm | AED2 | | BOC Edwards | BOCE |
| | Reichle Konrad | ASA42 | | Dutch Space Solar Arrays | DSSA |
| | Runge Axel | OTN/ASA44 | | EADS Astrium Sub-Subsyst. & Equipment | ASSE |
| | Schink Dietmar | AED32 | | EADS CASA Espacio | CASA |
| | Schlosser Christian | OTN/ASA44 | | EADS CASA Espacio | ECAS |
| | Schmidt Rudolf | FAE12 | | European Test Services | ETS |
| | Schmidt Thomas | ASA42 | | Patria New Technologies Oy | PANT |
| | Schuler Günter | ASA42 | | SENER Ingenieria SA | SEN |