







Title: **IST Instrument Commissioning  
SPIRE FM Peak-up Mode Test**

CI-No: 125200

Prepared by:	 A. Koppe/S. Hamer	Date:	22.07.2008
Checked by:	 S. Idler		<del>24.07.2008</del>
Product Assurance:	for R. Stritter 		24/07/08
Configuration Control:	W. Wietbrock 		24.107/08
Project Management:	W. Fricke 		25/07/08
TAS-F	For D. Montet  collaudem		24/7/08

Distribution: See Distribution List (last page)

Copying of this document, and giving it to others and the use or communication of the contents thereof, are forbidden without express authority. Offenders are liable to the payment of damages. All rights are reserved in the event of the grant of a patent or the registration of a utility model or design.

Issue	Date	Sheet	Description of Change	Release
1	04.07.08	All	First Formal Issue	
1.1	22.07.08	22	Removal of "TBD" in step 4	

**Table of Content**

<b>1</b>	<b>Scope</b>	<b>7</b>
1.1	Objective	7
1.2	Test Flow	7
<b>2</b>	<b>Documents/Drawings</b>	<b>8</b>
2.1	Applicable Documents	8
2.2	Reference Documents	8
2.3	Other Documents	9
2.4	Acronyms & Abbreviations	9
<b>3</b>	<b>Configuration</b>	<b>13</b>
3.1	Satellite Configuration	13
3.2	EGSE Configuration	13
3.3	Set-up	13
<b>4</b>	<b>Test Sequence</b>	<b>14</b>
<b>5</b>	<b>Conditions</b>	<b>16</b>
5.1	Personnel	16
5.2	Environmental	17
5.3	General Precautions and Safety	17
5.3.1	General Safety Requirements, Precautions	17
5.3.2	ESD constraints	18
5.3.3	Cryo Specific Safety Requirements	18
5.3.4	Special QA Requirements	19
5.4	GSE	19
5.4.1	MGSE	19
5.4.2	CVSE	19
5.4.3	EGSE	19
5.4.4	OGSE	19
5.4.5	Special Equipment	19
<b>6</b>	<b>Verification Requirements and Test Criteria</b>	<b>20</b>

<b>7</b>	<b>Test Procedure</b>	<b>21</b>
7.1	Initial EGSE and Satellite Configuration for the Test	21
7.2	Step by Step Procedure	22
7.2.1	EGSE & Satellite Switch On for Peak-up Mode Test	22
7.2.2	SPIRE Peak-up Mode Tests - Nominal	25
7.2.2.1	Switch ON SPIRE PRIME	25
7.2.2.2	Peak-up Mode Procedure – Nominal	29
7.2.3	SPIRE Peak-up Mode Test – Redundant	34
7.2.3.1	Switch ON SPIRE REDUNDANT	34
7.2.3.2	Peak-up Mode Procedure – Redundant	38
7.2.3.3	Switch OFF SPIRE REDUNDANT	39
7.2.4	Satellite & EGSE Switch Off After Peak-up Mode Test	42
7.2.5	SPIRE SAFE Switch Off	43
<b>8</b>	<b>Summary Sheets</b>	<b>45</b>
8.1	Procedure Variation Summary	46
8.2	Non Conformance Report (NCR) Summary	47
8.3	Sign-off Sheet	48
<b>APPENDIX 1</b>		<b>49</b>

## Table of Figures

**No table of figures entries found.**

## List of Tables

Table 8.1-1: Procedure Variation Sheet .....	46
Table 8.2-1: Non-Conformance Record Sheet.....	47

## 1 Scope

This document describes the Peak-up Mode Tests to be performed on the SPIRE FM Instrument for IST Instrument Commissioning (ref AD6 & AD9) in Hel or Hell conditions.

This test will be run independently of the other parts of the IST Instrument Commissioning.

Both redundancies are tested within this procedure.

### Constraints General

- This procedure requires the presence of SPIRE personnel as the I-EGSE will be required to assess the results online as part of the pass/fail criteria.
- Before carrying out the next procedure within the test sequence always ask for the go ahead by the SPIRE staff.

### Constraints Specific

- There are no specific constraints for this test

## 1.1 Objective

The objective of the test is to functionally check FM instrument as much as feasibly possible in Hel or Hell conditions in an AIT environment.

## 1.2 Test Flow

The CFT flow is as follows:

1. Power on and configure SPIRE I-EGSE for test
2. Power on and configure SVM for test including CCU
3. Power on NOMINAL SPIRE Prime DPU & DRCU and enable Mil1553B-bus interface
4. Run Peak-up Mode Procedures
5. Power off MCU Prime
6. Disable Mil1553B-bus interface and Power off SPIRE Prime DRCU & DPU
7. Repeat Steps 3 – 6 for Spire Redundant Peak-up Mode Procedures
8. Power off SVM including CCU
9. Switch off all EGSE

## 2 Documents/Drawings

### 2.1 Applicable Documents

AD 1	FM SPIRE PFM Final Electrical Integration Procedure	HP-2-ASED-TP-0166
AD 2	Herschel PCDU & CDMS Nominal Switch On/Off Procedure	HP-2-ASED-PR-0070
AD 3	Herschel SAT Emergency Switch Off Procedure	HP-2-ASED-PR-0071
AD 4	PA Plan	HP-2-ASED-PL-0007
AD 5	I-EGSE Switch ON/OFF Procedure	TBI
AD 6	Test Specification for Herschel Instrument AVM & FM Tests Performed at Satellite Level, Issue 2	H-P-2-ASP-TS-1083
AD 7	H-P GDIR	H-P-1-ASPI-SP-0027
AD 8	SPIRE I-EGSE Set-Up, Issue 2.2	SPIRE-RAL-DOC-002841
AD 9	Herschel Integrated Satellite Test Specification, Issue 5	H-P-2-ASP-SP-0939
AD 10	Herschel IST Lead Procedure	HP-2-ASED-TP-0134
AD11	S/C Configuration for IST Instrument Commissioning, Issue 1	HP-2-ASED-TP-0237

### 2.2 Reference Documents

RD 1	Herschel Planck Central Checkout System System User Manual	H-P-4-TE-MA-0010
RD 2	SPIRE Cold Functional Test Procedures, Iss. 2.5	SPIRE-RAL-PRC-2398
RD 3	Herschel CDMU ASW S/W Interface Control Document	H-P-4-SSF-IC-0001
RD 4	Herschel CDMU BSW S/W Interface	H-P-4-SES-NT-0076



Control Document

RD 5	SPIRE IID-B	SCI-PT-IIDB/SPIRE-02124
RD 6	SPIRE Functional Test Specification Iss. 1.4	SPIRE-RAL-DOC-001652
RD 7	SPIRE Instrument User Manual Iss. 1.0	SPIRE-RAL-PRJ-002395
RD 8	H/P OBT-UTC Time Synchronisation Technical Note Iss. 1.3	PT-CMOC-OPS-TN-6604-OPS- OGH
RD 9	SPIRE Peak-up Mode Test Procedure; Issue 1.0	SPIRE-RAL-PRC-3033

**2.3 Other Documents**

None

**2.4 Acronyms & Abbreviations**

1553	MIL-STD-1553B conform communication interface
AAD	Attitude Anomaly Detector
ACC	ACMS Control Computer
ACMS	Attitude Control and Measurement Subsystem
AD	Applicable Document
AIR	ACC In Reconfiguration
AIT	Assembly, Integration and Test
AIV	Assembly, Integration and Verification
APID	Application Process ID
ASW	Application Software
AVM	Avionics Model
BOLC	BOLometer Control unit (PACS)
BSW	Basic Software
CBH	Catalyst Bed Heater
CCS	Central Check-out System
CCSDS	Consultative Committee for Space Data Systems
CDMU	Control and Data Management Unit
CDMS	Control and Data Management Sub-system
CFT	Cold Functional Test

CIR	CDMU In Reconfiguration
CLCW	Command Link Control Word
CLTU	Command Link Transmission Unit
CPDU	Command Pulse Distribution Unit
CRS	Coarse Rate Sensor
CTR	Central on board Reference Time
DCU	Detector Control Unit (SPIRE)
DEC	Detectors Electronics Control unit (PACS)
DMC	Detector and Mechanism Control unit (PACS)
DPU	Digital Processing Unit
DRCU	Detector Readout & Control Unit (SPIRE)
EEPROM	Electrically Erasable PROM
EGSE	Electrical Ground Support Equipment
FCL	Fold-back Current Limiter
FCU	FPU Control Unit (Spire)
FCV	Flow Control Valves
FDIR	Failure Detection, Isolation, and Recovery
FPU	Focal Plane Unit
GDIR	General Design and Interface Requirement
GRP	Group Heaters Switch
HBR	High Bit Rate
HL/HLC	High Level command
HP/HPC	High Priority commands
HPLM	Herschel PayLoad Module
HPsDB	Herschel Planck System Data Base
HW	Hardware
i.a.w.	In accordance with
I/F	InterFace
I/O	Input/Output
ICD	Interface Control Document
IST	Integrated System Test
LCL	Latching Current Limiter

LV	Latching Valves
LBR	Low Bit Rate
MAP	Multiplexed Access Point
MBR	Medium Bit Rate
MCU	Mechanisms Control Unit (SPIRE)
MEC	Mechanisms Electronics Control unit (PACS)
ML 16	Memory Load command (ML 16)
MM	Memory Module
MOIS	Mission Operations Information System
MTL	Mission Timeline
NRZ-L	Non Return to Zero – Litton
OBCP	On-Board Control Procedure
OBDH	On-Board Data Handling
OBMF	On-Board Monitoring Function
OBRT/OBT	On-Board Reference Time
OIRD	Operation Interface Requirement Document
PACS	Photodetector Array Camera & Spectrometer
P/L	Payload
PCDU/PCS	Power Control Distribution Unit/Power Control Subsystem
PM	Processor Module
PROM	Programmable Read Only Memory
PSK	Phase Shift Keying
RA	Rate Anomaly
RAM	Random Access Memory
RCS	Reaction Control Subsystem
RD	Reference Document
RF	Radio Frequency
RM	Reconfiguration Module
RT	1553 Remote Terminal
RTU	RT Unit
RTA	RTU
RWL	Reaction Wheel Assembly

SA	1553 Remote Terminal Sub Address
SAS	Sun Acquisition Sensor
SCOE	Special Check-out Equipment
SCU	Subsystems Control Unit (SPIRE)
SIR	S/C In Reconfiguration
SIT	Subsystem Integrated Test
SP	Sun Pointing
SPIRE	Spectral & Photometric Imaging Receiver
SPU	Signal Processing Unit (PACS)
SSMM	Solid State Mass Memory
STR	Star Tracker
SVM	Service Module
SW	Software
TAI	International Atomic Time
TC	TeleCommand
TFG	Transfer Frame Generator
TM	TeleMetry
TTC	Telemetry Tracking & Command subsystem
TTR	Telemetry Telecommand and Reconfiguration
UFT	Unit Functional Test
VC	Virtual Channel
WD	Watchdog

### **3 Configuration**

#### **3.1 Satellite Configuration**

The test requires use of the FM SVM powered on in its basic test mode (i.e. quick switch on (PCDU & CDMS) in accordance with AD 2 plus CCU connected to cryostat temperature and pressure sensors. Note this also means that the cryostat valves (command able from the CCS) may also be connected therefore this has to be considered as a SAFETY critical area to be addressed in section 5.

SPIRE FM units will be powered ON as per this procedure and assumes that FPU has already been successfully integrated to the warm units.

#### **3.2 EGSE Configuration**

This test requires the EGSE to be configured and elements powered on in accordance with AD 2.

I-EGSE shall be configured and connected to the HPCCS in accordance with AD 5 & AD 8.

#### **3.3 Set-up**

SPIRE Test Scripts for the test must be loaded on to the HPCCS and checked in prior to start of test.

## 4 Test Sequence

Ensure that the latest deliveries of SPIRE Peak-up Mode test scripts are installed on the CCS prior to start of test. The SPIRE I-EGSE will be running the following software for the test:

I-EGSE Software	Version	Comment
SPIRE MIB version		
SPIRE CUS version		
SCOS version		

The HPCSS HPSDB must also include the same SPIRE MIB version.

The normal sequence of events for a Peak-up mode operation is:

Send peak-up mode command to SPIRE

SPIRE executes a set of operations to determine the offsets to bring the source back onto the central pixel (takes approximately 3 mins)

SPIRE issues an event packet, TM(5,1) containing the offsets in y and z (format defined in AD01)

The CDMS acts on this event packet and sends the appropriate TC(s) to the AOCS.

There are 11 TCL scripts to verify full compliance to the interface:

Test Script	Delay/ seconds	Yangle Raw Decimal / Hex	Zangle Raw Decimal/Hex	Comments
SPIRE-IST- PeakUpTest-1.tcl	180	500 / 0x01f4	500 / 0x01f4	Move +5 arcsec in Y and Z
SPIRE-IST- PeakUpTest-2.tcl	10	-500 / 0x81f4	-500 / 0x81f4	Move -5 arcsec in Y and Z
SPIRE-IST- PeakUpTest-3.tcl	10	200 / 0x00c8	-200 / 0x80c8	Move +2 arcsec in Y and -2 arcsec in Z
SPIRE-IST- PeakUpTest-4.tcl	10	-200 / 0x80c8	200 / 0x00c8	Move -2 arcsec in Y and +2 arcsec in Z
SPIRE-IST- PeakUpTest-5.tcl	10	10100 / 0x2774	100 / 0x0064	Move +10.1 arcsec in Y and +1 arcsec in Z. Should be flagged as an error by the AOCS.

Test Script	Delay/ seconds	Yangle Raw Decimal / Hex	Zangle Raw Decimal/Hex	Comments
SPIRE-IST- PeakUpTest-6.tcl	10	100 / 0x0064	10100 / 0x2774	Move +1 arcsec in Y and +10.1 arcsec in Z. Should be flagged as an error by the AOCS.
SPIRE-IST- PeakUpTest-7.tcl	10	10100 / 0x2774	10100 / 0x2774	Move +10.1 arcsec in Y and +10.1 arcsec in Z. Should be flagged as an error by the AOCS.
SPIRE-IST- PeakUpTest-8.tcl	10	-10100 / 0xa774	100 / 0x0064	Move -10.1 arcsec in Y and +1 arcsec in Z. Should be flagged as an error by the AOCS.
SPIRE-IST- PeakUpTest-9.tcl	10	100 / 0x0064	-10100 / 0xa774	Move +1 arcsec in Y and -10.1 arcsec in Z. Should be flagged as an error by the AOCS.
SPIRE-IST- PeakUpTest-10.tcl	10	-10100 / 0xa774	-10100 / 0xa774	Move -10.1 arcsec in Y and -10.1 arcsec in Z.  Should be flagged as an error by the AOCS.
SPIRE-IST- PeakUpTest-11.tcl	10	0 / 0x0	0 / 0x0	No movement in Y or Z. How does the AOCS treat this event?

## 5 Conditions

### 5.1 Personnel

Responsibility	Name / Organisation
Test Director	
Test Conductor	
EGSE Operator	
PA Responsible	
Instrument Representative	
Customer Representative	
ESA Representative	



## 5.2 Environmental

The actual clean room and spacecraft environmental conditions for the test shall be recorded below.

Clean Room Conditions	Nominal	Actual
Clean Room Class	class 100000 or better	
Temperature	22°C ± 3°C	
Rel. Humidity	40 % - 60 %	
Pressure	Ambient	

S/C Environmental	Required	Actual
S/C Orientation	20° tilted around Z-axis, +Y pointing down	
Cryostat Status (Hel/Hell)	He 2	
Cryostat Level 0 Temp	1.77 K < T < 1.82 K	
Cryostat Level 1 Temp	< 7 K	
Cryostat Level 2 Temp	< 12 K	
Cryostat Level 3 Temp	N/A	N/A

## 5.3 General Precautions and Safety

Non-test specific precautions and safety considerations are detailed in section 5.3 of AD 2. Specific safety issues and general precautions for the tests to be performed are detailed in the following sections.

### 5.3.1 General Safety Requirements, Precautions

In the event of unrecoverable anomaly requiring emergency switch off of the satellite, the switch off shall be performed in accordance with AD 3.

**5.3.2 ESD constraints**

Normal ESD constraints are to be observed during the test.

**5.3.3 Cryo Specific Safety Requirements**

During the test the CCU may be connected to the Cryostat sensors and valves. Although no valve operation is performed in this test all Cryogenic specific safety requirements shall be considered when running this procedure as indicated below.

Safety instructions for cryogenic hazards coming from the Helium system are as follows:

1	<p>Helium itself is a non-toxic gas. The hazards to be expected are personal injuries from frostbites (cold surfaces, cold gas plumes), asphyxiation due to insufficient oxygen in the remaining air, loss of orientation due to dense fog generation and impacts of cold damaged structures.</p>
2	<p>Due to the amount of stored energy the Herschel cryostat is a pressure vessel and the general rules for pressure vessel design have to be followed. In addition to these general rules, the safety regulations at CSG launch site have to be considered. The application of these rules leads to a safety concept, which is based on the 'leak before burst' criterion. Herschel is based on the following safety and reliability philosophy:</p> <ul style="list-style-type: none"> <li>a. Two failure tolerant</li> <li>b. Three independent paths for overpressure relief</li> <li>c. Passive safety system for all operation modes (no active controls for monitoring is required at any time)</li> </ul> <p>As emergency situations may occur at unexpected points in time and typically need immediate action, the full hierarchy of the project cannot be deployed and consultation of all knowledgeable persons may not be possible.</p>
3	<p>The main intent of immediate actions will therefore be to ensure safety of personnel and to bring the S/C into a safe waiting condition. The priority of safeguarding is</p> <ul style="list-style-type: none"> <li>1) Personnel</li> <li>2) S/C</li> <li>3) Facility</li> <li>4) Support equipment</li> </ul> <p>The second aim is to keep the cryostat near the foreseen test conditions in order to continue the test without unnecessary time delay if the failure can be corrected.</p>
4	<p>The ASED test director (or his representative) will be informed by the test personnel of any non-conformances, alarm and unforeseen events that might lead to emergency situations. The ASED test director (or his representative) will initiate immediate steps and call the decision committee (ASED test director, ASED PA, ESA test director, ASP representative, ETS representative) if necessary.</p>

5	Prior to begin a pre-task briefing shall be performed to inform all participants about purpose of operation, possible hazards and emergency shut down
6	<p>In case of operation of the Cryostat safety system the following IMMEDIATE activities shall be performed:</p> <ul style="list-style-type: none"> <li>• Operation of the safety valve: EVERYBODY has to leave the test room, <u>except</u> test Conductor and necessary CVSE operations personnel</li> <li>• Operation of burst disc: EVERYBODY has to leave the test room</li> </ul>

**5.3.4 Special QA Requirements**

None.

**5.4 GSE**

Non-test specific GSE details are provided in section 5.4 of AD 2. Specific GSE needs for the tests to performed are detailed in the following sections.

**5.4.1 MGSE**

None.

**5.4.2 CVSE**

None.

**5.4.3 EGSE**

The I-EGSE is required for this test and will be connected to the HPCCS in accordance with AD 5.

**5.4.4 OGSE**

None.

**5.4.5 Special Equipment**

None.

## 6 Verification Requirements and Test Criteria

This is a functional check of a specific SPIRE FM mode test in Hel or Hell conditions and in AIT configuration as per AD6 and AD9.

Functional performance and status parameter actual values recorded will be checked during the test and must be the same as the nominal status value indicated.

The test will only be deemed successful once all offline analysis of the results has been performed. Typically, the PTR will be held before completion of this activity and therefore only a preliminary assessment of the test success can be provided to allow disconnection of any specific GSE required for the test and which needs to be removed before further activities can be performed.

Enter Start Date Time:			
------------------------	--	--	--

## 7 Test Procedure

### 7.1 Initial EGSE and Satellite Configuration for the Test

The Spire FM Final Integration according to the Test Procedure ref. AD 1 must be successfully completed before the execution of this procedure.

The EGSE and Satellite must be configured according to AD 2 prior to start of test.

***In case of anomaly on SPIRE requiring immediate switch off as directed by SPIRE responsible supporting the test section 7.2.5 shall be executed.***

***In the event of emergency the Satellite SHALL be switched down according to AD 3.***

Enter Date/Time:			Sign Off:	
------------------	--	--	-----------	--

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

**7.2 Step by Step Procedure**

<b>Test Location:</b>	
<b>Test Session Id:</b>	
<b>Test Environment:</b>	

**7.2.1 EGSE & Satellite Switch On for Peak-up Mode Test**

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
<b>Satellite &amp; EGSE Switch On</b>							
1	Confirm I-EGSE physically connected to HPCCS	OK					
2	Switch on & configure SPIRE I-EGSE i.a.w. <b>AD5 &amp; AD 8</b>	OK					
3	Confirm SPIRE I-EGSE is in the correct configuration as per AD5 & AD 8	OK					
4	Switch on HPCCS, SCOEs and Satellite/SVM and configure into Basic Test Mode, with SSMM initialized OBCP/EAT load/active and CCU monitoring in Mode 1 i.a.w. AD 10 sections 7.1 and 7.2 . In section 7.2.4 selecting the test case SPIRE Commissioning 5.8.4.5.1 in the Master GUI	OK					

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
5	Configure the Satellite specifically for SPIRE Commissioning i.a.w. with AD11 Section 7.2 continuing up to step 41	OK					
6	Confirm that EGSE and Satellite are in the correct configuration as per AD 2	OK					
7	If not already on, from HPCCS power ON CCU A & CCU B by executing test script:  <b>K102999ECVT001_ASDGENCCU_ABPWRON</b>	OK					
8	If not already enabled, from HPCCS enable Monitoring Mode 1 (512sec cycle) for CCU A & B by executing test script:  <b>K102999ECVT001_ASDGENCCU_MnEBOTH1</b>	OK					
9	Confirm that the ACMS is connected and powered on (ACC in SCM mode)	OK					
10	From HPCCS Test Conductor console issue command to connect to SPIRE I-EGSE  <b>connect HSPIREEGSE</b>	OK					
11	Confirm from HPCCS and SPIRE I-EGSE that the connection has been established	YZS29940= CONNECTED			<b>AND SYS_PARS</b>		
12	Verify that I-EGSE is receiving CCU Cryo packets	OK					
13	On HPCCS start the following test script:  <b>ALL_SubscribeParams.tcl</b>	OK					
14	Verify HPCCS-IEGSE connection by sending test command: <b>YC00X066</b> From the manual command stack (repeater value of "0")	OK					

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------



Enter Start Date Time:			
------------------------	--	--	--

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value	Remarks	P	N
15	If required load Synoptics INSTRUMENTS on HPCCS to display SPIRE status overview						
	<b>READY FOR START OF SPIRE PEAK-UP MODE TEST</b>						

Enter Date/Time:			Sign Off:	
------------------	--	--	-----------	--



<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

**7.2.2 SPIRE Peak-up Mode Tests - Nominal**

**7.2.2.1 Switch ON SPIRE PRIME**

The following will switch ON and configure SPIRE Prime instrument in REDY (Standby) mode. HKTm packets will be generated on APIDs 1280 dec and 1282 decimal (these can be observed using TMPH with corresponding filter – note however a limited number of TMPHs should be running at one time).

During power on of SPIRE a number of soft/hard OOLs are reported due to the sequential switch on of the units. This is expected and will clear when SPIRE is in REDY mode. When in REDY mode one parameter remains OOL (soft) namely SMD2V505 this is also expected.

Step-No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
1.	On HPCCS start Packet History displays for the following APIDs:1280,1282	OK				
2.	From the HPCCS test conductor console start the test script to power on SPIRE Prime: <b>S102999SCVT031_ASDCFTSPIR_PWR_ON_P</b>	OK		AND: ZAD07999, ZAD14999 MIM: LCL_HERSCHEL		

<b>Enter Date/Time:</b>			<b>Sign Off:</b>	
-------------------------	--	--	------------------	--

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Step-No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
3.	<p>On HPCCS when prompted:</p> <p>"SPIRE Switch ON for Cold FT related tests in Hel/Hell conditions only - Select NO to abort TS if not correct"</p> <p><b>Select YES</b></p>	YES				
	<p>If <b>YES</b> is selected the test script will go on to automatically power on all SPIRE warm units, force boot the DPU ASW and configure the instrument to Standby mode. Reply to prompts as indicated below.</p>					
4.	<p>On HPCCS when prompted:</p> <p>"Check Telemetry Updating Correctly and OBT is Consistent with CDMU - OK to continue"</p> <p><b>Select OK</b></p>	OK		<b>AND: SA_1_559</b>		

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Step-No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
5.	If I-EGSE connected when prompted on HPCCS, perform check requested then select <b>OK</b> : "Check IEGSE Time Consistent - OK to continue when RAL confirm"	OK				
6.	On HPCCS when prompted: "Check Telemetry No Longer Updating - OK to continue" Check that parameters: <div style="text-align: right; margin-right: 20px;">                         THSK Not refreshing                          TM2N Not incrementing                     </div> Select OK to continue	OK				
7.	On HPCCS when prompted: "Check Telemetry Updating Correctly - OK to continue" Check that parameters: <div style="text-align: right; margin-right: 20px;">                         THSK Refreshing @ 1Hz                          TM2N Incrementing by 1 @ 1Hz                     </div> Select OK to continue	OK		<b>AND: SA_1_559</b>		

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Step-No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
8.	On HPCCS when all autonomous actions have been completed by the power on script <b>S102999SCVT031_ASDCFTSPIR_PWR_ON_P</b> it will prompt: "Set Bus Profile Back to Original Setting?" Select NO	NO				
9.	At the prompt: "Bus Profile left unchanged" Select OK to continue	OK				
10.	Verify HK TM packets are being received on APIDs 1280 & 1282	OK				
	<b>SPIRE DPU &amp; DRCU powered</b>					

<b>Enter Date/Time:</b>			<b>Sign Off:</b>	
-------------------------	--	--	------------------	--

Enter Start Date Time:			
------------------------	--	--	--

7.2.2.2 Peak-up Mode Procedure – Nominal

The instrument shall be in DPU ON mode before test execution

Step	Action(s)	Description	Comments
	<p><i>The following step will generate peak-up command(s) to be sent to the ACMS. However because the test configuration is not a dynamic one (i.e. MTL controlled), these commands will have no direct effect on the ACMS (i.e. no manoeuvre performed), instead the ACMS will generate 5,1 events</i></p>		
1	<p>Execute TCL script SPIRE-IST-PeakUpTest-&lt;n&gt;.tcl</p> <p>Where n = 1 to 11.</p>	<p>If n=1 Wait for ~3 minutes, otherwise wait for 10 seconds (see table in section 4)</p>	
2	<p>Check that 5,1 event packet is issued with correct contents on the CCS</p> <p>See <b>Appendix A</b> for an example of a peak-up event packet dump</p>	<p>Event ID = 0x0504            SID = 0x5101            Instrument ID = 2            Yangle – see section 2.2            Zangle – see section 2.2</p> <p>The I-EGSE staff will also check the contents of peak-up event packet.</p>	
3	<p>Check CDMS issues correct commands to AOCS</p>	<p>Post test check by AOCS experts to see if the command to move is in accordance with</p>	

Enter Date/Time:			Sign Off:
------------------	--	--	-----------

Enter Start Date Time:			
------------------------	--	--	--

	Verify that the ACMS reports corresponding 8,6 packets with the correct content for the peak-up commands sent by SPIRE.	the peak-up event packet.	
4	Wait for the I-EGSE staff go-ahead before executing next step		

SPIRE remains in DPU ON mode after test execution

Enter Date/Time:			Sign Off:	
------------------	--	--	-----------	--

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Switch OFF SPIRE PRIME

Step- No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
1.	From the HPCCS test conductor console start the test script to power OFF SPIRE Prime:  <b>S102999SCVT032_ASDCFTSPIR_PWR_OFF_P</b>	OK				
2.	On HPCCS when prompted:  "SPIRE Switch OFF for CFT related tests in Hel/Hell conditions only - Select NO to abort TS if not correct"  <b>Select YES</b>	YES				
	If <b>YES</b> is selected the test script will go on to automatically power off all SPIRE warm units.					

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Step- No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
	<p>Note that during Switch OFF of SPIRE the following (5,2) and (5,4) event messages on APID 1280 may be expected and do not indicate a problem:</p> <p style="margin-left: 40px;">a) EVID 1313 No_MCU_Response_Error b) EVID 21773 ALARM_LSMCU_DEAD</p> <p><b>However, be aware that if FDIR is enabled for SPIRE in the CDMU then this may trigger an OBCP</b></p>					
3.	<p>On HPCCS when prompted: "Check Telemetry No Longer Updating - OK to continue"</p> <p>Check that parameters:</p> <p style="text-align: right; margin-right: 20px;">THSK Not refreshing TM2N Not incrementing</p>			AND: SA_1_559		
4.	Select OK to continue	OK				

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------



<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Step- No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
5.	On HPCCS when all autonomous actions have been completed by the power on script <b>S102999SCVT032_ASDCFTSPIR_PWR_OFF_P</b> it will prompt:  "Bus profile left as SPIRE PRIME, change manually after if required - OK to continue"					
6.	Select OK to continue	OK				
7.	On HPCCS stop Packet History displays for the following APIDs:1280,1282	OK				
	<b>SPIRE PRIME OFF</b>					

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

**7.2.3 SPIRE Peak-up Mode Test – Redundant**

**7.2.3.1 Switch ON SPIRE REDUNDANT**

The following will switch ON and configure SPIRE Redundant instrument in REDY (Standby) mode. HKTM packets will be generated on APIDs 1281 dec and 1283 decimal (these can be observed using TMPH with corresponding filter – note however a limited number of TMPHs should be running at one time).

During power on of SPIRE a number of soft/hard OOLs are reported due to the sequential switch on of the units. This is expected and will clear when SPIRE is in REDY mode. When in REDY mode one parameter remains OOL (soft) namely SMD2V505 this is also expected.

Step-No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
1.	On HPCCS start Packet History displays for the following APIDs:1281,1283	OK				
2.	From the HPCCS test conductor console start the test script to power on SPIRE Redundant: <b>S102999SCVT033_ASDCFTSPIR_PWR_ON_R</b>	OK		AND: ZAD07999, ZAD14999 MIM: LCL_HERSCHEL		

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Step-No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
3.	<p>On HPCCS when prompted:</p> <p>"SPIRE Switch ON for Cold FT related tests in Hel/Hell conditions only - Select NO to abort TS if not correct"</p> <p><b>Select YES</b></p>	YES				
	<p>If <b>YES</b> is selected the test script will go on to automatically power on all SPIRE warm units, force boot the DPU ASW and configure the instrument to Standby mode. Reply to prompts as indicated below.</p>					
4.	<p>On HPCCS when prompted:</p> <p>"Check Telemetry Updating Correctly and OBT is Consistent with CDMU - OK to continue"</p> <p><b>Select OK</b></p>	OK		AND: SA_1_559		
5.	<p>If I-EGSE connected when prompted on HPCCS, perform check requested then select <b>OK</b>:</p> <p>"Check IEGSE Time Consistent - OK to continue when RAL confirm"</p>	OK				

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Step-No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
6.	On HPCCS when prompted: "Check Telemetry No Longer Updating - OK to continue"  Check that parameters:  <div style="text-align: right; margin-right: 20px;">                         THSK Not refreshing                          TM2N Not incrementing                     </div> Select OK to continue					
7.	On HPCCS when prompted: "Check Telemetry Updating Correctly - OK to continue"  Check that parameters:  <div style="text-align: right; margin-right: 20px;">                         THSK Refreshing @ 1Hz                          TM2N Incrementing by 1 @ 1Hz                     </div> Select OK to continue			<b>AND: SA_1_559</b>		

<b>Enter Date/Time:</b>			<b>Sign Off:</b>	
-------------------------	--	--	------------------	--

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Step-No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
8.	On HPCCS when all autonomous actions have been completed by the power on script <b>S102999SCVT033_ASDCFTSPIR_PWR_ON_R</b> it will prompt: "Set Bus Profile Back to Original Setting?" Select NO	NO				
9.	At the prompt: "Bus Profile left unchanged" Select OK to continue	OK				
10.	Verify HK TM packets are being received on APIDs 1281 & 1283	OK				
	<b>SPIRE DPU &amp; DRCU Redundant powered</b>					

<b>Enter Date/Time:</b>			<b>Sign Off:</b>	
-------------------------	--	--	------------------	--

Enter Start Date Time:			
------------------------	--	--	--

7.2.3.2 Peak-up Mode Procedure – Redundant

Step	Action(s)	Description	Comments
1	Execute TCL script SPIRE-IST-PeakUpTest-<n>.tcl  Where n = 1 to 11.	If n=1 Wait for ~3 minutes, otherwise wait for 10 seconds (see table in section 2.2)	
2	Check event packet is issued with correct contents on the CCS  See <b>Appendix A</b> for an example of a peak-up event packet dump	Event ID = 0x0504 SID = 0x5101 Instrument ID = 2 Yangle – see section 2.2 Zangle – see section 2.2  The I-EGSE staff will also check the contents of peak-up event packet.	
3	Check CDMS issues correct commands to AOCS	Post test check by AOCS experts to see if the command to move is in accordance with the peak-up event packet.	
4	Wait for the I-EGSE staff go-ahead before executing next step		

Enter Date/Time:			Sign Off:
------------------	--	--	-----------

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

7.2.3.3 Switch OFF SPIRE REDUNDANT

Step- No	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
1.	From the HPCCS test conductor console start the test script to power OFF SPIRE REDUNDANT:  <b>S102999SCVT034_ASDCFTSPIR_PWR_OFF_R</b>	OK				
2.	On HPCCS when prompted:  "SPIRE Switch OFF for CFT related tests in Hel/Hell conditions only - Select NO to abort TS if not correct"  <b>Select YES</b>	YES				
	If <b>YES</b> is selected the test script will go on to automatically power off all SPIRE warm units.					

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------

Enter Start Date Time:			
------------------------	--	--	--

Step- No.	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
	<p>Note: During Switch OFF of SPIRE, the following (5,1) and (5,4) event messages on APID 1281 may be expected and do not indicate a problem:</p> <p style="margin-left: 40px;">c) EVID 1313 No_MCU_Response_Error d) EVID 21773 ALARM_LSMCU_DEAD</p> <p><b>However, be aware that if FDIR is enabled for SPIRE in the CDMU then this may trigger an OBCP</b></p>					
3.	<p>On HPCCS when prompted: "Check Telemetry No Longer Updating - OK to continue"</p> <p>Check that parameters:</p> <p style="margin-left: 40px;">THSK Not refreshing TM2N Not incrementing</p>			<b>AND: SA_1_559</b>		
4.	Select OK to continue	OK				

Enter Date/Time:			Sign Off:
------------------	--	--	-----------



<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Step-No	Test-Step-Description	Nominal Value	Actual Value	Remarks	P	N
5.	On HPCCS when all autonomous actions have been completed by the power on script <b>S102999SCVT034_ASDCFTSPIR_PWR_OFF_R</b> it will prompt: "Bus profile left as SPIRE PRIME, change manually after if required - OK to continue"					
6.	Select OK to continue	OK				
7.	On HPCCS stop Packet History displays for the following APIDs:1281,1283	OK				
	<b>SPIRE REDUNDANT OFF</b>					

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

**7.2.4 Satellite & EGSE Switch Off After Peak-up Mode Test**

Step- No.	Test-Step-Description	Nominal Value	Tolerance	Actual Value		P	N
<b>Satellite &amp; EGSE Switch Off</b>							
	Initial Conditions: Nominal & Redundant SPIRE warm units OFF						
1	On HPCSS terminate <b>ALL_SubscribeParams.tcl</b> test script.	OK					
2	From HPCSS Test Conductor console issue command to disconnect from SPIRE I-EGSE  <b>disconnect HSPIREEGSE</b>	OK					
3	Confirm from HPCSS and SPIRE I-EGSE that the disconnection was successful	YZS29940= DISCONNECTED			<b>AND SYS_PARS</b>		
4	If no longer required switch OFF I-EGSE i.a.w. AD 5	OK					
5	Switch off Satellite/SVM, HPCSS and SCOE's i.a.w. procedure AD11 Section 7.4 continuing from step 42, then return to lead procedure AD10 section 7.4 to complete the switch-off	OK					
6	Confirm both Satellite and EGSE powered down	OK					
	End Conditions: Satellite and EGSE OFF						
<b>END OF SPIRE Peak-up Mode TEST</b>							

<b>Enter Date/Time:</b>			<b>Sign Off:</b>	
-------------------------	--	--	------------------	--

Enter Start Date Time:			
------------------------	--	--	--

**7.2.5 SPIRE SAFE Switch Off**

The following procedure describes the necessary steps to safely switch off SPIRE when directed by RAL personnel if an anomaly should occur.

<b>Version</b>	2.4
<b>Date</b>	6 <sup>th</sup> December 2007
<b>Purpose</b>	To switch OFF the SPIRE instrument if an anomaly should occur
<b>Initial configuration</b>	SPIRE can be in ANY configuration as specified in the test sequence in section 4.1
<b>Final configuration</b>	SPIRE is OFF
<b>Preconditions</b>	<ul style="list-style-type: none"> <li>• SPIRE FM DPU is electrically integrated with the Herschel Satellite</li> <li>• SPIRE MIB is imported in the CCS database.</li> <li>• CCS is up and running</li> <li>• FUNCTIONAL TEST PARAMETERS display is selected on the CCS</li> </ul>
<b>Duration</b>	~5-8 minutes
<b>Pass/Fail Criteria</b>	SPIRE is OFF. All instrument subsystems are completely powered OFF.

Enter Date/Time:			Sign Off:	
------------------	--	--	-----------	--

<b>Enter Start Date Time:</b>			
-------------------------------	--	--	--

Step	Description	Parameter - Unit	Expected value before/after	Actual value before/after
1.	Execute Procedures: <ul style="list-style-type: none"> <li>▪ SPIRE-IST-COLD-PDET-OFF-P/R</li>   <li>▪ SPIRE-IST-COLD-BSM-OFF-P/R</li> </ul>	PLIABITSAT PSWJFETSTAT PMLWJFETSTAT  CHOPSENSPWR JIGGSENSPWR	- / 0 - / 0 - / 0  - / 0 - / 0	
2.	Execute Procedures: <ul style="list-style-type: none"> <li>▪ SPIRE-IST-COLD-SDET-OFF-P/R</li>   <li>▪ SPIRE-IST-COLD-SMEC-OFF-P/R</li> </ul>	SLIABITSAT SPECJFETSTAT  SMECENCPWR SMECLVDPWR	- / 0 - / 0  - / 0 - / 0	
3.	Execute Procedures: <ul style="list-style-type: none"> <li>▪ SPIRE-IST-COLD-MCU-OFF-P/R</li>   <li>▪ SPIRE-IST-COLD-SCU-OFF-P/R</li> </ul>	MCUBITSTAT   SCUTEMPSTAT SUBKSTAT	- / 0   - / 0 - / 0	

<b>Enter Date/Time:</b>			<b>Sign Off:</b>
-------------------------	--	--	------------------



## 8 Summary Sheets

**8.1 Procedure Variation Summary**

	Test Change	Curr. No.:	
		Date	
		Page	of
Test designation	Test Procedure	Issue	Rev.
Test step changed	Reason for Change		
Prepared by:	Resp. Test Leader	Project Engineer	
PA/QA	Prime	Customer	

Table 8.1-1: Procedure Variation Sheet

**8.2 Non Conformance Report (NCR) Summary**

NCR - No.	NCR - Title	Date	Open Closed	PA sig.

Table 8.2-1: Non-Conformance Record Sheet

8.3 Sign-off Sheet

	Date	Signature
Test Director		
Operator		
PA Responsible		
ESA Representative		



## APPENDIX 1

### Actual SCOE cable connection (to be confirmed by AIT)

SCOE CABLES CONNECTION to HERSCHEL S/C					
SKIN-01	PWR Panel (PCDU)				
	Connector Function	Skin Connector	S/C unit	SCOE CABLE	Flight Connector
	BS Nom Power	SK01BJ09	PCDU	BS SCOE Cable Plugged	
	BS Red Power	SK01BJ10	PCDU	BS SCOE Cable Plugged	
	BDR1 AIT	SK01BJ11	PCDU	LPS SCOE Cable Plugged	
	BDR2 AIT	SK01BJ12	PCDU	LPS SCOE Cable Plugged	
	SA Nom Power	SK01AJ01	PCDU	POWER SCOE Cable Plugged	
	SA Nom Power	SK01AJ02	PCDU	POWER SCOE Cable Plugged	
	SA Nom Power	SK01AJ03	PCDU	POWER SCOE Cable Plugged	
	SA Nom Power	SK01AJ04	Battery	EMC Dust Cap	
	SA Red Power	SK01AJ05	PCDU	POWER SCOE Cable Plugged	
	SA Red Power	SK01AJ06	PCDU	POWER SCOE Cable Plugged	
	SA Red Power	SK01AJ07	PCDU	POWER SCOE Cable Plugged	
SKIN-02	PWR Panel (ACC, CDMU, RCS, 1553 & Thruster)				
	Connector Function	Skin Connector	S/C unit	SCOE CABLE	Flight Connector
	DMS 1553 Bus_A	J01	CDMU	Bus Monitor Cable Plugged	
	DMS 1553 Bus_B	J02	CDMU	Bus Monitor Cable Plugged	
	ACMS 1553 Bus_A	J03	ACC	ACMS SCOE Cable Plugged	
	ACMS 1553 Bus_B	J04	ACC	ACMS SCOE Cable Plugged	
SKIN-02	LV1/FCV 20N CMD S/A M	J05	ACC/RCS	ACMS SCOE Cable Plugged	

SKIN-02	LV2/FCV 20N CMD S/A R	J06	ACC/RCS	ACMS SCOE Cable Plugged	
SKIN-02	RCS Press/Tank Temp/PT Pwr	J07	ACC/PT&TH	ACMS SCOE Cable Plugged	
SKIN-02	Thruster Temp M/LV1 Sts	J08	ACC/RCS	ACMS SCOE Cable Plugged	
SKIN-02	CDMU and ACC EEPROM reprogramming input	J09	ACC/CDMU		Flight Plug SK02P09 Plugged
SKIN-02	CDMU and ACC EEPROM reprogramming input	J10	ACC/CDMU		Flight Plug SK02P10 Plugged
SKIN-02	Thruster Temp R/LV2 Sts	J11	ACC/RCS	ACMS SCOE Cable Plugged	
SKIN-02	Thruster C/B Heaters M	J12	ACC/CBH	ACMS SCOE Cable Plugged	
SKIN-02	Thruster C/B Heaters R	J13	ACC/CBH	ACMS SCOE Cable Plugged	
SKIN-02	Str1/2 On/Off Cmd M/Str1 Sts	J14	ACC/STR-1		ACMS Flight Plug SK02P14 Plugged
SKIN-02	Str1/2 On/Off Cmd R/Str2 Sts	J15	ACC/STR-2		ACMS Flight Plug SK02P15 Plugged
SKIN-02	Gyro A On/Off Cmd	J16	ACC/GYRO-E1		ACMS Flight Plug SK02P16 Plugged
SKIN-02	Gyro B On/Off Cmd	J17	ACC/GYRO-E2		ACMS Flight Plug SK02P17 Plugged
SKIN-03	<b>TTC Panel</b>				
	Connector Function	Skin Connector	S/C unit	SCOE CABLE	Flight Connector
SKIN-03	Test point TC + protection jumper EPC1	SK03J01	XPND1/EPC1		Plastic cap
SKIN-03	Test point TC + protection jumper EPC2	SK03J02	XPND2/EPC2		Plastic cap
	<b>RF LINK</b>				
	Connector Function	Skin Connector	S/C unit	SCOE CABLE	Flight Connector
	RF link for antenna LGA1	N/A	LGA1	RF SCOE LGA1 Plugged	LGA1 Anechoic Cap
	RF link for antenna LGA2	N/A	LGA2	RF SCOE LGA2 Plugged	LGA2 Anechoic Cap
	RF link for antenna MGA	N/A	MGA	RF SCOE MGA Plugged	MGA Anechoic Cap
SKIN-04	<b>ACMS Panel (RWE)</b>				
	Connector Function	Skin Connector	S/C unit	SCOE CABLE	Flight Connector
SKIN-04	RWL1 Sgn	J01	ACC/RWL-1		ACMS Flight Plug SK04P01 Plugged
SKIN-04	RWL2 Sgn	J02	ACC/RWL-2		ACMS Flight Plug SK04P02 Plugged

SKIN-04	RWL3 Sgn	J03	ACC/RWL-3		ACMS Flight Plug SK04P03 Plugged
SKIN-04	RWL4 Sgn	J04	ACC/RWL-4		ACMS Flight Plug SK04P04 Plugged
SKIN-05	GYR/QRS Panel				
	Connector Function	Skin Connector	S/C unit	SCOE CABLE	Flight Connector
SKIN-05	CRS1 AOCS Sgn	J01	CRS-1/ACC		ACMS Flight Plug
SKIN-05	CRS2 AOCS Sgn	J02	CRS-2/ACC		ACMS Flight Plug
SKIN-05	GYRO RS422 / Test	J03	GYRO	ACMS SCOE Cable Plugged	
SKIN-05	CRS 1/2 Stimuli	J04	CRS-1,2	ACMS SCOE Cable Plugged	
SKIN-05	AAD Sgn M	J05	AAD/ACC	ACMS SCOE Cable Plugged	
SKIN-05	SAS1/2 Sgn M	J06	SAS/ACC	ACMS SCOE Cable Plugged	
SKIN-05	SAS1/2 Sgn R	J07	SAS/ACC	ACMS SCOE Cable Plugged	
SKIN-05	AAD Sgn R	J08	AAD/ACC	ACMS SCOE Cable Plugged	
SKIN-06	STR Panel				
	Connector Function	Skin Connector	S/C unit	SCOE CABLE	Flight Connector
SKIN-06	STR1 Stimuli	J01	STR1	ACMS SCOE Cable Plugged	
SKIN-06	STR2 Stimuli	J02	STR2	ACMS SCOE Cable Plugged	
	UMBILICAL				
	Connector Function	Connector	S/C unit	SCOE CABLE	
	Power/Data	HU1J01	SYSTEM	SCOE's cable Plugged	
	Power/Data	HU2J01	SYSTEM	SCOE's cable Plugged	



END OF DOCUMENT

Name	Dep./Comp.	Name	Dep./Comp.
Baldock Richard	FAE12	Schink Dietmar	AED321
Barlage Bernhard	AED13	Schmidt Thomas	AED15
Bayer Thomas	ASA42	Schweickert Gunn	ASG23
Brune Holger	ASA45	Sonn Nico	ASG51
Chen Bing	HE Space	Steininger Eric	AED321
Davis William	Captec	Stritter Rene	AED11
Edelhoff Dirk	AED21	Suess Rudi	OTN/ASA44
Fehringer Alexander	ASG15	Theunissen Martijn	DSSA
Fricke Wolfgang Dr.	AED 65	Vascotto Riccardo	HE Space
Geiger Hermann	ASA42	Wagner Klaus	ASG23
Grasl Andreas	OTN/ASA44	Wietbrock Walter	AET12
Grasshoff Brigitte	AET12	Wöhler Hans	ASG23
Hamer Simon	Terma	Wössner Ulrich	ASE252
Hanka, Erhard	FI522	Zumstein Armin	AED15
Hendrikse Jeffrey	HE Space		
Hendry David	Terma		
Hengstler Reinhold	ASA42		
Hinger Jürgen	ASG23		
Hohn Rüdiger	AED65		
Hopfgarten Michael	AET32		
Huber Johann	ASA42		
Hund Walter	ASE252		
Idler Siegmund	AED312	ESA/ESTEC	ESA
Ivány von András	FAE12	Thales Alenia Space Cannes	TAS-F
Jahn Gerd Dr.	ASG23	Thales Alenia Space Torino	TAS-I
Jolk Matthias	AET1		
Klenke Uwe	ASG72		
Kölle Markus	ASA43	<b>Instruments:</b>	
König Werner	AET32	MPE (PACS)	MPE
Koppe Axel	AED312	RAL (SPIRE)	RAL
Kroeker Jürgen	AED65	SRON (HIFI)	SRON
La Gioia Valentina	Terma		
Lang Jürgen	ASE252		
Langenstein Rolf	AED15	<b>Subcontractors:</b>	
Langfermann Michael	ASA41	Austrian Aerospace	AAE
Leitermann Stefan	AET12	Austrian Aerospace	AAEM
Liberatore Danilo	Rhea	BOC Edwards	BOCE
Martin Olivier	Altec	Dutch Space Solar Arrays	DSSA
Maukisch Jan	ASA43	EADS Astrium Sub-Subsyst. & Equipment	ASSE
Much Christoph	ASA43	EADS CASA Espacio	CASA
Müller Martin	ASA43	EADS CASA Espacio	ECAS
Pietroboni Karin	AED65	European Test Services	ETS
Reichle Konrad	ASA42	Patria New Technologies Oy	PANT
Runge Axel	OTN/ASA44	SENER Ingenieria SA	SEN
Saal Christoph	External	Thales Alenia Space, Antwerp	TAS-ETCA