

Telescope decontamination during Telescope cool down  
File: H\_COP\_SYS\_DEC2.xls  
Author: E. Picallo



## Procedure Summary

### Objectives

This procedure describes the steps needed to perform the Telescope decontamination during Telescope cool down.

The procedure must be initiated when the telescope temperature is below 200K to avoid FDIR triggering and above 170K order to start decontamination in steady-state phase with temperature thresholds set to [170K , 171K].

It is proposed to start the procedure execution at the time when the telescope reaches the 175K reference point. This might have to be advanced even further.

Three heater lines out of seven on M1 and both heater lines on M2 are turned ON.

Note: According to the latest H-CoP Timeline, the decontamination shall stabilize the telescope at 170 K starting on day H0+4.25 for a total of 25 days.

### Summary of Constraints

The decontamination must be started in steady-state phase to ensure that the decontamination power need is about 20W average and ~360W peak. Thus, the constraints on ACMS mode to be Sun pointing and no RWL commanding are not applicable (i.e. ACMS can be set in SCM and RWLs run-in can be activated).

It is proposed to use only 3 lines on M1 (lines 4, 6 and 7) and both heater lines on M2 in order to have a peak consumption of ~360W.

The Cryostat cover shall be closed to protect FPU.

The decontamination shall not start earlier than 48h after the maximum Helium temperature has been reached.

TCS Dgn. Packet shall be enabled.

The 10 new pair of MOT/EAT shall be defined according to procedure H\_COP\_SYS\_DECD (Decontamination MOT and EAT entries definition) since they are not part of the default CDMU ASW 3.10 on-board MOT/EAT tables

### Spacecraft Configuration

#### Start of Procedure

Telescope cooldown to <200K and > 175K  
Decontamination nominal HPS 1 and 6 shall be ON  
Decontamination heating function stopped  
Battery 99% fully charged  
Cryostat cover closed  
Instruments OFF

#### End of Procedure


Telescope temperature stabilize at [170K 171K]  
Decontamination nominal HPS 1 and 6 shall be ON  
Decontamination redundant HPS 10, 15 and 17 shall be ON  
Decontamination heating function running  
Battery 99% fully charged  
Cryostat cover closed  
Instruments OFF



Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



### Procedure Flowchart Overview



Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
<b>Beginning of Procedure</b>				
<p>TC Seq. Name : HCYDEC2 (Decont.during COP)            Telescope decontamination during Telescope cool down</p> <p>TimeTag Type: N            Sub Schedule ID:</p> <p style="text-align: center;">□</p>				
1		Verify Telescope cooldown to <200K and >175K		Next Step: 2
		<p><b>Initiate the procedure after the telescope temperature is below 200K to avoid FDIR triggering and before the telescope temperature has dropped down to 175 K, for two reasons:</b></p> <p><b>i) the energy request on the battery is lower,</b>  <b>ii) there is no need to have intermediate steps (to maintain the temperature gradients lower than 50K) to heat up from cold steady state to 170 K.</b></p>		
		<b>Telescope shall reach a temperature of 175 K on day H0+4.25 days</b>		
1.1		Verify M1 Thermistors		□
		<b>Nominal M1 thermistors used for temperature determination (used to calculate the temperature median algorithm) are: TH A (T331), TH A'' (T332), TH C (T335).</b>		
		Verify on telescope; M1 THA ; T21-5 (A) PT1000_T331                      KD253302	> 175.0 K < 200.0 K	AND=ZAZ9J999
		Verify on telescope; M1 THA'' ; T16-5 (B) PT1000_T332                      KD248303	> 175.0 K < 200.0 K	AND=ZAZ9J999
		Verify on telescope; M1 THC ; T23-5 (A) PT1000_T335                      KD255302	> 175.0 K < 200.0 K	AND=ZAZ9J999
1.2		Verify M2 Thermistors		□
		<b>Nominal M2 thermistors used for temperature determination (used to calculate the temperature median algorithm) are: TH X (T339), TH Y (T341), TH Z (T342).</b>		
		Verify on telescope; M2 THX ; T25-5 (A) PT1000_T339                      KD257302	> 175.0 K < 200.0 K	AND=ZAZ9J999





Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify Telemetry TM_VBATT_BDR_1 WMT02565	>= 25.32 V	AND=ZAZ9J999
		Verify Telemetry TM_VBATT_BDR_2 WMT03565	>= 25.32 V	AND=ZAZ9J999
7		Check status of nominal HPS involved in decontamination of M1 and M2		Next Step: 8
		<b>There are 7 heaters lines for M1 (4N+3R):</b> <b>M1 heater line 3 (HPS 02 HCS 1 N)</b> <b>M1 heater line 4 (HPS 17 HCS 1 R) *</b>  <b>M1 heater line 5 (HPS 04 HCS 1 N)</b> <b>M1 heater line 6 (HPS 15 HCS 1 R) *</b>  <b>M1 heater line 7 (HPS 06 HCS 1 N) *</b> <b>M1 heater line 8 (HPS 09 HCS 1 N)</b> <b>M1 heater line 9 (HPS 18 HCS 1 R)</b>		
		<b>There are 2 heaters lines for M2 (1N+1R):</b> <b>M2 heater line 1 (HPS 01 HCS 1 N) *</b> <b>M2 heater line 2 (HPS 10 HCS 1 R) *</b>		
		* It is proposed to use only 3 lines on M1 (lines 4, 6 and 7) both heater lines on M2 in order to have peak consumption of ~360W.		
7.1		Check status of nominal HPS involved in decontamination of M1 & M2 (HPS#6 for M1 and HPS#1 for M2)		<input type="checkbox"/>
		Verify Telemetry GRP6_HPS_STS WMT2G565	= ON	AND=ZAZ9J999
		Verify Telemetry GRP1_HPS_STS WMT2G565	= ON	AND=ZAZ9J999
8		Switch ON redundant HPS involved in decontamination of M1 & M2 (HPS#15 & 17 for M1 and HPS#10 for M2 )		Next Step: 9
8.1		Switch ON HPS15		<input type="checkbox"/>
		Execute Telecommand PcdSwOnHps15  TC Control Flags : GBM IL DSE --Y -- --  Subsch. ID : 10 Det. descr. : PCDU:TC(8,4,112,5) switch On HPS 15	DCC15170	

Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify Telemetry GRP15_HPS_STS WM82H565	= ON	AND=ZAZ9J999
8.2		Switch ON HPS17		<input type="checkbox"/>
		Execute Telecommand PcduSwOnHps17 TC Control Flags : GBM IL DSE --Y -- -- Subsch. ID : 10 Det. descr. : PCDU:TC(8,4,112,5) switch On HPS 17	DCC17170	
		Verify Telemetry GRP17_HPS_STS WM92H565	= ON	AND=ZAZ9J999
8.3		Switch ON HPS10		<input type="checkbox"/>
		Execute Telecommand PcduSwOnHps10 TC Control Flags : GBM IL DSE --Y -- -- Subsch. ID : 10 Det. descr. : PCDU:TC(8,4,112,5) switch On HPS 10	DCC10170	
		Verify Telemetry GRP10_HPS_STS WM62G565	= ON	AND=ZAZ9J999
9		Set heater mask on M1 & M2 and decontamination thresholds to [-103.15 , -102.15] °C = [170 , 171] K		Next Step: 10
		Initiate the telescope decontamination function during the cool down phase, with the following parameters: M1 mask ON: lines 4, 6 and 7 M1 mask OFF: lines 3, 5, 8 and 9 M2 mask ON: lines 1 and 2 M2 mask OFF: none M1 lower threshold = 170K = -103.15°C M1 upper threshold = 171K = -102.15°C M2 lower threshold = 170K = -103.15°C M2 upper threshold = 171K = -102.15°C		




Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Execute Telecommand  Decont - Heater mask  Command Parameter(s) : Decont - M1 heater 7           ZHB17999       NOTACTIVE (Def) Decont - M1 heater 6           ZHB16999       NOTACTIVE Decont - M1 heater 5           ZHB15999       ACTIVE (Def) Decont - M1 heater 4           ZHB14999       ACTIVE (Def) Decont - M1 heater 3           ZHB13999       NOTACTIVE (Def) Decont - M1 heater 2           ZHB12999       ACTIVE (Def) Decont - M1 heater 1           ZHB11999       NOTACTIVE Decont - M2 heater 2           ZHB22999       ACTIVE (Def) Decont - M2 heater 1           ZHB21999       ACTIVE (Def)  TC Control Flags :  GBM IL DSE --Y -- ---  Subsch. ID : 10 Det. descr. : TC(8,4,113,1) to update the M1 and M2 active heaters	ZCB03999	
		Execute Telecommand  Decont - Tresholds  Command Parameter(s) : Decont - M1 - TMIN            ZHB06999       -103.15 degC Decont - M1 - TMAX            ZHB07999       -102.15 degC Decont - M2 - TMIN            ZHB08999       -103.15 degC Decont - M2 - TMAX            ZHB09999       -102.15 degC Decont - Cont Check           ZHB10999       0.5 degC (Def)  TC Control Flags :  GBM IL DSE --Y -- ---  Subsch. ID : 10 Det. descr. : TC(8,4,113,1) to update the tresholds - TMIN - TMAX - Cont check	ZCB04999	
9.1		Report decontamination heating parameters		<input type="checkbox"/>
		Execute Procedure: H_LEO_SYS_DECS Decontamination Heating Status Report		
10		Start decontamination (in steady-state )		Next Step: 11
10.1		Acquire the status of the function		<input type="checkbox"/>
		Default status of the function is "Stopped"		
		Verify Telemetry  DhSts            DEG17170       = Stopped		AND=ZAZ9J999

Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch																																			
10.2		Send TC(8,1,113) to start the function		<input type="checkbox"/>																																			
		<b>Start Decontamination Heating telecommand is used for switching on the function.</b>																																					
		Execute Telecommand <div style="text-align: right;"><b>StartDecontHeat</b></div> TC Control Flags : <div style="text-align: right;"><b>GBM IL DSE</b></div> <div style="text-align: right;"><b>--Y -- ---</b></div> Subsch. ID : 10 Det. descr. : Start Decontamination Heating TC(8,1,113)	DC13M170																																				
10.3		Verify that the function has been started		<input type="checkbox"/>																																			
		Verify Telemetry <div style="text-align: right;"><b>DhSts</b></div> <div style="text-align: right;"><b>DEG17170</b></div> <div style="text-align: right;"><b>= Running</b></div>		AND=ZAZ9J999																																			
11		Enable Decontamination MOT & EAT entries		Next Step: 12																																			
11.1		Define (if not already performed) the 10 new pair of MOT/EAT Decontamination entries		<input type="checkbox"/>																																			
		Execute Procedure: <b>H_COP_SYS_DECD</b> <b>Decontamination MOT and EAT entries definition</b>																																					
11.2		Enable Decontamination MOT entries		<input type="checkbox"/>																																			
		<b>There are 10 entries defined in the MOT related to decontamination:</b> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Parameter ID</th> <th>Monitoring ID</th> <th>Event ID</th> </tr> </thead> <tbody> <tr><td>M1 median temp (2048)</td><td>216</td><td>40976</td></tr> <tr><td>M1 median temp (2048)</td><td>217</td><td>40977</td></tr> <tr><td>M1 median temp (2048)</td><td>218</td><td>40978</td></tr> <tr><td>M1 median temp (2048)</td><td>219</td><td>40979</td></tr> <tr><td>M1 median temp (2048)</td><td>220</td><td>40980</td></tr> <tr><td colspan="3"> </td></tr> <tr><td>M2 median temp (2049)</td><td>224</td><td>40984</td></tr> <tr><td>M2 median temp (2049)</td><td>225</td><td>40985</td></tr> <tr><td>M2 median temp (2049)</td><td>226</td><td>40986</td></tr> <tr><td>M2 median temp (2049)</td><td>227</td><td>40987</td></tr> <tr><td>M2 median temp (2049)</td><td>228</td><td>40988</td></tr> </tbody> </table> <b>These entries are disabled by default, so they must be enabled after starting the decontamination</b>	Parameter ID	Monitoring ID	Event ID	M1 median temp (2048)	216	40976	M1 median temp (2048)	217	40977	M1 median temp (2048)	218	40978	M1 median temp (2048)	219	40979	M1 median temp (2048)	220	40980				M2 median temp (2049)	224	40984	M2 median temp (2049)	225	40985	M2 median temp (2049)	226	40986	M2 median temp (2049)	227	40987	M2 median temp (2049)	228	40988	
Parameter ID	Monitoring ID	Event ID																																					
M1 median temp (2048)	216	40976																																					
M1 median temp (2048)	217	40977																																					
M1 median temp (2048)	218	40978																																					
M1 median temp (2048)	219	40979																																					
M1 median temp (2048)	220	40980																																					
M2 median temp (2049)	224	40984																																					
M2 median temp (2049)	225	40985																																					
M2 median temp (2049)	226	40986																																					
M2 median temp (2049)	227	40987																																					
M2 median temp (2049)	228	40988																																					



Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch																																							
		<p>There are 10 entries defined in the EAT related to decontamination:</p> <table border="1"> <thead> <tr> <th>APID</th> <th>Event ID</th> <th>Action TC</th> </tr> </thead> <tbody> <tr> <td colspan="3"><b>For M1:</b></td> </tr> <tr> <td>16(CDMS)</td> <td>40976</td> <td>Switch OFF HPS1 TC(8,4,112,3)</td> </tr> <tr> <td>16(CDMS)</td> <td>40977</td> <td>Switch OFF HPS6 TC(8,4,112,3)</td> </tr> <tr> <td>16(CDMS)</td> <td>40978</td> <td>Switch OFF HPS10 TC(8,4,112,3)</td> </tr> <tr> <td>16(CDMS)</td> <td>40979</td> <td>Switch OFF HPS15 TC(8,4,112,3)</td> </tr> <tr> <td>16(CDMS)</td> <td>40980</td> <td>Switch OFF HPS17 TC(8,4,112,3)</td> </tr> <tr> <td colspan="3"><b>For M2:</b></td> </tr> <tr> <td>16(CDMS)</td> <td>40984</td> <td>Switch OFF HPS1 TC(8,4,112,3)</td> </tr> <tr> <td>16(CDMS)</td> <td>40985</td> <td>Switch OFF HPS6 TC(8,4,112,3)</td> </tr> <tr> <td>16(CDMS)</td> <td>40986</td> <td>Switch OFF HPS10 TC(8,4,112,3)</td> </tr> <tr> <td>16(CDMS)</td> <td>40987</td> <td>Switch OFF HPS15 TC(8,4,112,3)</td> </tr> <tr> <td>16(CDMS)</td> <td>40988</td> <td>Switch OFF HPS17 TC(8,4,112,3)</td> </tr> </tbody> </table> <p>These entries are disabled by default, so they must be enabled after starting the decontamination.</p>	APID	Event ID	Action TC	<b>For M1:</b>			16(CDMS)	40976	Switch OFF HPS1 TC(8,4,112,3)	16(CDMS)	40977	Switch OFF HPS6 TC(8,4,112,3)	16(CDMS)	40978	Switch OFF HPS10 TC(8,4,112,3)	16(CDMS)	40979	Switch OFF HPS15 TC(8,4,112,3)	16(CDMS)	40980	Switch OFF HPS17 TC(8,4,112,3)	<b>For M2:</b>			16(CDMS)	40984	Switch OFF HPS1 TC(8,4,112,3)	16(CDMS)	40985	Switch OFF HPS6 TC(8,4,112,3)	16(CDMS)	40986	Switch OFF HPS10 TC(8,4,112,3)	16(CDMS)	40987	Switch OFF HPS15 TC(8,4,112,3)	16(CDMS)	40988	Switch OFF HPS17 TC(8,4,112,3)		
APID	Event ID	Action TC																																									
<b>For M1:</b>																																											
16(CDMS)	40976	Switch OFF HPS1 TC(8,4,112,3)																																									
16(CDMS)	40977	Switch OFF HPS6 TC(8,4,112,3)																																									
16(CDMS)	40978	Switch OFF HPS10 TC(8,4,112,3)																																									
16(CDMS)	40979	Switch OFF HPS15 TC(8,4,112,3)																																									
16(CDMS)	40980	Switch OFF HPS17 TC(8,4,112,3)																																									
<b>For M2:</b>																																											
16(CDMS)	40984	Switch OFF HPS1 TC(8,4,112,3)																																									
16(CDMS)	40985	Switch OFF HPS6 TC(8,4,112,3)																																									
16(CDMS)	40986	Switch OFF HPS10 TC(8,4,112,3)																																									
16(CDMS)	40987	Switch OFF HPS15 TC(8,4,112,3)																																									
16(CDMS)	40988	Switch OFF HPS17 TC(8,4,112,3)																																									
		<p>Execute Telecommand</p> <pre> EnableActions DCT84170  Command Parameter(s) :   N_Repetition          DH041170    10 &lt;dec&gt;   APID_for_EAT_TC      DH236170    CDMS (Def)   EventId              DH146170    40976 &lt;dec&gt;   APID_for_EAT_TC      DH236170    CDMS (Def)   EventId              DH146170    40977 &lt;dec&gt;   APID_for_EAT_TC      DH236170    CDMS (Def)   EventId              DH146170    40978 &lt;dec&gt;   APID_for_EAT_TC      DH236170    CDMS (Def)   EventId              DH146170    40979 &lt;dec&gt;   APID_for_EAT_TC      DH236170    CDMS (Def)   EventId              DH146170    40980 &lt;dec&gt;    APID_for_EAT_TC      DH236170    CDMS (Def)   EventId              DH146170    40984 &lt;dec&gt;   APID_for_EAT_TC      DH236170    CDMS (Def)   EventId              DH146170    40985 &lt;dec&gt;   APID_for_EAT_TC      DH236170    CDMS (Def)   EventId              DH146170    40986 &lt;dec&gt;   APID_for_EAT_TC      DH236170    CDMS (Def)   EventId              DH146170    40987 &lt;dec&gt;   APID_for_EAT_TC      DH236170    CDMS (Def)   EventId              DH146170    40988 &lt;dec&gt;  TC Control Flags :   GBM IL DSE   --Y -- ---  Subsch. ID : 10  Det. descr. : TEMPLATE Enable Actions TC(19,4) </pre>																																									
11.5		Report EAT table to check the decontamination EAT entries		<input type="checkbox"/>																																							

Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Execute Telecommand  <b>ReptEvtActTable</b>  <i>TC Control Flags :</i>  Subsch. ID : 10 Det. descr. : TEMPLATE Report The contents of the event/action table TC(19,6)  <b>GBM IL DSE</b> <b>--Y -- --</b>	DCT86170	
12		Wait for temperature stabilisation		Next Step: 13
		<b>Wait until the median temperature on M1 and M2 oscillate between the selected thresholds: [-103.15 , -102.15] °C = [170 , 171] K</b>		
12.1		Verify M1 Thermistors		<input type="checkbox"/>
		Verify on telescope; M1 THA ; T21-5 (A) <b>PT1000_T331</b> <b>KD253302</b>	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
		Verify on telescope; M1 THA'' ; T16-5 (B) <b>PT1000_T332</b> <b>KD248303</b>	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
		Verify on telescope; M1 THC ; T23-5 (A) <b>PT1000_T335</b> <b>KD255302</b>	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
12.2		Verify M2 Thermistors		<input type="checkbox"/>
		Verify on telescope; M2 THX ; T25-5 (A) <b>PT1000_T339</b> <b>KD257302</b>	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
		Verify on telescope; M2 THY ; T26-5 (A) <b>PT1000_T341</b> <b>KD258302</b>	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
		Verify on telescope; M2 THZ ; T30-5 (B) <b>PT1000_T342</b> <b>KD262303</b>	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
12.3		Verify median temperatures on M1 & M2		<input type="checkbox"/>
		Verify M1 median temperature Telemetry <b>DhM1Temp</b> <b>DE800171</b>	<= -102.15 <dec> >= -103.15 <dec>	AND=ZAZ9J999
		Verify M2 median temperature Telemetry <b>DhM2Temp</b> <b>DE801171</b>	<= -102.15 <dec> >= -103.15 <dec>	AND=ZAZ9J999

Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
12.4		Verify reception of decontamination packets		<input type="checkbox"/>
		<b>Verify reception of TM packets:</b> TM(5,1,113,1) -> generated when M1 Heating is switch ON TM(5,1,113,2) -> generated when M1 Heating is switch OFF TM(5,1,113,3) -> generated when M2 Heating is switch ON TM(5,1,113,4) -> generated when M2 Heating is switch OFF		
		<b>Monitor the related HCS status, after reception of Event 5-1:</b> <b>M1 Decontamination Heating ON -&gt;</b> Decont_4_G17H1_S must be ON, Decont_6_G15H1_S must be ON, Decont_7_G6H1_S must be ON  <b>M1 Decontamination Heating OFF -&gt;</b> Decont_4_G17H1_S must be OFF, Decont_6_G15H1_S must be OFF, Decont_7_G6H1_S must be OFF  <b>M2 Decontamination Heating ON -&gt;</b> Decont_1_G1H1_S must be ON, Decont_2_G10H1_S must be ON  <b>M2 Decontamination Heating OFF -&gt;</b> Decont_1_G1H1_S must be OFF, Decont_2_G10H1_S must be OFF		
12.5		Verify TM(5,1) M1 Decontamination Heating ON		<input type="checkbox"/>
		Verify Packet Reception CdmuAsw Event 5-1 M1 Decontamination Heating ON Herschel Packet Details:	D_EvRp_109	
		APID: 16 Type: 5 Subtype: 1 PI1: 28929 PI2: 0		
		Verify Telemetry Decon4_G17H1_S WM91G565 = ON		GRD=ZGZ3F999
		Verify Telemetry Decon6_G15H1_S WM81G565 = ON		GRD=ZGZ3F999
		Verify Telemetry Decon7_G6H1_S WM41A565 = ON		GRD=ZGZ3F999
12.6		Verify TM(5,1) M1 Decontamination Heating OFF		<input type="checkbox"/>

Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify Packet Reception CdmuAsw Event 5-1 M1 Decontamination Heating OFF Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28930 PI2: 0	D_EvRp_187	
		Verify Telemetry Decon4_G17H1_S WM91G565	= OFF	GRD=ZGZ3F999
		Verify Telemetry Decon6_G15H1_S WM81G565	= OFF	GRD=ZGZ3F999
		Verify Telemetry Decon7_G6H1_S WM41A565	= OFF	GRD=ZGZ3F999
12.7		Verify TM(5,1) M2 Decontamination Heating ON		☐
		Verify Packet Reception CdmuAsw Event 5-1 M2 Decontamination Heating ON Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28931 PI2: 0	D_EvRp_188	
		Verify Telemetry Decon1_G1H1_S WM11A565	= ON	GRD=ZGZ3G999
		Verify Telemetry Decon2_G10H1_S WM61A565	= ON	GRD=ZGZ3G999
12.8		Verify TM(5,1) M2 Decontamination Heating OFF		☐
		Verify Packet Reception CdmuAsw Event 5-1 M2 Decontamination Heating OFF Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28932 PI2: 0	D_EvRp_189	
		Verify Telemetry Decon1_G1H1_S WM11A565	= OFF	GRD=ZGZ3G999
		Verify Telemetry Decon2_G10H1_S WM61A565	= OFF	GRD=ZGZ3G999
13		Continue monitoring		Next Step: 14

Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		<p><b>Keep monitoring M1/M2 thermistors and M1/M2 median temperatures on, which should remain in the range: [-103.15 , -102.15] °C = [170 , 171] K</b></p> <p><b>Expected duty cycle: M1 ~ 7% and M2 ~ 5%</b></p> <p><b>According to the H-COP timeline the decontamination function stabilize the telescope at [170 , 171] K starting on day H0+4 for a total of 25 days until H0+28.</b></p>		
13.1		Verify M1 Thermistors		<input type="checkbox"/>
		Verify on telescope; M1 THA ; T21-5 (A) PT1000_T331                      KD253302	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
		Verify on telescope; M1 THA'' ; T16-5 (B) PT1000_T332                      KD248303	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
		Verify on telescope; M1 THC ; T23-5 (A) PT1000_T335                      KD255302	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
13.2		Verify M2 Thermistors		<input type="checkbox"/>
		Verify on telescope; M2 THX ; T25-5 (A) PT1000_T339                      KD257302	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
		Verify on telescope; M2 THY ; T26-5 (A) PT1000_T341                      KD258302	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
		Verify on telescope; M2 THZ ; T30-5 (B) PT1000_T342                      KD262303	>= 170.0 K <= 171.0 K	AND=ZAZ9J999
13.3		Verify median temperatures on M1 & M2		<input type="checkbox"/>
		Verify M1 median temperature Telemetry DhM1Temp                      DE800171	<= -102.15 <dec> >= -103.15 <dec>	AND=ZAZ9J999
		Verify M2 median temperature Telemetry DhM2Temp                      DE801171	<= -102.15 <dec> >= -103.15 <dec>	AND=ZAZ9J999
13.4		Verify reception of decontamination packets		<input type="checkbox"/>




Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch										
		<b>Verify reception of TM packets:</b> TM(5,1,113,1) -> generated when M1 Heating is switch ON TM(5,1,113,2) -> generated when M1 Heating is switch OFF TM(5,1,113,3) -> generated when M2 Heating is switch ON TM(5,1,113,4) -> generated when M2 Heating is switch OFF												
		<b>Monitor the related HCS status, after reception of Event 5-1:</b> <b>M1 Decontamination Heating ON -&gt;</b> Decont_4_G17H1_S must be ON, Decont_6_G15H1_S must be ON, Decont_7_G6H1_S must be ON  <b>M1 Decontamination Heating OFF -&gt;</b> Decont_4_G17H1_S must be OFF, Decont_6_G15H1_S must be OFF, Decont_7_G6H1_S must be OFF  <b>M2 Decontamination Heating ON -&gt;</b> Decont_1_G1H1_S must be ON, Decont_2_G10H1_S must be ON  <b>M2 Decontamination Heating OFF -&gt;</b> Decont_1_G1H1_S must be OFF, Decont_2_G10H1_S must be OFF												
13.5		Verify TM(5,1) M1 Decontamination Heating ON		<input type="checkbox"/>										
		Verify Packet Reception CdmuAsw Event 5-1 M1 Decontamination Heating ON Herschel Packet Details: <table style="margin-left: 200px;"> <tr><td>APID:</td><td>16</td></tr> <tr><td>Type:</td><td>5</td></tr> <tr><td>Subtype:</td><td>1</td></tr> <tr><td>PI1:</td><td>28929</td></tr> <tr><td>PI2:</td><td>0</td></tr> </table>	APID:	16	Type:	5	Subtype:	1	PI1:	28929	PI2:	0	D_EvRp_109	
APID:	16													
Type:	5													
Subtype:	1													
PI1:	28929													
PI2:	0													
		Verify Telemetry Decon4_G17H1_S                  WM91G565                  = ON		GRD=ZGZ3F999										
		Verify Telemetry Decon6_G15H1_S                  WM81G565                  = ON		GRD=ZGZ3F999										
		Verify Telemetry Decon7_G6H1_S                  WM41A565                  = ON		GRD=ZGZ3F999										
13.6		Verify TM(5,1) M1 Decontamination Heating OFF		<input type="checkbox"/>										

Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify Packet Reception CdmuAsw Event 5-1 M1 Decontamination Heating OFF Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28930 PI2: 0	D_EvRp_187	
		Verify Telemetry Decon4_G17H1_S WM91G565	= OFF	GRD=ZGZ3F999
		Verify Telemetry Decon6_G15H1_S WM81G565	= OFF	GRD=ZGZ3F999
		Verify Telemetry Decon7_G6H1_S WM41A565	= OFF	GRD=ZGZ3F999
13.7		Verify TM(5,1) M2 Decontamination Heating ON		☐
		Verify Packet Reception CdmuAsw Event 5-1 M2 Decontamination Heating ON Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28931 PI2: 0	D_EvRp_188	
		Verify Telemetry Decon1_G1H1_S WM11A565	= ON	GRD=ZGZ3G999
		Verify Telemetry Decon2_G10H1_S WM61A565	= ON	GRD=ZGZ3G999
13.8		Verify TM(5,1) M2 Decontamination Heating OFF		☐
		Verify Packet Reception CdmuAsw Event 5-1 M2 Decontamination Heating OFF Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28932 PI2: 0	D_EvRp_189	
		Verify Telemetry Decon1_G1H1_S WM11A565	= OFF	GRD=ZGZ3G999
		Verify Telemetry Decon2_G10H1_S WM61A565	= OFF	GRD=ZGZ3G999
14		Stop decontamination function		Next Step: END

Telescope decontamination during Telescope cool down  
 File: H\_COP\_SYS\_DEC2.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		<b>Call procedure H_COP_SYS_DEC0 to Stop Decontamination heating during Telescope cool down</b>		
		Execute Procedure: H_COP_SYS_DEC0 Stop Decontamination heating during Telescope cool down		
<b>End of Procedure</b>				