

CDMU and ACC TC test (Serv 17 or BD/BSW counter only)  
 File: H\_FCP\_DHS\_1029.xls  
 Author: S. Manganelli



## Procedure Summary

### Objectives

To execute a TC connection test against CDMU and ACC, either by use of service 17 or just verifying the increase of the related BSW TC counters

### Summary of Constraints

In case the BSW TC counters have to be used (no service 17 TM available, for example after transition to SM) the procedure should be run while the allocated MSTACK is the only TC source, Ground and On-Board. If this is not the case, the increase of the BSW counters may not be related to the test commands from this procedure. The change of BD counters is certain verification that the TC has reached the spacecraft.

### Spacecraft Configuration

**Start of Procedure**

Any

**End of Procedure**

Unchanged

### Reference File(s)

**Input Command Sequences**

**Output Command Sequences**

HFD1029A  
 HFD1029B

### Referenced Displays

<b>ANDs</b>	<b>GRDs</b>	<b>SLDs</b>
ZAZ8T999	ZGZ61999	
ZAA08999		


### Configuration Control Information

DATE	FOP ISSUE	VERSION	MODIFICATION DESCRIPTION	AUTHOR	SPR REF
28/10/08		1	Created	S. Manganelli	
11/11/08	2	2	Added AD mode setup	S. Manganelli	
19/03/09	2.2	3	Added use of BD counters DB changes due to OBSW 3_8_2	S. Manganelli	



CDMU and ACC TC test (Serv 17 or BD/BSW counter only)  
 File: H\_FCP\_DHS\_1029.xls  
 Author: S. Manganelli



### Procedure Flowchart Overview



CDMU and ACC TC test (Serv 17 or BD/BSW counter only)  
 File: H\_FCP\_DHS\_1029.xls  
 Author: S. Manganelli

Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch	AIT Comment
<b>Beginning of Procedure</b>					
Dummy1 <i>TC Seq. Name : Dummy1 ( Dummy sequence )</i>  <i>TimeTag Type:</i> <i>Sub Schedule ID:</i>  <input type="checkbox"/>					
1		Is transmission of TM(17,2) enabled ?  type: [If]		Next Step: YES 2 NO 9	
		If the answer is not known, both cases can be tried. There is no risk asking for TM(17,2) when not enabled for transmission.			
<b>End of Sequence</b>					
HFD1029A <i>TC Seq. Name : HFD1029A ( TCtest CDMU ACC TM17 )</i> <i>Using service 17 TM</i>  <i>TimeTag Type:</i> <i>Sub Schedule ID:</i>  <input type="checkbox"/>					
2		Send TC(17,1) to check the link status		Next Step: 3	
		<b>At the reception of this TC, the CDMU will generate a TM(17,2) ("link connection report").</b>			
		Execute Telecommand <div style="text-align: right;"><b>ConnectionTest</b></div> <i>TC Control Flags :</i> <div style="text-align: right;"><b>GBM IL DSE</b></div> <div style="text-align: right;"><b>--Y -- ---</b></div> <i>Subsch. ID : 10</i> <i>Det. descr. : Perform Connection Test</i>	<b>DC810180</b>	<b>TC</b>	
3		Verify that TM(17,2) has been received		Next Step: 4	
		Verify Packet Reception  Link Connection Report Packet Mnemonic : LnkConnecRep APID : 16 Type : 17 Subtype : 2 PI1 : PI2 :			
4		AD protocol initialisation		Next Step: 5	
		In the ' <b>Uplink Configuration</b> ' Tab of the <b>TC SPACON</b> application set the value of <b>V(S)</b> to 0.  <b>After having set the value click on the 'Generate Packet' button.</b>			

CDMU and ACC TC test (Serv 17 or BD/BSW counter only) File: H_FCP_DHS_1029.xls Author: S. Manganelli	
--	--


Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch	AIT Comment
		Check that <b>BD mode</b> is still selected in the <b>Manual Stack</b> application.			
		Execute Telecommand <div style="text-align: right; margin-right: 20px;"><b>ConnectionTest</b></div> TC Control Flags : <div style="text-align: right; margin-right: 20px;">GBM IL DSE --Y -- ---</div> Subsch. ID : 10 Det. descr. : Perform Connection Test	DC810180	TC	
		Execute Telecommand <div style="text-align: right; margin-right: 20px;"><b>FARM1 Unlock Directive</b></div> TC Control Flags : <div style="text-align: right; margin-right: 20px;">GBM IL DSE --Y -- ---</div> Subsch. ID : 30 Det. descr. : FARM1 Unlock Directive	GCUNL000	TC	
		Execute Telecommand <div style="text-align: right; margin-right: 20px;"><b>FARM1 SET V-R- Directive</b></div> Command Parameter(s) : <div style="margin-left: 40px;">V-R- Value                    GPVAL000      0 &lt;dec&gt;</div> TC Control Flags : <div style="text-align: right; margin-right: 20px;">GBM IL DSE --Y -- ---</div> Subsch. ID : 30 Det. descr. : FARM1 SET V-R- Directive	GCSET000	TC	
		NOW Select <b>AD mode</b> in the <b>Manual Stack</b> application.			
5		Send TC(17,1) to check the link status in AD mode		Next Step: 6	
		<b>At the reception of this TC, the CDMU will generate a TM(17,2) ("link connection report").</b>			
		Execute Telecommand <div style="text-align: right; margin-right: 20px;"><b>ConnectionTest</b></div> TC Control Flags : <div style="text-align: right; margin-right: 20px;">GBM IL DSE --Y -- ---</div> Subsch. ID : 10 Det. descr. : Perform Connection Test	DC810180	TC	
6		Verify that TM(17,2) has been received		Next Step: 7	
		Verify Packet Reception  Link Connection Report Packet Mnemonic :        LnkConnecRep APID :                        16 Type :                        17 Subtype :                    2 PI1 : PI2 :			

CDMU and ACC TC test (Serv 17 or BD/BSW counter only)  
 File: H\_FCP\_DHS\_1029.xls  
 Author: S. Manganelli



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch	AIT Comment
6.1		Verify in TC History that this TC has now passed the "O" verification stage. If not, AD protocol has NOT been initialized correctly. Check and Repeat step 4 up to here.			
7		Send TC(17,1) to check the link status		Next Step: 8	
		<b>At the reception of this TC, the ACC will generate a TM(17,2) ("link connection report").</b>			
		Execute Telecommand  <b>ConnectionTest</b>  TC Control Flags :  Subsch. ID : 20 Det. descr. : Perform Connection Test  GBM IL DSE --Y -- ---	<b>AC810070</b>	TC	
8		Verify that TM(17,2) has been received		Next Step: END	
		Verify Packet Reception  Link Connection Report Packet Mnemonic : LnkConnecRep APID : 512 Type : 17 Subtype : 2 PI1 : PI2 :			
End of Sequence					
TC Seq. Name :Dummy2 ( Dummy sequence )  <b>Dummy2</b>  TimeTag Type: Sub Schedule ID:  <input type="checkbox"/>					
9		Note the CDMU and ACC BSW TC counter values		Next Step: 10	
		Verify Telemetry  BSW_TC_TO_BSW                      DELVF160	Note current value	AND=ZAZ8T999	
		Verify Telemetry  BSW_TC_TO_BSW                      AEHKF050	Note current value	AND=ZAA08999	
End of Sequence					
TC Seq. Name :HFD1029B ( TCtest CDMU ACC BSW ) Using BSW TC counters only  <b>HFD1029B</b>  TimeTag Type: N Sub Schedule ID:  <input type="checkbox"/>					

CDMU and ACC TC test (Serv 17 or BD/BSW counter only)  
 File: H\_FCP\_DHS\_1029.xls  
 Author: S. Manganelli



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch	AIT Comment
10		Send TC(17,1) to check the link status		Next Step: 11	
		<b>At the reception of this TC, the CDMU will generate a TM(17,2) ("link connection report").</b>			
		Execute Telecommand  ConnectionTest  TC Control Flags :  Subsch. ID : 10 Det. descr. : Perform Connection Test  GBM IL DSE --Y -- ---	DC810180	TC	
11		If in BD mode: Verify one of the two BD frame counters increase. This confirms reception on board.		Next Step: 12	
		Verify Telemetry  FARM B CNT.                    XD170991	Changing value (cycles between 0 and 3)	GRD=ZGZ61999	
		Verify Telemetry  FARM B CNT.                    XD199991	Changing value (cycles between 0 and 3)	GRD=ZGZ61999	
12		Verify BSW counter increase		Next Step: 13	
		Verify Telemetry  BSW_TC_TO_BSW                    DELVF160	Previous value + 1	AND=ZAZ8T999	
13		Send TC(17,1) to check the link status		Next Step: 14	
		Execute Telecommand  ConnectionTest  TC Control Flags :  Subsch. ID : 20 Det. descr. : Perform Connection Test  GBM IL DSE --Y -- ---	AC810070	TC	
14		If in BD mode: Verify one of the two BD frame counters increase. This confirms reception on board.		Next Step: 15	
		Verify Telemetry  FARM B CNT.                    XD170991	Changing value (cycles between 0 and 3)	GRD=ZGZ61999	

CDMU and ACC TC test (Serv 17 or BD/BSW counter only) File: H_FCP_DHS_1029.xls Author: S. Manganelli	 
--	--

Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch	AIT Comment
		Verify Telemetry <b>FARM B CNT.</b> <b>XD199991</b>	<b>Changing value</b> (cycles between 0 and 3)	GRD=ZGZ61999	
15		Verify BSW counter increase on ACC side		Next Step: END	
		Verify Telemetry <b>BSW_TC_TO_BSW</b> <b>AEHKF050</b>	<b>Previous value</b> + 1	AND=ZAA08999	
End of Sequence					
<b>End of Procedure</b>					