

Perform connection test
File: H_FCP_DHS_3040.xls
Author: S. Manganelli



Procedure Summary

Objectives

This procedure describes the steps needed to perform an end-to-end "connection test", at the beginning of the DTCP, between Ground and the S/C.

Summary of Constraints

n/a

Spacecraft Configuration

Start of Procedure

CDMU in default configuration, that is:

- PM A or B ON (nominally A)
- TM Encoder/OBT A or B active (nominally A)
- RM A and B enabled
- MM A and B ON

Up/downlink active, that is:

- TX1 and TWT1 or TX2 and TWT2 ON (nominally 1)
- RX1 or RX2 locked (nominally 1)

End of Procedure

CDMU in default configuration, that is:

- PM A or B ON (nominally A)
- TM Encoder/OBT A or B active (nominally A)
- RM A and B enabled
- MM A and B ON

Up/downlink active, that is:

- TX1 and TWT1 or TX2 and TWT2 ON (nominally 1)
- RX1 or RX2 locked (nominally 1)

Reference File(s)

Input Command Sequences

Output Command Sequences

HFD3040A
HFD3040B
HFD3040C
HFD3040D
HFD3040E

Referenced Displays

ANDs GRDs SLDs

Perform connection test
 File: H_FCP_DHS_3040.xls
 Author: S. Manganelli



ZAZAG999
 ZAZAH999
 ZAZAP999
 ZAZ08999
 ZAZ0D999
 ZAZ0C999


Configuration Control Information

DATE	FOP ISSUE	VERSION	MODIFICATION DESCRIPTION	AUTHOR	SPR REF
23/11/07		1	Created	cmevi-hp	
03/12/07		2	Minor update.	cmevi-hp	
03/12/07		3	Name of sequences modified.	cmevi-hp	
24/01/08		4	Batch update of TC flags	S. Manganelli	
13/06/08		5	DB check	S. Manganelli	
13/06/08		6	Visio editorial	S. Manganelli	
04/08/08	1	7	Added list of bus profiles	S. Manganelli	
24/10/08		8	TM checks modified for OBSW 3_6_2	S. Manganelli	
02/12/08		9	Added some comments	S. Manganelli	
13/01/09	2	10	Updated following OBSW 3_8	S. Manganelli	
19/03/09	2.2	11	DB changed due to OBSW 3_8_2	S. Manganelli	

Perform connection test
 File: H_FCP_DHS_3040.xls
 Author: S. Manganelli




Procedure Flowchart Overview



Perform connection test
File: H_FCP_DHS_3040.xls
Author: S. Manganelli



Procedure Flowchart Overview



Perform connection test
 File: H_FCP_DHS_3040.xls
 Author: S. Manganelli



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
Beginning of Procedure				
TC Seq. Name :HFD3040 (Dummy sequence) TimeTag Type: N Sub Schedule ID: <input type="checkbox"/>				
1		Choose the RT to be tested		Next Step: 2
2		What did you choose ?		Next Step: CDMU 3 ACC 5 HIFI 7 PACS 13 SPIRE 19
TC Seq. Name :HFD3040A (CDMU connection test) TimeTag Type: Sub Schedule ID: <input type="checkbox"/>				
3		Send TC(17,1) to check the link status		Next Step: 4
		At the reception of this TC, the CDMU will generate a TM(17,2) ("link connection report").		
		Execute Telecommand <div style="text-align: right;">ConnectionTest</div> TC Control Flags : <div style="text-align: right;">GBM IL DSE --Y -- ---</div> Subsch. ID : 10 Det. descr. : Perform Connection Test	DC810180	
4		Verify that TM(17,2) has been received		Next Step: END
		Verify Packet Reception Packet Details: <div style="float: right; text-align: right;"> Link Connection Report APID: 16 Type: 17 Subtype: 2 PI1: PI2: </div>	LnkConneRep	

Perform connection test
 File: H_FCP_DHS_3040.xls
 Author: S. Manganelli



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
TC Seq. Name :HFD3040B (ACC connection test) TimeTag Type: N Sub Schedule ID: <input type="checkbox"/>				
5		Send TC(17,1) to check the link status		Next Step: 6
		At the reception of this TC, the ACC will generate a TM(17,2) ("link connection report").		
		Execute Telecommand <div style="text-align: right;">ConnectionTest</div> TC Control Flags : <div style="text-align: right;">GBM IL DSE --Y -- ---</div> Subsch. ID : 20 Det. descr. : Perform Connection Test	AC810070	
6		Verify that TM(17,2) has been received		Next Step: END
		Verify Packet Reception <div style="text-align: right;">Link Connection Report</div> Packet Details: <div style="text-align: right;"> APID: 512 Type: 17 Subtype: 2 PI1: PI2: </div>	LnkConnecRep	
TC Seq. Name :HFD3040C (HIFI connection tes) TimeTag Type: N Sub Schedule ID: <input type="checkbox"/>				
7		Verify Status of Remote Terminal being used (A -> Nominal assumed here)		Next Step: 8
		Verify RT HW status <div style="text-align: right;">HIFIA_OnOff</div> <div style="text-align: right;">DEDZG161</div> <div style="text-align: right;">= ON</div>		AND=ZAZAG999
		Verify RT soft status <div style="text-align: right;">HIFIA_DeadAlive</div> <div style="text-align: right;">DEDZH161</div> <div style="text-align: right;">= Alive</div>		AND=ZAZAG999
		Verify RT TC Link <div style="text-align: right;">HIFIA_WellsicTC</div> <div style="text-align: right;">DEDZZ161</div> <div style="text-align: right;">= Well</div>		AND=ZAZAG999
		Verify RT TM Link <div style="text-align: right;">HIFIA_WellsicTM</div> <div style="text-align: right;">DEDZJ161</div> <div style="text-align: right;">= Well</div>		AND=ZAZAG999
		Verify RT validity <div style="text-align: right;">HIFIA_ValidInv</div> <div style="text-align: right;">DEDZK161</div> <div style="text-align: right;">= Valid</div>		AND=ZAZAG999

Perform connection test
 File: H_FCP_DHS_3040.xls
 Author: S. Manganelli



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify RT HW status HIFIB_OnOff DED11161	= OFF	AND=ZAZAG999
		Verify RT soft status HIFIB_DeadAlive DED12161	= Alive	AND=ZAZAG999
		Verify Telemetry HIFIB_WellsicTC DED13161	= Well	AND=ZAZAG999
		Verify Telemetry HIFIB_WellsicTM DED14161	= Well	AND=ZAZAG999
		Verify Telemetry HIFIB_ValidInv DED15161	= Invalid	AND=ZAZAG999
		Verify Telemetry HIFI_NomRed DED4H161	= NOMINAL	AND=ZAZAH999
		Verify Telemetry HIFIA_TFLTM DEDZL161	= ENABLED	AND=ZAZAP999
		Verify Telemetry HIFIB_TFLTM DED16161	= DISABLED	AND=ZAZAP999
8		Verify SDB configuration See bus profile list at end of procedure		Next Step: 9
		Verify :Index of currently active bus profile BSW_SDB_ActProf DEF5F160	as required	AND=ZAZ08999
9		Health status of bus A / B		Next Step: 10
		Verify :bus-side A Healthy/Unhealthy BusA_HealthySts DEFJ2160	= Healthy	AND=ZAZ08999
		Verify :bus-side B Healthy/Unhealthy BusB_HealthySts DEFJ3160	= Healthy	AND=ZAZ08999
10		Verify Spacecraft Data Bus BSW configuration		Next Step: 11
		Verify : active 1553 bus Active_Bus_A_B DEFJ1160	= BUS_A	AND=ZAZ08999
		Verify : 1553 bus FDIR status SDB_FDIR DEFJ4160	= ENABLED	AND=ZAZ08999
		Verify :SDB handling enabled or disabled. BSW_SDB_ENAB DEF60160	= ENABLED	AND=ZAZ08999
11		Send TC(17,1) to check the link status		Next Step: 12

Perform connection test
 File: H_FCP_DHS_3040.xls
 Author: S. Manganelli



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		At the reception of this TC, HIFI will generate a TM(17,2) ("link connection report").		
		Execute Telecommand <p style="text-align: right;">HIFI_connection_test</p> TC Control Flags : <p style="text-align: right;">GBM IL DSE --Y -- ---</p> Subsch. ID : 70 Det. descr. : Generate a connection test report	HC176289	
12		Verify that TM(17,2) has been received		Next Step: END
		Verify Packet Reception <p style="text-align: right;">HIFI_Connection_report</p> Packet Details: <p style="text-align: right;">APID: Type: Subtype: PI1: PI2:</p>	H_HIFI_Conn 1024 17 2	
TC Seq. Name :HFD3040D (PACS connection test) TimeTag Type: Sub Schedule ID: <input type="checkbox"/>				
13		Verify Status of Remote Terminal being used (A -> Nominal assumed here)		Next Step: 14
		Verify RT HW status <p style="text-align: right;">PACSA_OnOff DED2G161</p>	= ON	AND=ZAZ0D999
		Verify RT soft status <p style="text-align: right;">PACSA_Dealiv DED2H161</p>	= Alive	AND=ZAZ0D999
		Verify RT TC Link <p style="text-align: right;">PACSA_WellsiTC DED2Z161</p>	= Well	AND=ZAZ0D999
		Verify RT TM Link <p style="text-align: right;">PACSA_WellsiTM DED2J161</p>	= Well	AND=ZAZ0D999
		Verify RT validity <p style="text-align: right;">PACSA_ValidInv DED2K161</p>	= Valid	AND=ZAZ0D999
		Verify RT HW status <p style="text-align: right;">PACSB_OnOff DED31161</p>	= OFF	AND=ZAZ0C999
		Verify RT soft status <p style="text-align: right;">PACSB_Dealiv DED32161</p>	= Alive	AND=ZAZ0C999
		Verify RT TC Link <p style="text-align: right;">PACSB_WellsiTC DED33161</p>	= Well	AND=ZAZ0C999

Perform connection test
 File: H_FCP_DHS_3040.xls
 Author: S. Manganelli



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify RT TM Link PACSB_WellsiTM DED34161	= Well	AND=ZAZ0C999
		Verify RT validity PACSB_ValidInv DED35161	= Invalid	AND=ZAZ0C999
		Verify Telemetry PACS_NomRed DED5H161	= NOMINAL	AND=ZAZAH999
		Verify Telemetry PACSA_TFLTM DED2L161	= ENABLED	AND=ZAZAP999
		Verify Telemetry PACSB_TFLTM DED36161	= DISABLED	AND=ZAZAP999
14		Verify SDB configuration See bus profile list at end of procedure		Next Step: 15
		Verify :Index of currently active bus profile BSW_SDB_ActProf DEF5F160	as required	AND=ZAZ08999
15		Health status of bus A / B		Next Step: 16
		Verify :bus-side A Healthy/Unhealthy BusA_HealthySts DEFJ2160	= Healthy	AND=ZAZ08999
		Verify :bus-side B Healthy/Unhealthy BusB_HealthySts DEFJ3160	= Healthy	AND=ZAZ08999
16		Verify Spacecraft Data Bus BSW configuration		Next Step: 17
		Verify : active 1553 bus Active_Bus_A_B DEFJ1160	= BUS_A	AND=ZAZ08999
		Verify : 1553 bus FDIR status SDB_FDIR DEFJ4160	= ENABLED	AND=ZAZ08999
		Verify :SDB handling enabled or disabled. BSW_SDB_ENAB DEF60160	= ENABLED	AND=ZAZ08999
17		Send TC(17,1) to check the link status		Next Step: 18
		At the reception of this TC, the PACS will generate a TM(17,2) ("link connection report").		

Perform connection test
 File: H_FCP_DHS_3040.xls
 Author: S. Manganelli



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Execute Telecommand DPU_TEST_CONN <i>TC Control Flags :</i> Subsch. ID : 90 Det. descr. : DPU STARTS THE ARE YOU ALIVE PROCEDURE GBM IL DSE --Y -- --	PC023380	
18		Verify that TM(17,2) has been received		Next Step: END
		Verify Packet Reception Packet Details: PACS_LINK_CONNECTION APID: Type: Subtype: PI1: PI2:	LINK_CONNECT 1152 17 2	
TC Seq. Name :HFD3040E (SPIREconnection test) TimeTag Type: Sub Schedule ID: <input type="checkbox"/>				
19		Verify Status of Remote Terminal being used (A -> Nominal assumed here)		Next Step: 20
		Verify RT HW status SPIREA_OnOff DED1G161	= ON	AND=ZAZ0D999
		Verify RT soft status SPIREA_DeadAliv DED1H161	= Alive	AND=ZAZ0D999
		Verify RT TC Link SPIREA_WellsiTC DED1Z161	= Well	AND=ZAZ0D999
		Verify RT TM Link SPIREA_WellsiTM DED1J161	= Well	AND=ZAZ0D999
		Verify RT validity SPIREA_ValidInv DED1K161	= Valid	AND=ZAZ0D999
		Verify RT HW status SPIREB_OnOff DED21161	= OFF	AND=ZAZ0C999
		Verify RT soft status SPIREB_DeadAliv DED22161	= Alive	AND=ZAZ0C999
		Verify RT TC Link SPIREB_WellsiTC DED23161	= Well	AND=ZAZ0C999
		Verify RT TM Link SPIREB_WellsiTM DED24161	= Well	AND=ZAZ0C999

Perform connection test
 File: H_FCP_DHS_3040.xls
 Author: S. Manganelli



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify RT validity SPIREB_ValidInv DED25161	= Invalid	AND=ZAZ0C999
		Verify Telemetry SPIRE_NomRed DED53161	= NOMINAL	AND=ZAZAH999
		Verify Telemetry SPIREA_TFLTM DED1L161	= ENABLED	AND=ZAZAP999
		Verify Telemetry SPIREB_TFLTM DED26161	= DISABLED	AND=ZAZAP999
20		Verify SDB configuration		Next Step: 21
		See bus profile list at end of procedure		
		Verify :Index of currently active bus profile BSW_SDB_ActProf DEF5F160	as required	AND=ZAZ08999
21		Health status of bus A / B		Next Step: 22
		Verify :bus-side A Healthy/Unhealthy BusA_HealthySts DEFJ2160	= Healthy	AND=ZAZ08999
		Verify :bus-side B Healthy/Unhealthy BusB_HealthySts DEFJ3160	= Healthy	AND=ZAZ08999
22		Verify Spacecraft Data Bus BSW configuration		Next Step: 23
		Verify : active 1553 bus Active_Bus_A_B DEFJ1160	= BUS_A	AND=ZAZ08999
		Verify : 1553 bus FDIR status SDB_FDIR DEFJ4160	= ENABLED	AND=ZAZ08999
		Verify :SDB handling enabled or disabled. BSW_SDB_ENAB DEF60160	= ENABLED	AND=ZAZ08999
23		Send TC(17,1) to check the link status		Next Step: 24
		At the reception of this TC, the SPIRE will generate a TM(17,2) ("link connection report").		
		Execute Telecommand TEST_CONNECTION TC Control Flags : Subsch. ID : 370 Det. descr. : PERFORM CONNECTION TEST	SCL00500 GBM IL DSE --Y -- --	

Perform connection test
 File: H_FCP_DHS_3040.xls
 Author: S. Manganelli



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
24		Verify that TM(17,2) has been received		Next Step: END
		Verify Packet Reception Packet Details: <div style="text-align: right;"> Test_Service_Report APID: Type: Subtype: PI1: PI2: </div>	STESTSERV500 1280 17 2	
End of Procedure				

Perform connection test
File: H_FCP_DHS_3040.xls
Author: S. Manganelli



Bus Profiles

HERSCHEL: 9 Operative Bus Profiles

- Launch : index 0 and defined by TC(8,4,6,1) identified by C001 to C064.
- Earth Acquisition : index 1 and defined by TC(8,4,6,1) identified by C101 to C164.
- HIFI Prime : index 2 and defined by TC(8,4,6,1) identified by C201 to C264.
- SPIRE Prime : index 3 and defined by TC(8,4,6,1) identified by C301 to C364.
- PACS Prime : index 4 and defined by TC(8,4,6,1) identified by C401 to C464.
- Sun Acquisition : index 5 and defined by TC(8,4,6,1) identified by C501 to C564.
- Survival : index 6 and defined by TC(8,4,6,1) identified by C601 to C664.
- Burst : index 7 and defined by TC(8,4,6,1) identified by C701 to C764.
- Parallel Mode : index 8 and defined by TC(8,4,6,1) identified by C801 to C864.

PLANCK: 5 Operative Bus Profiles

- Launch : index 0 and defined by TC(8,4,6,1) identified by C001 to C064.
- Earth Acquisition : index 1 and defined by TC(8,4,6,1) identified by C101 to C164.
- Science : index 2 and defined by TC(8,4,6,1) identified by C201 to C264.
- Sun Acquisition : index 3 and defined by TC(8,4,6,1) identified by C301 to C364.
- Survival : index 4 and defined by TC(8,4,6,1) identified by C401 to C464.