

Start Decontamination heating  
File: H\_LEO\_SYS\_DECL.xls  
Author: E. Picallo



## Procedure Summary

### Objectives

This procedure describes the steps needed to start the decontamination of the mirrors M1 and M2

In order to balance the power budget in pre-op phase, an operational strategy has been implemented: in a first decontamination phase, to switch ON only 5 out the 7 heater lines on the M1 and both heater lines on M2. When stabilisation is reached, switch ON the two remaining heater lines on M1.

### Summary of Constraints

Due to power constraints, the following pre-conditions are required to start decontamination and shall remain valid during the entire warm-up phase:

- Spacecraft mode shall be either SAM (Instruments OFF) or NOM but with instruments OFF
- ACMS shall be SAM or OCM / Sun pointing (SAA < 1°)
- Battery shall be at 99% EOC with Vbatt > 25,32 V
- The RWLs shall be OFF or STBY (i.e. can be ON but not commanded)

The warm-up phase should take ~8 hs.

Once in steady-state phase, the decontamination power need will decrease from ~570W to ~290W. Thus, the constraints on ACMS mode to be Sun pointing and no RWL commanding are not anymore applicable (i.e. ACMS can be set in SCM and RWLs run-in can be activated).

There is enough power margin during the steady state decontamination phase to cope with the wheel run in spikes of max 90 W per wheel for a few minutes.

The Cryostat cover shall be closed to protect FPU.

The spacecraft shall be in visibility for all the procedure execution.

TCS Dgn. Packet shall be enabled.

### Spacecraft Configuration

#### Start of Procedure

The nominal HPS shall be ON (1,2,4,6,9)  
Decontamination heating function stopped  
ACMS mode in SAM or OCM/Sun pointing  
Battery 99% full charged  
RWLs OFF or in STBY (i.e. can be ON but not commanded)  
Cryostat cover closed  
Instruments OFF

#### End of Procedure

Decontamination heating function running  
HPSs 1,2,4,6,9,10,15,17,18 ON

### Reference File(s)

#### Input Command Sequences

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECl.xls  
 Author: E. Picallo



**Output Command Sequences**

HLVDEC1

**Referenced Displays**

**ANDs**      **GRDs**      **SLDs**  
 ZAZ9J999      (None)


**Configuration Control Information**

DATE	FOP ISSUE	VERSION	MODIFICATION DESCRIPTION	AUTHOR	SPR REF
01/08/08	1	1	Created	E. Picallo	
04/09/08		2	TCS Diag Pkt added (updated with SDB v.7)	E. Picallo	
05/11/08		3	Dec. temperature thresholds corrected (RAW values) □ MOT dec. entries default thresholds corrected (RAW values) □ MOT dec. entries enabled in AFS and AFO	E. Picallo	
07/11/08		4	Enable MOT & EAT entries after start dec. function correction	E. Picallo	
08/01/09	2	5	Decontamination RAW threshold updated according to H-P-2-ASP-ID-1418 issue 4 cal. points	E. Picallo	
23/02/09	2.1	6	Pre-conditions check added □ Switch ON redundant lines on M1 at start of steady-state	E. Picallo	
24/03/09	2.2	7	reference to procedure "H_FCP_AOC_D3FD" Define/Enable/Disable DTM for FD added	E. Picallo	

Start Decontamination heating  
 File: H\_LEO\_SYS\_DEC1.xls  
 Author: E. Picallo



### Procedure Flowchart Overview



Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
<b>Beginning of Procedure</b>				
<p>TC Seq. Name : HLYDEC1 (StartDecontamination)            Start the decontamination of the mirrors M1 and M2</p> <p>TimeTag Type: N            Sub Schedule ID:</p> <p style="text-align: center;">□</p>				
1		Enable "H TM Data for 9 Stars Com1" Diagnostic packet		Next Step: 2
		<b>It is required to enable the Diagnostic Packet in order to monitor the Sun asp angle.</b>		
		<b>Call procedure "H_FCP_AOC_D3FD" Define/Enable/Disable DTM for FD</b> 1) Acquire the list of the current enabled TM packets 2) Verify if the "H TM Data for 9 Stars Com1" (SPID 240011990) Diagnostic packet is enabled 3) If it is disabled, enable it		
2		Check required initial conditions		Next Step: 3
		<b>Due to power constraints, the following conditions are required to start the decontamination warm-up:</b> - ACMS in SAM or OCM / Sun pointing (Z axis) i.e. SAA < 1° - Vbatt > 25,32 V (battery at 99% charge) - RWLs OFF or in STBY (i.e. can be ON but not commanded)		
2.1		Check ACMS mode and Sun Aspect Angle		□
		Verify Telemetry <div style="display: flex; justify-content: space-between;"> <span>AcmsMode</span> <span>AESMG002</span> </div>	= OCM = SAM	(None)
		Verify Telemetry <div style="display: flex; justify-content: space-between;"> <span>AcmsSubstate</span> <span>AESMF002</span> </div>	= OCM Pointing = SAM Sun Point	(None)
		Verify Telemetry <div style="display: flex; justify-content: space-between;"> <span>Sun asp angle</span> <span>AESAN002</span> </div>	< 1 degree (0.017 rad)	(None)
2.1.1		Confirm sun pointing attitude		□
		Verify Telemetry <div style="display: flex; justify-content: space-between;"> <span>Sunvector X BRF</span> <span>AEUVX001</span> </div>	approx. 0	(None)
		Verify Telemetry <div style="display: flex; justify-content: space-between;"> <span>Sunvector Y BRF</span> <span>AEUVY001</span> </div>	approx. 0	(None)

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify Telemetry Sunvector Z BRF AEUVZ001	approx. 1	(None)
		Verify Telemetry Est ang rate X AESR7001	~0 rd/s	(None)
		Verify Telemetry Est ang rate Y AESR8001	~0 rd/s	(None)
		Verify Telemetry Est ang rate Z AESR9001	~0 rd/s	(None)
2.2		Check batteries charge status		□
		<b>The telescope decontamination can be started when the battery is at 99% EOC (Vbatt &gt; 25.32 V)</b>  <b>During LEOP, the battery shall be 99% charged after ~3 hours.</b>		
		Verify Telemetry TM_VBATT_BDR_1 WMT02565	>= 25.32 V	(None)
		Verify Telemetry TM_VBATT_BDR_2 WMT03565	>= 25.32 V	(None)
2.3		Check RWLs status		□
		<b>During the decontamination warm-up, the RWLs can be powered ON but in STBY (i.e. no RWL biasing ongoing and they can not be commanded).</b>		
		Verify Telemetry RWL1 power AE4P3002	= OFF = ON	(None)
		Verify Telemetry RWL2 power AE4P4002	= OFF = ON	(None)
		Verify Telemetry RWL3 power AE4P5002	= OFF = ON	(None)
		Verify Telemetry RWL4 power AE4P6002	= OFF = ON	(None)
		Verify Telemetry CurrentBiasAid AESM9002	= Standby = Stopped	(None)

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
3		<i>Is CCU A/B in monitoring mode for Decontamination (Period 8 sec)?</i>		Next Step: no 4 yes 5
4		<i>TM acquisition period change (CCU A and B)</i>		Next Step: 5
		<b>Select the monitoring mode for decontamination: set acquisition period to 8 seconds for all sensor except spre ones and enable the diagnostic packets CCU A/B monit#2</b>		
		Execute Procedure: H_FCP_CCU_ACQP CCU acquisition period update		
5		<i>Enable TCS Diagnostic Packet</i>		Next Step: 6
		<b>It is required to enable the TCS Diagnostic Packet in order to monitor the M1 &amp; M2 median temperature parameters.</b>		
		Call procedure "Enable or disable the generation of an housekeeping or diagnostic packet" H_FCP_DHS_3033  1) Acquire the list of the current enabled TM packets 2) Verify if the TCS Diagnostic packet is enabled: TCS -> subtype=26, packet-ID=100 3) If it is disabled, enable it		
		Execute Procedure: H_FCP_DHS_3033 Enable or disable the generation of an housekeeping or diagnostic packet		
6		<i>Verify CCU acquisition of decontamination thermistors</i>		Next Step: 7
		<b>The primary mirror M1 provides 3 sets of 3 thermistors. The secondary mirror M2 provides 1 set of 3 thermistors.</b>		
		<b>Nominal thermistors used for temperature determination (used to calculate the temperature median algorithm):</b>  <b>For M1 decontamination are TH A (T331), TH A'' (T332), TH C (T335).</b>  <b>For M2 decontamination are TH X (T339), TH Y (T341), TH Z (T342).</b>		

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
6.1		Verify M1 Thermistors		<input type="checkbox"/>
		<b>The nominal thermal sensors to be used for M1 decontamination are TH A (T331), TH A'' (T332), TH C (T335)</b>		
		Verify on telescope; M1 THA ; T21-5 (A) PT1000_T331                      KD253302		AND=ZAZ9J999
		Verify on telescope; M1 THA'' ; T16-5 (B) PT1000_T332                      KD248303		AND=ZAZ9J999
		Verify on telescope; M1 THC ; T23-5 (A) PT1000_T335                      KD255302		AND=ZAZ9J999
6.2		Verify M2 Thermistors		<input type="checkbox"/>
		<b>The nominal thermal sensors to be used for M2 decontamination are TH X (T339), TH Y (T341), TH Z (T342)</b>		
		Verify on telescope; M2 THX ; T25-5 (A) PT1000_T339                      KD257302		AND=ZAZ9J999
		Verify on telescope; M2 THY ; T26-5 (A) PT1000_T341                      KD258302		AND=ZAZ9J999
		Verify on telescope; M2 THZ ; T30-5 (B) PT1000_T342                      KD262303		AND=ZAZ9J999
7		Check status of nominal HPS involved in decontamination heating phase of M1 and M2		Next Step: 8
7.1		Check status of nominal HPS involved in decontamination heating phase of M1 (HPS 2,4,6 and 9)		<input type="checkbox"/>
		<b>There are 7 heaters lines for M1 (4N+3R): M1 heater line 3 (HPS 02 HCS 1 N) M1 heater line 4 (HPS 17 HCS 1 R)  M1 heater line 5 (HPS 04 HCS 1 N) M1 heater line 6 (HPS 15 HCS 1 R)  M1 heater line 7 (HPS 06 HCS 1 N) M1 heater line 8 (HPS 09 HCS 1 N) M1 heater line 9 (HPS 18 HCS 1 R)</b>		
		Verify Telemetry GRP2_HPS_STS                      WM22G565	= ON	AND=ZAZ9J999
		Verify Telemetry GRP4_HPS_STS                      WM32G565	= ON	AND=ZAZ9J999

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify Telemetry GRP6_HPS_STS WM42G565	= ON	AND=ZAZ9J999
		Verify Telemetry GRP9_HPS_STS WM52H565	= ON	AND=ZAZ9J999
7.2		Check status of nominal HPS involved in decontamination heating phase of M2 (HPS1)		<input type="checkbox"/>
		<b>There are 2 heaters lines for M2 (1N+1R): M2 heater line 1 (HPS 01 HCS 1 N) M2 heater line 2 (HPS 10 HCS 1 R)</b>		
		Verify Telemetry GRP1_HPS_STS WM12G565	= ON	AND=ZAZ9J999
8		Switch ON redundant HPS invloved in first decontamination heating phase (warm up) on M1 & M2		Next Step: 9
		<b>Redundant heater line 4 on M1 (HPS 17 HCS 1 R) Redundant heater line 6 on M1 (HPS 15 HCS 1 R)</b>		
		<b>Redundant heater line 2 on M2 (HPS 10 HCS 1 R)</b>		
8.1		Switch ON HPS17		<input type="checkbox"/>
		Execute Telecommand PcduswOnHps17 TC Control Flags : GBM IL DSE --Y -- -- Subsch. ID : 10 Det. descr. : PCDU:TC(8,4,112,5) switch On HPS 17	DCC17170	
		Verify Telemetry GRP17_HPS_STS WM92H565	= ON	AND=ZAZ9J999
8.2		Switch ON HPS15		<input type="checkbox"/>
		Execute Telecommand PcduswOnHps15 TC Control Flags : GBM IL DSE --Y -- -- Subsch. ID : 10 Det. descr. : PCDU:TC(8,4,112,5) switch On HPS 15	DCC15170	
		Verify Telemetry GRP15_HPS_STS WM82H565	= ON	AND=ZAZ9J999



Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch																											
8.3		Switch ON HPS10		<input type="checkbox"/>																											
		Execute Telecommand <p style="text-align: right;">PcduswOnHps10</p> TC Control Flags : <p style="text-align: right;">GBM IL DSE --Y -- ---</p> Subsch. ID : 10 Det. descr. : PCDU:TC(8,4,112,5) switch On HPS 10	DCC10170																												
		Verify Telemetry <p style="text-align: center;">GRP10_HPS_STS                      WM62G565</p>	= ON	AND=ZAZ9J999																											
9		Set heater mask on M1 & M2 and decontamination thresholds to 39,5°C/40,5°C		Next Step: 10																											
		<p><b>In the first phase, the proposed strategy is to switch ON only 5 of the 7 heater lines of M1 and both lines of M2, then:</b></p> <p><b>- M1 heater mask: 0000 0000 0011 1011 = 0x003B = 59 (selecting lines 1,2,4,5,6 and excluding lines 3 &amp; 7)</b></p> <p><b>- M2 heater mask: 0000 0000 0000 0011 = 0x0003 = 3 (using both lines 1 &amp; 2)</b></p>																													
		Execute Telecommand <p style="text-align: right;">Decont - Heater mask</p> Command Parameter(s) : <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 40%;">Decont - M1 heater 7</td> <td style="width: 20%;">ZHB17999</td> <td style="width: 40%;">NOTACTIVE (Def)</td> </tr> <tr> <td>Decont - M1 heater 6</td> <td>ZHB16999</td> <td>ACTIVE (Def)</td> </tr> <tr> <td>Decont - M1 heater 5</td> <td>ZHB15999</td> <td>ACTIVE (Def)</td> </tr> <tr> <td>Decont - M1 heater 4</td> <td>ZHB14999</td> <td>ACTIVE (Def)</td> </tr> <tr> <td>Decont - M1 heater 3</td> <td>ZHB13999</td> <td>NOTACTIVE (Def)</td> </tr> <tr> <td>Decont - M1 heater 2</td> <td>ZHB12999</td> <td>ACTIVE (Def)</td> </tr> <tr> <td>Decont - M1 heater 1</td> <td>ZHB11999</td> <td>ACTIVE (Def)</td> </tr> <tr> <td>Decont - M2 heater 2</td> <td>ZHB22999</td> <td>ACTIVE (Def)</td> </tr> <tr> <td>Decont - M2 heater 1</td> <td>ZHB21999</td> <td>ACTIVE (Def)</td> </tr> </table> TC Control Flags : <p style="text-align: right;">GBM IL DSE --Y -- ---</p> Subsch. ID : 10 Det. descr. : TC(8,4,113,1) to update the M1 and M2 active heaters	Decont - M1 heater 7	ZHB17999	NOTACTIVE (Def)	Decont - M1 heater 6	ZHB16999	ACTIVE (Def)	Decont - M1 heater 5	ZHB15999	ACTIVE (Def)	Decont - M1 heater 4	ZHB14999	ACTIVE (Def)	Decont - M1 heater 3	ZHB13999	NOTACTIVE (Def)	Decont - M1 heater 2	ZHB12999	ACTIVE (Def)	Decont - M1 heater 1	ZHB11999	ACTIVE (Def)	Decont - M2 heater 2	ZHB22999	ACTIVE (Def)	Decont - M2 heater 1	ZHB21999	ACTIVE (Def)	ZCB03999	
Decont - M1 heater 7	ZHB17999	NOTACTIVE (Def)																													
Decont - M1 heater 6	ZHB16999	ACTIVE (Def)																													
Decont - M1 heater 5	ZHB15999	ACTIVE (Def)																													
Decont - M1 heater 4	ZHB14999	ACTIVE (Def)																													
Decont - M1 heater 3	ZHB13999	NOTACTIVE (Def)																													
Decont - M1 heater 2	ZHB12999	ACTIVE (Def)																													
Decont - M1 heater 1	ZHB11999	ACTIVE (Def)																													
Decont - M2 heater 2	ZHB22999	ACTIVE (Def)																													
Decont - M2 heater 1	ZHB21999	ACTIVE (Def)																													





Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo




Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch															
		<p>There are 2 entries are defined in the EAT related to decontamination:</p> <p><b>APID Event ID Action TC</b>  <b>16(CDMS) 40960 Switch OFF HPS1 TC(8,4,112,3)</b>  <b>16(CDMS) 40961 Switch OFF HPS10 TC(8,4,112,3)</b></p>																	
		<p>Execute Telecommand</p> <p style="text-align: right;"><b>EnableActions</b></p> <p><b>DCT84170</b></p> <p>Command Parameter(s) :</p> <table border="0"> <tr> <td>N_Repetition</td> <td>DH041170</td> <td>2 &lt;dec&gt;</td> </tr> <tr> <td>APID_for_EAT_TC</td> <td>DH236170</td> <td>CDMS (Def)</td> </tr> <tr> <td>EventId</td> <td>DH146170</td> <td>40960 &lt;dec&gt;</td> </tr> <tr> <td>APID_for_EAT_TC</td> <td>DH236170</td> <td>CDMS (Def)</td> </tr> <tr> <td>EventId</td> <td>DH146170</td> <td>40961 &lt;dec&gt;</td> </tr> </table> <p>TC Control Flags :</p> <p style="text-align: right;"><b>GBM IL DSE</b>  <b>--Y -- ---</b></p> <p>Subsch. ID : 10  Det. descr. : TEMPLATE Enable Actions TC(19,4)</p>	N_Repetition	DH041170	2 <dec>	APID_for_EAT_TC	DH236170	CDMS (Def)	EventId	DH146170	40960 <dec>	APID_for_EAT_TC	DH236170	CDMS (Def)	EventId	DH146170	40961 <dec>		
N_Repetition	DH041170	2 <dec>																	
APID_for_EAT_TC	DH236170	CDMS (Def)																	
EventId	DH146170	40960 <dec>																	
APID_for_EAT_TC	DH236170	CDMS (Def)																	
EventId	DH146170	40961 <dec>																	
11.4		Report EAT table to check the decontamination EAT entries		<input type="checkbox"/>															
		<p>Execute Telecommand</p> <p style="text-align: right;"><b>ReptEvtActTable</b></p> <p><b>DCT86170</b></p> <p>TC Control Flags :</p> <p style="text-align: right;"><b>GBM IL DSE</b>  <b>--Y -- ---</b></p> <p>Subsch. ID : 10  Det. descr. : TEMPLATE Report The contents of the event/action table TC(19,6)</p>																	
12		Wait for temperature stabilisation		Next Step: 13															
		Wait until the median temperature on M1 and M2 oscillate between the selected thresholds [39,5°C/40,5°C]																	
		Decontamination warm-up phase does not allow for extra power consumption peaks nor sun depointing ( not compatible of wheel run in spikes or reorientations for deltaV maneuver).																	
		Duration of warm-up phase depends on start-up temperature and environment and is estimated to last approximately 8 hours if started at T0+8 hours.																	
		Verify M1 median temperature Telemetry <b>DhM1Temp DE800171</b>	<b>&gt;= 39.5 &lt;dec&gt;</b> <b>&lt;= 40.5 &lt;dec&gt;</b>	AND=ZAZ9J999															
		Verify M2 median temperature Telemetry <b>DhM2Temp DE801171</b>	<b>&gt;= 39.5 &lt;dec&gt;</b> <b>&lt;= 40.5 &lt;dec&gt;</b>	AND=ZAZ9J999															

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch										
		<b>Verify reception of TM packets:</b> TM(5,1,113,1) -> generated when M1 Heating is switch ON TM(5,1,113,2) -> generated when M1 Heating is switch OFF TM(5,1,113,3) -> generated when M2 Heating is switch ON TM(5,1,113,4) -> generated when M2 Heating is switch OFF												
		Verify Packet Reception CdmuAsw Event 5-1 M1 Decontamination Heating ON Herschel Packet Details: <table style="margin-left: 200px;"> <tr><td>APID:</td><td>16</td></tr> <tr><td>Type:</td><td>5</td></tr> <tr><td>Subtype:</td><td>1</td></tr> <tr><td>PI1:</td><td>28929</td></tr> <tr><td>PI2:</td><td>0</td></tr> </table>	APID:	16	Type:	5	Subtype:	1	PI1:	28929	PI2:	0	D_EvRp_109	
APID:	16													
Type:	5													
Subtype:	1													
PI1:	28929													
PI2:	0													
		Verify Packet Reception CdmuAsw Event 5-1 M1 Decontamination Heating OFF Herschel Packet Details: <table style="margin-left: 200px;"> <tr><td>APID:</td><td>16</td></tr> <tr><td>Type:</td><td>5</td></tr> <tr><td>Subtype:</td><td>1</td></tr> <tr><td>PI1:</td><td>28930</td></tr> <tr><td>PI2:</td><td>0</td></tr> </table>	APID:	16	Type:	5	Subtype:	1	PI1:	28930	PI2:	0	D_EvRp_187	
APID:	16													
Type:	5													
Subtype:	1													
PI1:	28930													
PI2:	0													
		Verify Packet Reception CdmuAsw Event 5-1 M2 Decontamination Heating ON Herschel Packet Details: <table style="margin-left: 200px;"> <tr><td>APID:</td><td>16</td></tr> <tr><td>Type:</td><td>5</td></tr> <tr><td>Subtype:</td><td>1</td></tr> <tr><td>PI1:</td><td>28931</td></tr> <tr><td>PI2:</td><td>0</td></tr> </table>	APID:	16	Type:	5	Subtype:	1	PI1:	28931	PI2:	0	D_EvRp_188	
APID:	16													
Type:	5													
Subtype:	1													
PI1:	28931													
PI2:	0													
		Verify Packet Reception CdmuAsw Event 5-1 M2 Decontamination Heating OFF Herschel Packet Details: <table style="margin-left: 200px;"> <tr><td>APID:</td><td>16</td></tr> <tr><td>Type:</td><td>5</td></tr> <tr><td>Subtype:</td><td>1</td></tr> <tr><td>PI1:</td><td>28932</td></tr> <tr><td>PI2:</td><td>0</td></tr> </table>	APID:	16	Type:	5	Subtype:	1	PI1:	28932	PI2:	0	D_EvRp_189	
APID:	16													
Type:	5													
Subtype:	1													
PI1:	28932													
PI2:	0													
13		Update heater mask and increase decontamination thresholds of 1° [40,5°C/41,5°C]		Next Step: 14										

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECl.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Execute Telecommand  <b>Decont - Tresholds</b>  <i>Command Parameter(s) :</i> Decont - M1 - TMIN            ZHB06999            40.5 degC Decont - M1 - TMAX            ZHB07999            41.5 degC Decont - M2 - TMIN            ZHB08999            40.5 degC Decont - M2 - TMAX            ZHB09999            41.5 degC Decont - Cont Check            ZHB10999            0.5 degC (Def)  <i>TC Control Flags :</i>  GBM IL DSE --Y -- --  <i>Subsch. ID : 10</i> Det. descr. : TC(8,4,113,1) to update the tresholds - TMIN - TMAX - Cont check	ZCB04999	
13.1		Report decontamination heating parameters		<input type="checkbox"/>
		Execute Procedure: <b>H_LEO_SYS_DECS</b> <b>Decontamination Heating Status Report</b>		
14		Wait for temperature stabilisation		Next Step: 15
		<b>Wait until the median temperature on M1 and M2 oscillate between the selected thresholds [40,5°C/41,5°C]</b>		
		Verify M1 median temperature Telemetry DhM1Temp            DE800171	>= 40.5 <dec> <= 41.5 <dec>	AND=ZAZ9J999
		Verify M2 median temperature Telemetry DhM2Temp            DE801171	>= 40.5 <dec> <= 41.5 <dec>	AND=ZAZ9J999
		<b>Verify reception of TM packets:</b> <b>TM(5,1,113,1) -&gt; generated when M1 Heating is switch ON</b> <b>TM(5,1,113,2) -&gt; generated when M1 Heating is switch OFF</b> <b>TM(5,1,113,3) -&gt; generated when M2 Heating is switch ON</b> <b>TM(5,1,113,4) -&gt; generated when M2 Heating is switch OFF</b>		
		Verify Packet Reception <b>CdmuAsw Event 5-1 M1 Decontamination Heating ON</b> <b>Herschel</b> <i>Packet Details:</i>  APID:            16 Type:            5 Subtype:        1 PI1:            28929 PI2:            0	D_EvRp_109	

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify Packet Reception <b>CdmuAsw Event 5-1 M1 Decontamination Heating OFF</b> <b>Herschel</b> Packet Details: <div style="text-align: right;">             APID: 16              Type: 5              Subtype: 1              PI1: 28930              PI2: 0           </div>	D_EvRp_187	
		Verify Packet Reception <b>CdmuAsw Event 5-1 M2 Decontamination Heating ON</b> <b>Herschel</b> Packet Details: <div style="text-align: right;">             APID: 16              Type: 5              Subtype: 1              PI1: 28931              PI2: 0           </div>	D_EvRp_188	
		Verify Packet Reception <b>CdmuAsw Event 5-1 M2 Decontamination Heating OFF</b> <b>Herschel</b> Packet Details: <div style="text-align: right;">             APID: 16              Type: 5              Subtype: 1              PI1: 28932              PI2: 0           </div>	D_EvRp_189	
15		<i>Increase decontamination thresholds of 1°</i> <i>[41,5°C/42.5°C]</i>		Next Step: 16
		Execute Telecommand <div style="text-align: right;"><b>Decont - Tresholds</b></div> Command Parameter(s) : <div style="text-align: right;">             Decont - M1 - TMIN      ZHB06999      41.5 degC              Decont - M1 - TMAX      ZHB07999      42.5 degC              Decont - M2 - TMIN      ZHB08999      41.5 degC              Decont - M2 - TMAX      ZHB09999      42.5 degC              Decont - Cont Check      ZHB10999      0.5 degC (Def)           </div> TC Control Flags : <div style="text-align: right;">             GBM IL DSE              --Y -- --           </div> Subsch. ID : 10 Det. descr. : TC(8,4,113,1) to update the tresholds - TMIN - TMAX - Cont check	ZCB04999	
15.1		<i>Report decontamination heating parameters</i>		<input type="checkbox"/>
		Execute Procedure: <b>H_LEO_SYS_DECS</b> <b>Decontamination Heating Status Report</b>		

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
16		Wait for temperature stabilisation		Next Step: 17
		<b>Wait until the median temperature on M1 and M2 oscillate between the selected thresholds [41,5°C/42,5°C]</b>		
		Verify M1 median temperature Telemetry DhM1Temp DE800171	>= 41.5 <dec> <= 42.5 <dec>	AND=ZAZ9J999
		Verify M2 median temperature Telemetry DhM2Temp DE801171	>= 41.5 <dec> <= 42.5 <dec>	AND=ZAZ9J999
		<b>Verify reception of TM packets:            TM(5,1,113,1) -&gt; generated when M1 Heating is switch ON            TM(5,1,113,2) -&gt; generated when M1 Heating is switch OFF            TM(5,1,113,3) -&gt; generated when M2 Heating is switch ON            TM(5,1,113,4) -&gt; generated when M2 Heating is switch OFF</b>		
		Verify Packet Reception CdmuAsw Event 5-1 M1 Decontamination Heating ON Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28929 PI2: 0	D_EvRp_109	
		Verify Packet Reception CdmuAsw Event 5-1 M1 Decontamination Heating OFF Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28930 PI2: 0	D_EvRp_187	
		Verify Packet Reception CdmuAsw Event 5-1 M2 Decontamination Heating ON Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28931 PI2: 0	D_EvRp_188	
		Verify Packet Reception CdmuAsw Event 5-1 M2 Decontamination Heating OFF Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28932 PI2: 0	D_EvRp_189	



Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
17		Increase decontamination thresholds of 1° [42,5°C/43,5°C]		Next Step: 18
		Execute Telecommand  Decont - Tresholds  Command Parameter(s) : Decont - M1 - TMIN           ZHB06999     42.5 degC (Def) Decont - M1 - TMAX           ZHB07999     43.5 degC Decont - M2 - TMIN           ZHB08999     42.5 degC (Def) Decont - M2 - TMAX           ZHB09999     43.5 degC Decont - Cont Check          ZHB10999     0.5 degC (Def)  TC Control Flags : GBM IL DSE --Y -- ---  Subsch. ID : 10 Det. descr. : TC(8,4,113,1) to update the tresholds - TMIN - TMAX - Cont check	ZCB04999	
17.1		Report decontamination heating parameters		<input type="checkbox"/>
		Execute Procedure: H_LEO_SYS_DECS Decontamination Heating Status Report		
18		Wait for temperature stabilisation		Next Step: 19
		<b>Wait until the median temperature on M1 and M2 oscillate between the selected thresholds [42,5°C/43,5°C]</b>		
		Verify M1 median temperature Telemetry DhM1Temp           DE800171	>= 42.5 <dec> <= 43.5 <dec>	AND=ZAZ9J999
		Verify M2 median temperature Telemetry DhM2Temp           DE801171	>= 42.5 <dec> <= 43.5 <dec>	AND=ZAZ9J999
		Verify reception of TM packets: TM(5,1,113,1) -> generated when M1 Heating is switch ON TM(5,1,113,2) -> generated when M1 Heating is switch OFF TM(5,1,113,3) -> generated when M2 Heating is switch ON TM(5,1,113,4) -> generated when M2 Heating is switch OFF		

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch																	
		Verify Packet Reception <b>CdmuAsw Event 5-1 M1 Decontamination Heating ON</b> <b>Herschel</b> Packet Details: <table style="margin-left: 200px;"> <tr><td>APID:</td><td>16</td></tr> <tr><td>Type:</td><td>5</td></tr> <tr><td>Subtype:</td><td>1</td></tr> <tr><td>PI1:</td><td>28929</td></tr> <tr><td>PI2:</td><td>0</td></tr> </table>	APID:	16	Type:	5	Subtype:	1	PI1:	28929	PI2:	0	D_EvRp_109								
APID:	16																				
Type:	5																				
Subtype:	1																				
PI1:	28929																				
PI2:	0																				
		Verify Packet Reception <b>CdmuAsw Event 5-1 M1 Decontamination Heating OFF</b> <b>Herschel</b> Packet Details: <table style="margin-left: 200px;"> <tr><td>APID:</td><td>16</td></tr> <tr><td>Type:</td><td>5</td></tr> <tr><td>Subtype:</td><td>1</td></tr> <tr><td>PI1:</td><td>28930</td></tr> <tr><td>PI2:</td><td>0</td></tr> </table>	APID:	16	Type:	5	Subtype:	1	PI1:	28930	PI2:	0	D_EvRp_187								
APID:	16																				
Type:	5																				
Subtype:	1																				
PI1:	28930																				
PI2:	0																				
		Verify Packet Reception <b>CdmuAsw Event 5-1 M2 Decontamination Heating ON</b> <b>Herschel</b> Packet Details: <table style="margin-left: 200px;"> <tr><td>APID:</td><td>16</td></tr> <tr><td>Type:</td><td>5</td></tr> <tr><td>Subtype:</td><td>1</td></tr> <tr><td>PI1:</td><td>28931</td></tr> <tr><td>PI2:</td><td>0</td></tr> </table>	APID:	16	Type:	5	Subtype:	1	PI1:	28931	PI2:	0	D_EvRp_188								
APID:	16																				
Type:	5																				
Subtype:	1																				
PI1:	28931																				
PI2:	0																				
		Verify Packet Reception <b>CdmuAsw Event 5-1 M2 Decontamination Heating OFF</b> <b>Herschel</b> Packet Details: <table style="margin-left: 200px;"> <tr><td>APID:</td><td>16</td></tr> <tr><td>Type:</td><td>5</td></tr> <tr><td>Subtype:</td><td>1</td></tr> <tr><td>PI1:</td><td>28932</td></tr> <tr><td>PI2:</td><td>0</td></tr> </table>	APID:	16	Type:	5	Subtype:	1	PI1:	28932	PI2:	0	D_EvRp_189								
APID:	16																				
Type:	5																				
Subtype:	1																				
PI1:	28932																				
PI2:	0																				
19		Increase decontamination thresholds of 1° [43,5°C/44,5°C]		Next Step: 20																	
		Execute Telecommand <div style="text-align: right;"><b>Decont - Tresholds</b></div> Command Parameter(s) : <table style="margin-left: 100px;"> <tr><td>Decont - M1 - TMIN</td><td>ZHB06999</td><td>43.5 degC</td></tr> <tr><td>Decont - M1 - TMAX</td><td>ZHB07999</td><td>44.5 degC</td></tr> <tr><td>Decont - M2 - TMIN</td><td>ZHB08999</td><td>43.5 degC</td></tr> <tr><td>Decont - M2 - TMAX</td><td>ZHB09999</td><td>44.5 degC</td></tr> <tr><td>Decont - Cont Check</td><td>ZHB10999</td><td>0.5 degC (Def)</td></tr> </table> TC Control Flags : <table style="margin-left: 150px;"> <tr><td>GBM IL DSE</td></tr> <tr><td>--Y -- ---</td></tr> </table> Subsch. ID : 10 Det. descr. : TC(8,4,113,1) to update the tresholds - TMIN - TMAX - Cont check	Decont - M1 - TMIN	ZHB06999	43.5 degC	Decont - M1 - TMAX	ZHB07999	44.5 degC	Decont - M2 - TMIN	ZHB08999	43.5 degC	Decont - M2 - TMAX	ZHB09999	44.5 degC	Decont - Cont Check	ZHB10999	0.5 degC (Def)	GBM IL DSE	--Y -- ---	ZCB04999	
Decont - M1 - TMIN	ZHB06999	43.5 degC																			
Decont - M1 - TMAX	ZHB07999	44.5 degC																			
Decont - M2 - TMIN	ZHB08999	43.5 degC																			
Decont - M2 - TMAX	ZHB09999	44.5 degC																			
Decont - Cont Check	ZHB10999	0.5 degC (Def)																			
GBM IL DSE																					
--Y -- ---																					
19.1		Report decontamination heating parameters		□																	

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Execute Procedure: H_LEO_SYS_DECS Decontamination Heating Status Report		
20		Wait for temperature stabilisation		Next Step: 21
		<b>Wait until the median temperature on M1 and M2 oscillate between the selected thresholds [43,5°C/44,5°C]</b>		
		Verify M1 median temperature Telemetry DhM1Temp DE800171	>= 43.5 <dec> <= 44.5 <dec>	AND=ZAZ9J999
		Verify M2 median temperature Telemetry DhM2Temp DE801171	>= 43.5 <dec> <= 44.5 <dec>	AND=ZAZ9J999
		<b>Verify reception of TM packets:</b> TM(5,1,113,1) -> generated when M1 Heating is switch ON TM(5,1,113,2) -> generated when M1 Heating is switch OFF TM(5,1,113,3) -> generated when M2 Heating is switch ON TM(5,1,113,4) -> generated when M2 Heating is switch OFF		
		Verify Packet Reception CdmuAsw Event 5-1 M1 Decontamination Heating ON Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28929 PI2: 0	D_EvRp_109	
		Verify Packet Reception CdmuAsw Event 5-1 M1 Decontamination Heating OFF Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28930 PI2: 0	D_EvRp_187	
		Verify Packet Reception CdmuAsw Event 5-1 M2 Decontamination Heating ON Herschel Packet Details: APID: 16 Type: 5 Subtype: 1 PI1: 28931 PI2: 0	D_EvRp_188	

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify Packet Reception <b>CdmuAsw Event 5-1 M2 Decontamination Heating OFF</b> <b>Herschel</b> Packet Details: <div style="text-align: right; margin-right: 100px;"> <b>APID: 16</b>  <b>Type: 5</b>  <b>Subtype: 1</b>  <b>PI1: 28932</b>  <b>PI2: 0</b> </div>	D_EvRp_189	
21		<i>Start steady-state decontamination phase: switch ON            redundant lines on M1</i>		Next Step: 22
		<b>M1 heater line 9 (HPS 18 HCS 1 R)</b>		
21.1		<i>Switch ON HPS18</i>		☐
		Execute Telecommand <div style="text-align: right; margin-right: 100px;"><b>PcduswOnHps18</b></div> TC Control Flags : <div style="text-align: right; margin-right: 100px;"><b>GBM IL DSE</b> --Y -- ---</div> Subsch. ID : 10 Det. descr. : PCDU:TC(8,4,112,5) switch On HPS 18	DCC18170	
		Verify Telemetry <div style="text-align: center; margin: 0 auto;"> <b>GRP18_HPS_STS                      WMA2G565</b> </div>	= ON	AND=ZAZ9J999
21.2		<i>Set M1 Heater Mask to activate all M1 heater lines</i>		☐
		Execute Telecommand <div style="text-align: right; margin-right: 100px;"><b>Decont - Heater mask</b></div> Command Parameter(s) : <div style="margin-left: 20px;"> <b>Decont - M1 heater 7                      ZHB17999                      ACTIVE</b>  <b>Decont - M1 heater 6                      ZHB16999                      ACTIVE (Def)</b>  <b>Decont - M1 heater 5                      ZHB15999                      ACTIVE (Def)</b>  <b>Decont - M1 heater 4                      ZHB14999                      ACTIVE (Def)</b>  <b>Decont - M1 heater 3                      ZHB13999                      ACTIVE</b>  <b>Decont - M1 heater 2                      ZHB12999                      ACTIVE (Def)</b>  <b>Decont - M1 heater 1                      ZHB11999                      ACTIVE (Def)</b>  <b>Decont - M2 heater 2                      ZHB22999                      ACTIVE (Def)</b>  <b>Decont - M2 heater 1                      ZHB21999                      ACTIVE (Def)</b> </div> TC Control Flags : <div style="text-align: right; margin-right: 100px;"><b>GBM IL DSE</b> --Y -- ---</div> Subsch. ID : 10 Det. descr. : TC(8,4,113,1) to update the M1 and M2 active heaters	ZCB03999	
21.3		<i>Report decontamination heating parameters</i>		☐

Start Decontamination heating  
 File: H\_LEO\_SYS\_DECL.xls  
 Author: E. Picallo



Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Execute Procedure: H_LEO_SYS_DECS Decontamination Heating Status Report		
		<b>NOTE: once in steady-state phase, the decontamination power need will decrease from ~570W to ~290W. Thus, the constraints on ACMS mode to be Sun pointing and no RWLs commanding are not anymore applicable (i.e. ACMS can be set in SCM are RWL run-in can be activated).</b>		
22		Continue monitoring		Next Step: END
		<b>During decontamination, monitor the values of the involved thermistors and the median temperatures on M1 &amp; M2, which should be in the range [43,5°C/44,5°C]</b>  <b>The nominal thermistors used for temperature determination are:</b> <b>For M1 decontamination are TH A (T331), TH A' (T332), TH C (T335).</b>  <b>For M2 decontamination are TH X (T339), TH Y (T341), TH Z (T342).</b>		
22.1		Verify M1 Thermistors		<input type="checkbox"/>
		Verify on telescope; M1 THA ; T21-5 (A) PT1000_T331                      KD253302		AND=ZAZ9J999
		Verify on telescope; M1 THA'' ; T16-5 (B) PT1000_T332                      KD248303		AND=ZAZ9J999
		Verify on telescope; M1 THC ; T23-5 (A) PT1000_T335                      KD255302		AND=ZAZ9J999
22.2		Verify M2 Thermistors		<input type="checkbox"/>
		Verify on telescope; M2 THX ; T25-5 (A) PT1000_T339                      KD257302		AND=ZAZ9J999
		Verify on telescope; M2 THY ; T26-5 (A) PT1000_T341                      KD258302		AND=ZAZ9J999
		Verify on telescope; M2 THZ ; T30-5 (B) PT1000_T342                      KD262303		AND=ZAZ9J999
22.3		Verify median temperatures on M1 & M2		<input type="checkbox"/>

Start Decontamination heating File: H_LEO_SYS_DECL.xls Author: E. Picallo	 
---	--

Step No.	Time	Activity/Remarks	TC/TLM	Display/ Branch
		Verify M1 median temperature Telemetry <b>DhM1Temp</b> <b>DE800171</b>	>= 43.5 <dec> <= 44.5 <dec>	AND=ZAZ9J999
		Verify M2 median temperature Telemetry <b>DhM2Temp</b> <b>DE801171</b>	>= 43.5 <dec> <= 44.5 <dec>	AND=ZAZ9J999

<b>End of Procedure</b>
-------------------------